### DEPARTMENT OF VETERANS AFFAIRS



VA HEALTHCARE NETWORK UPSTATE NEW YORK
VA MEDICAL CENTER
800 IRVING AVENUE
SYRACUSE, NY 13210

# Project #528A7-12-706 REPLACE AND UPGRADE HVAC AHU'S AND HOT WATER STATIONS

PHASE 2
TASK 'B' - REPLACE AIR HANDLING UNITS
TAST 'D' – UPGRADE HOT WATER STATIONS

March 14, 2012

ALL VISITORS TO THE MEDICAL CENTER ARE REQUIRED TO HAVE APPROPRIATE VA SECURITY IDENTIFICATION. ALL VISITORS WITHOUT EXISTING VA ID ARE REQUIRED TO REPORT TO FIRST FLOOR LOBBY SECURITY WINDOW, TO SIGN IN AND RECEIVE A TEMPORARY VISITOR'S ID BADGE



## DEPARTMENT OF VETERANS AFFAIRS VHA MASTER SPECIFICATIONS TASK B – REPLACE AIR HANDLING UNITS TASK D - REPLACE HOT WATER STATIONS

#### TABLE OF CONTENTS Section 00 01 10

	DIVISION 00 - SPECIAL SECTIONS	PAGE
00 01 15	List of Drawing Chapte	1
00 01 15	List of Drawing Sheets Infection Control	7
00 72 01	Infection Control	<del>'</del>
	DIVISION 01 - GENERAL REQUIREMENTS	
01 00 00	General Requirements	16
01 04 50	Cutting and Patching	5
01 06 10	Safety & Health Regulations	8
01 09 00	Reference Standards	45
01 09 40	Definitions	2
01 33 23	Shop Drawings, Product Data, and Samples	3
01 74 19	Construction Waste Management	6
	DIVISION 02 – EXISTING CONDITIONS	
	DIVIDION 02 - EXISTING CONDITIONS	
02 41 00	Demolition	3
	DIVISION 05 – METALS	
05 50 00	Metal Fabrications	9
05 50 00	Wetai Fabrications	9
	DIVISION 07 – THERMAL AND MOISTURE PROTECTION	
07 84 00	Firestopping	2
07 92 00	Joint Sealants	7
	DIVISION 09 – FINISHES	
09 91 00	Painting	14
	DIVISION 23 – HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)	
23 05 11	Common Work Results for HVAC and Steam Generation	25
23 05 12	General Motor Requirements for HVAC and Steam Generation	3
22.05.44	Equipment	
23 05 41	Noise and Vibration Control for HVAC Piping and Equipment	5
23 05 93	Testing, Adjusting, and Balancing for HVAC	6
23 07 11	HVAC, Plumbing, and Boiler Plant Insulation	16
23 09 23	Direct-Digital Control System for HVAC	18
23 21 13	Hydronic Piping	12
23 21 23	Hydronic Pumps	2

23 22 13	Steam and Condensate Heating Piping	11
23 25 00	HVAC Water Treatment	4
23 31 00	HVAC Ducts and Casings	6
23 34 00	HVAC Fans	5
23 40 00	HVAC Air Cleaning Devices	5
23 57 00	Packaged Heat Transfer Stations	13
23 73 00	Indoor Central-Station Air-Handling Units	12
23 74 13	Packaged, Outdoor Central Station – Air Handling Units	11
23 82 16	Air Coils	3

	DIVISION 26 – ELECTRICAL	
26 05 11	Requirements for Electrical Installations	7
26 05 21	Low-Voltage Electrical Power Conductors and Cables (600 Volts and	5
	Below)	
26 05 26	Grounding and Bonding for Electrical Systems	4
26 05 33	Raceway and Boxes for Electrical Systems	7
26 27 26	Wiring Devices	3
26 29 11	Motor Starters	7
26 29 21	Disconnect Switches	3
	DIVISION 28 – ELECTRONIC SAFETY AND SECURITY	
28 31 00	Fire Detection and Alarm	7

---END---

VA-528A7-12-706 TABLE OF CONTENTS 00 01 10-2

#### SECTION 00 01 15 LIST OF DRAWING SHEETS

The drawings listed below accompanying this specification form a part of the contract.

#### <u>Drawing No.</u> <u>Title</u>

DRAWING NO.	TITLE	ASSOCIATED TASK
G-001	COVER SHEET	ALL
M-101	BLDG 16 AC-01 DUCTWORK AND PIPING PLANS	
M-102	AC-08 & AC-09 RENOVATION PLAN	
M-103	AC-25 & AC-26 REMOVALS PLAN	
M-104	AC-25 & AC-26 DUCTWORK PLAN	
M-105	AC-25 & AC-26 PIPING PLAN	
M-501	HVAC DETAILS	TASK
M-502	HVAC DETAILS	<u> </u>
M-601	SCHEDULES, SYMBOLS AND ABBREVIATIONS	
M-701	CONTROL SCHEMATICS	
E-101	BLDG 16 AC-01 ELECTRICAL PLAN	
E-102	AC-08 & AC-09 ELECTRICAL PLAN	
E-103	AC-25 & AC-25 ELECTRICAL PLAN	
E-601	SCHEDULES AND INFORMATION	
ME-101	PART PLANS – HW STATION HWS-301	
ME-101 ME-102	PART PLANS – HW STATION HWS-301 PART PLANS – HW STATION HWS-401	
ME-102	PART PLANS – HW STATION HWS-401	
ME—103	PART PLANS – HW STATION HWS-602	
ME-105	PART PLANS – HW STATION HWS-902	
ME-106	PART PLANS – HW STATION HWS-903	TASK
ME-107	PART PLANS – HW STATION HWS-904	<del>~~~~</del>
ME-501	DETAILS & SCHEMATICS	D
ME-601	HVAC SCHEDULES	
ME-602	ELECTRICAL SCHEDULES & NOTES	
ME-701	CONTROL SCHEMATICS	

- - - END - - -



## 00 72 01 INFECTION CONTROL

#### PART 1 - GENERAL

#### A. GENERAL INTENTION:

- The Contractor is solely responsible for the health and safety of their employees. The Contractor is also responsible to protect the health and safety of the VA Community (patients, staff, and visitors) from unwanted effects of construction.
- 2. The Contractor shall comply with Section 01 00 00 General Requirements, Paragraph 1.8, Infection Prevention Measures.
- 3. PRECAUTIONS:
  - a. The Contractor is responsible for taking precautions necessary to minimize infection control risk. Such precautions are defined in this section.
  - b. Each construction activity has been assigned an "Infection Control Precaution Class" (ICP Class), which is determined by:
    - 1) The type of construction work;
    - 2) The duration of construction work;
    - 3) The location of construction work; and
    - 4) The relative risk to the VA Community.
  - c. Each ICP Class lists separate precautions, which must be taken during construction and at the completion of construction. Such precautions are mandatory.
  - d. The VA Infection Control Practitioner (or designee) shall assign an ICP Class for any construction activity, which has not been assigned one.
  - e. When several construction activities occur simultaneously in the Project Area, the highest ICP Class for any one of the activities shall apply to all of the activities.
- 4. INFECTION CONTROL PLAN: Contractor shall establish and maintain an Infection Control Plan detailing project-specific measures to be taken. Prior to the start of work, Contractor shall submit this plan for review for compliance with this section in accordance with Section 01 33 23, Shop Drawings, Product Data, and Samples.

#### B. SUBMITTALS

- 1. All submittal shall be in accordance with Section 01 33 23, Shop Drawings, Product Data, and Samples.
- 2. Submit complete manufacturer's data and literature on all products.
- 3. Submit a complete Infection Control Plan, including:
  - a. Floor plan showing temporary construction, dust mats, exhausts fans, floor protection, and paths of travel (for construction personnel access, construction materials, and debris removal).
  - b. Sequence of operations
  - c. Description of Infection Control procedures

#### C. TESTING:

1. Any time that the Contractor is working within the existing building, Contractor shall perform smoke tests each day that there is ICP Class II, III, or IV construction activity.

- 2. Perform a minimum of one test, three times a day.
- Location and schedule for testing shall be as directed by COR. COR and Construction Superintendent shall be present for all tests.
- 4. Testing shall determine if there is a "positive" reading (air flow moving from work areas to occupied areas) when ICP Class II, III, or IV activities are being performed, until such activities are complete. If a positive reading is taken, Contractor shall immediately stop construction, correct the situation, and re-test. Construction may not resume until authorized by the COR.
- D. INFECTION CONTROL PRECAUTION CLASSES (ICP CLASS):
  - 1. Work required in each ICP Class shall be in accordance with the following table:

ICP Class	Work Required During Construction Period 1	Work Required Upon Completion of Project
		Completion of Project
Class I	<ol> <li>Execute work by methods to minimize raising dust from construction operations.</li> <li>Immediately replace a ceiling tile displaced for visual inspection.</li> </ol>	
Class II	1. During drilling, grinding, cutting, sanding, and other dust-producing operations, provide active means to minimize dust from dispersing into the atmosphere.  These shall consist of vacuum attachments to power tools, industrial strength ("Shop-Vac") vacuum cleaners, or maintaining negative air pressure within the work area utilizing HEPA-filter-equipped air filtration units.  2. Water mist work surfaces to control dust while cutting.  3. For activities within work area, provide temporary construction partitions and seal unused doors and voids at perimeter of work area with duct tape to seal work area from non-work area.  4. Place dust mat at entrances and exits of work area.  5. To prevent contamination of duct system, isolate HVAC system in work area by removing diffusers, grilles and flex duct, and capping ducts airtight.	1. Wipe work surfaces with disinfectant. 2. Contain construction waste before transport in tightly covered containers. 3. Wet mop and/or vacuum with HEPA-filtered vacuum before leaving work area. 4. Remove isolation of HVAC system in work area; reinstall removed portions of HVAC system.

ICP Class	Work Required During	Work Required Upon	
	Construction Period 1	Completion of Project	
	6. Remove construction waste daily.		
Class III	1. To prevent contamination of duct system, isolate HVAC system in work area by removing diffusers, grilles and flex duct, and capping ducts airtight.	1. Remove barrier materials carefully to minimize spreading of dirt and debris	
	2. For activities within work area, provide temporary construction partitions and seal unused doors and voids at perimeter of work area with duct tape to seal work area from non-work area. For activities outside of work area, provide temporary partitions and seal doors as noted above or implement control cube method (cart with plastic covering and sealed connection to work site with HEPA-filtered vacuum for vacuuming prior to exit) before	associated with construction.  2. Thoroughly vacuum work area with HEPA-filtered vacuums.  3. Wet mop area with disinfectant.  4. Remove isolation of HVAC system in work area; reinstall removed portions of HVAC system.  5. Do not remove precautions from	
	construction begins.  Maintain negative air pressure within work area utilizing HEPA-filter-equipped air filtration units.  Contain construction waste before transport in tightly covered containers. Remove waste daily.  Cover transport containers. Tape covering unless using a solid lid. Provide dust mat at entrances and exits of work area.	work area until project is inspected by at least one of the following: the VA Safety Department, Infection Control Department, the COR, or their designees.	

ICP Class	Work Required During Construction Period 1	Work Required Upon Completion of Project	
Class IV	<ol> <li>To prevent contamination of duct system, isolate HVAC system in work area by removing diffusers, grilles and flex duct, and capping ducts airtight.</li> <li>For activities within work area, provide temporary construction partitions and seal unused doors and voids at perimeter of work</li> </ol>	1. Remove barrier material carefully to minimize spreading of dirt and debris associated with construction. 2. Thoroughly vacuum work area with HEPA-	
	area with duct tape to seal work area from non-work area. For activities outside of work area, provide temporary partitions and seal doors as noted above or implement control cube method (cart with plastic covering and sealed connection to work site with HEPA-filtered vacuum for vacuuming prior to exit) before	filtered vacuums.  3. Wet mop area with disinfectant.  4. Remove isolation of HVAC system in work area; reinstall removed portions of HVAC system.  5. Do not remove precautions from	

ICP Class	Work Required During Construction Period 1	Work Required Upon Completion of Project
	construction begins.  3. Maintain negative air pressure within work area utilizing HEPA-filter-equipped air filtration units.	work area until project is inspected by at least one of the following: the VA Safety
	4. Seal holes at pipes, conduits, ducts, and punctures airtight.	Department, Infection Control
	5. Construct an air-tight vestibule and require all personnel to pass through this room so they can be vacuumed using a HEPA-filtered vacuum cleaner before leaving work area; or they can wear cloth or paper coveralls that are removed in the temporary vestibule each time they leave the work area.  6. Provide dust mat at entrances and exits of work area.  7. All personnel entering the work area are required to wear shoe covers. Shoe covers must be changed in the temporary vestibule	Department, the COR, or their designees.
	each time personnel exits the work area.  8. Contain construction waste before	
	transport in tightly covered containers. Remove waste daily.	
	9. Cover transport containers. Tape covering unless using a solid lid.	

E. LIST OF INFECTION CONTROL PRECAUTION CLASS (ICP CLASS) FOR EACH CONSTRUCTION ACTIVITY 1:

SECTION #	SECTION NAME	CLASS
Section 02 41 00,	Demolition	Class IV
Section 04 05 13,	Masonry Mortaring	Class II
Section 04 20 00,	Unit Masonry	Class II
Section 06 10 00,	Rough Carpentry	Class II
Section 06 20 00,	Finish Carpentry:	Class II
Section 07 21 13,	Thermal Insulation	Class II
Section 07 92 00,	Joint Sealants	Class I
Section 09 22 16,	Non-Structural Metal Framing	Class II
Section 09 24 00,	Portland Cement Plastering	Class II
Section 09 29 00,	Gypsum Board	Class III

Section 09 51	Acoustical Ceilings	Class II
00,		
Section 09 91 00,	Painting:	
a.	Sanding & Cleaning	Class IV
b.	Coating Application	Class I
Section 10 28 00,	Toilet Accessories	Class II
Section 22 05 11,	Common Work Results for Plumbing	Class I
Section 22 05 23,	General-Duty Valves for Plumbing Piping	Class I
Section 22 11 00,	Facility Water Distribution	Class I
Section 22 13 00,	Facility Sanitary Sewerage	Class I
Section 22 40 00,	Plumbing Fixtures	Class I
Section 22 63 01,	Medical Gas and Vacuum Systems	Class II
Section 23 05	Common Work Results for HVAC and Steam Generation	Class I
Section 23 05 92,	Pre-Balancing and Testing for HVAC	Class I
Section 23 05 93,	Testing, Adjusting, and Balancing for HVAC	Class I
Section 23 07	HVAC, Plumbing, and Boiler Plant Insulation	Class II
Section 23 09 23,	Direct-Digital Control System for HVAC	Class I
Section 23 21 13,	Hydronic Piping	Class I
Section 23 31 00,	HVAC Ducts and Casings	Class II
Section 23 37 00,	Air Outlets and Inlets	Class I
Section 26 05	Requirements for Electrical Installations	Class I
Section 26 05 21,	Low-Voltage Electrical Power Conductors and Cables (600 Volts and Below)	Class I
Section 26 05 26,	Grounding and Bonding for Electrical Systems	Class I
Section 26 05 33,	Raceway and Boxes for Electrical Systems	Class I
Section 26 27 26,	Wiring Devices	Class I
Section 26 51 00,	Interior Lighting	Class I
Section 27 05 11,	Requirements for Communications Installations	Class I
Section 27 05 26,	Grounding and Bonding for Communications Systems	Class I
Section 27 05 33,	Raceways and Boxes for Communications Systems	Class I

Section 27 10 00,	Structured Cabling	Class I
Section 27 11 00,	Communications Equipment Room Fittings	Class I
Section 27 15 00.	Communications Horizontal Cabling	Class I

#### Notes:

1. Precautions listed under "Work Required During Construction Period" are applicable 24 hours a day, 7 days a week, until each activity is complete.

#### PART 2 - PRODUCTS/DEFINITIONS

- A. Temporary construction materials shall be as shown in the drawings.
- B. DUST MATS: 36" x 36", disposable LDPE adhesive sheets that hold particulate matter on contact, 30 sheets/mat, mounted on manufacturer's 38" x 38" mat base. Lab Safety Supply Inc., Items 1631-5BC (4 tacky mats) and 60428BE (1 mat base), or approved equal. Lab Safety can be contacted at 1-800-356-0783 and at www.labsafety.com.
- C. HEPA (HIGH EFFICIENCY PARTICULATE AIR) FILTER: filters which, when properly installed in HVAC and vacuum systems, capture 95% of 0.3 microns, including pollen, mold spores, and dust particles.
- D. FLOOR MATS: 3' wide x 10' long and 3' wide x 16' long walk-off mats with nylon surface and nitrile backing as provided by Staub Textile Services (Contact Richard Markus @ 1-800-836-0803), or approved equal.
- E. NEGATIVE PRESSURE: Providing an appreciable flow of clean air from the occupied portion of the Medical Center into the work area through the use of HVAC systems, fans, and filters. Exhaust for the work area shall be 20% greater than intake.
- F. Transport containers (for transporting waste through the Medical Center): Plastic, 4-wheel carts, approximately 31" W. x 66"" long x 38" H., 1 CY/1000 lb. capacity, as manufactured by Rubbermaid, or approved equal. Provide manufacturer's solid plastic lids for ICP Class III and IV activities.

#### PART 3 - EXECUTION

- A. TEMPORARY CONSTRUCTION: Construct temporary partitions in accordance with the drawings.
- B. SEQUENCING & SCHEDULING:
  - Prior to starting construction activities within the existing building or open to the existing building, infection control precautions shall be implemented in the following order:

- a. Install negative air pressure/HEPA filter system (ICP Classes III & IV; Class II when provided).
- b. Isolate HVAC system (ICP Classes II, III, and IV).
- c. Construct temporary partitions and seal openings (ICP Classes II, III, and IV).
- d. Provide all other precautions.
- 2. At the completion of construction activities, infection control precautions shall be removed in the reverse order from which they were implemented (i.e., start with 1.d and end with 1.a).
- 3. When VA inspection is required prior to removing precautions (see ICP chart in Part I), notify COR at least 2 working days prior to inspection.
- C. DUST MATS: Provide a new, clean, sticky surface as required to eliminate tracking of dust from the work area to occupied areas; at a minimum, provide this new surface at the **beginning** of **each** work day and as directed by CO/COR to maintain clean areas within the occupied building. Install on floor on the occupied side of each door between construction areas and areas occupied by the VA.
- D. HEPA FILTERS: Install in accordance with manufacturer's recommendations as required to produce the specified performance. Change filters and provide pre-filters as necessary to maintain the specified performance.
- E. NEGATIVE PRESSURE: Operate fans and other equipment continuously (24 hours a day, 7 days a week) during construction, to ensure that negative pressure is maintained in the work area. Provide galvanized steel ductwork from fans/filters/ equipment, to the exterior. Provide temporary magnahelic gauges at each door between construction areas and areas occupied by the VA. Provide sensors on both sides of doors. Check readings of magnahelic gauge with COR a minimum of 4 times a day.
- F. RESTORATION: Remove all precautions after work is complete (See "B" above). Repair or replace any damage due to temporary precautions. Remove all dust, dirt, and debris prior to removing temporary partitions.

END OF SECTION 00 72 01



## SECTION 01 00 00 SYRACUSE GENERAL REQUIREMENTS

#### PART 1 - GENERAL

#### 1.1 GENERAL INTENTION

- A. Contractor shall completely prepare site for building operations, including demolition and removal, and furnish labor and materials and perform work for "Replace Air Handler Units" as required by drawings and specifications.
- B. Visits to the site by Bidders may be made only by appointment with the COR.
- C. Offices of IPD Engineering, as Architect-Engineers, will render certain technical services during construction. Such services shall be considered as advisory to the Government and shall not be construed as expressing or implying a contractual act of the Government without affirmations by Contracting Officer or his duly authorized representative.
- D. All employees of general contractor and subcontractors shall comply with VA security management program and obtain permission of the VA police, be identified by project and employer, and restricted from unauthorized access. Contractors will be provided with badges after providing proof of identification. Badges must be worn by all persons while on VA property.
- E. Prior to commencing work, general contractor shall provide proof that a OSHA certified "competent person" (CP) (29 CFR 1926.20(b)(2) will maintain a presence at the work site whenever the general or subcontractors are present.

#### F. Training:

- All employees of general contractor or subcontractors shall have the OSHA certified Construction Safety course and /or other relevant competency training, as determined by VA CP with input from the ICRA team.
- Submit training records of all such employees for approval before the start of work.

#### 1.2 STATEMENT OF BID ITEM(S): SEE SF 1442

#### 1.3 SPECIFICATIONS AND DRAWINGS FOR CONTRACTOR

A. AFTER AWARD OF CONTRACT, Contractor shall make additional sets of drawings and specifications at Contractor's expense, from the .pdf files furnished by Issuing Office.

#### 1.4 CONSTRUCTION SECURITY REQUIREMENETS

#### A. Security Plan:

1. The security plan defines both physical and administrative security procedures that will remain effective for the entire duration of the project.

> The General Contractor is responsible for assuring that all sub-contractors working on the project and their employees also comply with these regulations.

#### Security Procedures: В.

- General Contractor's employees shall not enter the project site without appropriate badge. They may also be subject to inspection of their personal effects when entering or leaving the project site.
- For working outside the "regular hours" as defined in the contract, The General Contractor shall give 3 days notice to the Contracting Officer so that security arrangements can be provided for the employees. This notice is separate from any notices required for utility shutdown described later in this section.
- No photography of VA premises is allowed without written 3. permission of the Contracting Officer. When photographs are permitted, Contractor shall ensure that no VA patients or employees are in the photographs.
- 4. VA reserves the right to close down or shut down the project site and order General Contractor's employees off the premises in the event of a national emergency. The General Contractor may return to the site only with the written approval of the Contracting Officer.

#### C. Key Control:

- The COR shall provide construction cores and keys to the Contractor for the purpose of securing temporary doors and permanent doors (prior to the installation of permanent cylinders).
- Motor Vehicle Restrictions D.
  - Parking for Contractor and Subcontractor employees is not provided. One parking space for the Contractor's on-site superintendent shall be made available at a place designated by the COR.
  - Use of the loading dock shall be coordinated with the COR. 2. No vehicle shall be left at the dock without the approval of the warehouse supervisor.

#### FIRE SAFETY 1.5

- Applicable Publications: Publications listed below form part of Α. this Article to extent referenced. Publications are referenced in text by basic designations only.
  - American Society for Testing and Materials (ASTM): E84-2008 Surface Burning Characteristics of Building Materials
  - 2. National Fire Protection Association (NFPA): 10-2006 Standard for Portable Fire Extinguishers 30-2007 Flammable and Combustible Liquids Code 51B-2003 Standard for Fire Prevention During Welding, Cutting and Other Hot Work National Electrical Code 70-2007 241-2004 Standard for Safeguarding Construction, Alteration, and Demolition Operations
  - Occupational Safety and Health Administration (OSHA): 29 CFR 1926 Safety and Health Regulations for Construction

В. Fire Safety Plan: Establish and maintain a fire protection program in accordance with 29 CFR 1926. Prior to start of work, prepare a plan detailing project-specific fire safety measures, including periodic status reports, and submit to Contracting Officer Technical Representative for review for compliance with contract requirements in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES. Prior to any worker for the contractor or subcontractors beginning work, they shall undergo a safety briefing provided by the general contractor's competent person per OSHA requirements. This briefing shall include information on the construction limits, VAMC safety guidelines, means of egress, break areas, work hours, locations of restrooms, use of VAMC equipment, etc. Documentation shall be provided to the COR that individuals have undergone contractor's safety briefing.

- C. Site and Building Access: Maintain free and unobstructed access to facility emergency services and for fire, police and other emergency response forces in accordance with NFPA 241.
- D. Separate temporary facilities, such as trailers, storage sheds, and dumpsters, from existing buildings and new construction by distances in accordance with NFPA 241. For small facilities with less than 6 m (20 feet) exposing overall length, separate by 3m (10 feet).
- Ε. Temporary Construction Partitions:
  - Install and maintain temporary construction partitions to provide fire-rated and smoke-tight separations between construction areas and adjoining areas. Construct partitions of 2 layers of 5/8" type 'x' fire-rated gypsum board on both sides of metal studs. Extend the partitions through suspended ceilings to floor slab deck or roof, unless noted otherwise. Seal joints and penetrations. At door openings, install Class B, 1 1/2 hour fire - rated solid core wood (or hollow metal) doors, hollow metal frames, and hardware (doors shall be self-closing).
  - Temporary construction partitions shall be 2-hour fire-2. rated partitions; provide temporary construction partitions as shown on drawings to maintain integrity of existing exit stair enclosures, exit passageways, fire-rated enclosures of hazardous areas, horizontal exits, smoke barriers, vertical shafts and openings enclosures.
  - 3. Close openings in smoke barriers and fire-rated construction to maintain fire ratings. Seal penetrations with listed through-penetration firestop materials in accordance with Section 07 84 00, FIRESTOPPING.
- Temporary Heating and Electrical: Install, use and maintain F. installations in accordance with 29 CFR 1926, NFPA 241 and NFPA
- Means of Egress: Do not block exiting for occupied buildings, including paths from exits to roads. Minimize disruptions and coordinate with COR.

Η. Egress Routes for Construction Workers: Maintain free and unobstructed egress. Inspect daily. Report findings and corrective actions weekly to COR.

- Fire Extinguishers: Provide and maintain extinguishers in I. construction areas and temporary storage areas in accordance with 29 CFR 1926, NFPA 241 and NFPA 10.
- Flammable and Combustible Liquids: Store, dispense and use liquids in accordance with 29 CFR 1926, NFPA 241 and NFPA 30.
- Κ. Existing Fire Protection: Do not impair automatic sprinklers, smoke and heat detection, and fire alarm systems, except for portions immediately under construction, and temporarily for connections. Provide fire watch for impairments more than 4 hours in a 24-hour period. Request interruptions in accordance with Article, OPERATIONS AND STORAGE AREAS, and coordinate with COR. All existing or temporary fire protection systems (fire alarms, sprinklers) located in construction areas shall be tested as coordinated with the medical center. Parameters for the testing and results of any tests performed shall be recorded, witnessed by the COR, and copies provided to the COR.
- L. Smoke Detectors: Prevent accidental operation. Remove temporary covers at end of work operations each day. Coordinate with COR.
- Μ. Hot Work: Perform and safeguard hot work operations in accordance with NFPA 241 and NFPA 51B. Coordinate with COR to obtain permits at least 24 hours in advance. Designate contractor's responsible project-site fire prevention program manager to permit hot work.
- Fire Hazard Prevention and Safety Inspections: Inspect entire Ν. construction areas weekly. Coordinate with, and report findings and corrective actions weekly to COR.
- Ο. Smoking: Smoking is prohibited on VA property
- Dispose of waste and debris in accordance with NFPA 241. Remove from buildings daily.
- Perform other construction, alteration and demolition operations in accordance with 29 CFR 1926.
- If required, submit documentation to the COR that personnel have R. been trained in the fire safety aspects of working in areas with impaired structural or compartmentalization features.

#### 1.6 OPERATIONS AND STORAGE AREAS

The Contractor shall confine all operations (including storage of Α. materials) on Government premises to areas authorized or approved by the Contracting Officer. The Contractor shall hold and save the Government, its officers and agents, free and harmless from liability of any nature occasioned by the Contractor's performance.

В. The Contractor shall, under regulations prescribed by the Contracting Officer, use only established roadways. When materials are transported in prosecuting the work, vehicles shall not be loaded beyond the loading capacity recommended by the manufacturer of the vehicle or prescribed by any Federal, State, or local law or regulation. When it is necessary to cross curbs or sidewalks, the Contractor shall protect them from damage. The Contractor shall repair or pay for the repair of any damaged curbs, sidewalks, or roads.

- Working space and space available for storing materials shall be as determined by the COR
- Workmen are subject to rules of Medical Center applicable to D. their conduct.
- Ε. Execute work so as to interfere as little as possible with normal functioning of Medical Center as a whole, including operations of utility services, fire protection systems and any existing equipment, and with work being done by others.
- Building will be occupied during performance of work; but F. immediate areas of alterations will be vacated.
  - Contractor shall take all measures and provide all material necessary for protecting existing equipment and property in affected areas of construction against dust and debris, so that equipment and affected areas to be used in the Medical Centers operations will not be hindered. Contractor shall permit access to Department of Veterans Affairs personnel and patients through other construction areas which serve as routes of access to such affected areas and equipment. Coordinate alteration work in areas occupied by Department of Veterans Affairs so that Medical Center operations will continue during the construction period.
  - Immediate areas of alterations not mentioned in preceding 2. Subparagraph 1 will be temporarily vacated while alterations are performed.
- When the project area is turned over to Contractor, Contractor shall accept entire responsibility therefore.
  - Contractor shall maintain a minimum temperature of 60 degrees F at all times.
  - 2.. Contractor shall maintain in operating condition existing fire protection and alarm equipment. In connection with fire alarm equipment, Contractor shall make arrangements for pre-inspection of site with COR.
- Η. Utilities Services: Maintain existing utility services for Medical Center at all times. Provide temporary facilities, labor, materials, equipment, connections, and utilities to assure uninterrupted services. Where necessary to cut existing water, steam, gases, sewer or air pipes, or conduits, wires, cables, etc. of utility services or of fire protection systems and communications systems (including telephone), they shall be cut and capped at suitable places where shown; or, in absence of such indication, where directed by COR.

> No utility service such as water, gas, steam, sewers or electricity, or fire protection systems and communications systems may be interrupted without prior approval of COR. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished, work on any energized circuits or equipment shall not commence without the COR prior knowledge and written approval. Refer to specification Sections 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS and 27 05 11 REQUIREMENTS FOR COMMUNICATIONS INSTALLATIONS for additional requirements.

- 2. Contractor shall submit a request to interrupt any such services to COR, in writing, 48 hours in advance of proposed interruption. Request shall state reason, date, exact time of, and approximate duration of such interruption.
- 3. Contractor will be advised (in writing) of approval of request, or of which other date and/or time such interruption will cause least inconvenience to operations of Medical Center. Interruption time approved by Medical Center may occur at other than Contractor's normal working hours.
- 4. Major interruptions of any system must be requested, in writing, at least 15 calendar days prior to the desired time and shall be performed as directed by the COR.
- In case of a contract construction emergency, service will be interrupted on approval of COR. Such approval will be confirmed in writing as soon as practical.

#### Τ. Abandoned Lines:

- All abandoned services (wires, cables, conduits, ducts, pipes, etc., including their hangers and supports) within the project area shall be removed completely.
- All such abandoned services which penetrate perimeter walls, floors, and slabs of the project shall be sealed, capped, or plugged.
- To minimize interference of construction activities with flow of J. Medical Center traffic, comply with the following:
  - Keep roads, walks and entrances to grounds, to parking, and to occupied areas of buildings clear of construction materials, debris and standing construction equipment and vehicles.
- Coordinate the work for this contract with other construction Κ. operations as directed by COR. This includes the scheduling of traffic and the use of roadways, as specified in Article, USE OF ROADWAYS.

#### 1.7 ALTERATIONS

Survey: Before any work is started, the Contractor shall make a Α. thorough survey with the COR of areas of buildings in which alterations occur and areas which are anticipated routes of access, and furnish a report, signed by both, to the Contracting Officer. This report shall list by rooms and spaces:

> 1. Existing condition and types of resilient flooring, doors, windows, walls and other surfaces not required to be altered throughout affected areas of building.

- 2. Existence and conditions of items such as plumbing fixtures and accessories, electrical fixtures, equipment, venetian blinds, shades, etc., required by drawings to be either reused or relocated, or both.
- 3. Shall note any discrepancies between drawings and existing conditions at site.
- 4. Shall designate areas for working space, materials storage and routes of access to areas within buildings where alterations occur and which have been agreed upon by Contractor and COR
- Any items required by drawings to be either reused or relocated В. or both, found during this survey to be nonexistent, or in opinion of COR, to be in such condition that their use is impossible or impractical, shall be furnished and/or replaced by Contractor with new items in accordance with specifications which will be furnished by Government. Provided the contract work is changed by reason of this subparagraph B, the contract will be modified accordingly, under provisions of clause entitled "DIFFERING SITE CONDITIONS" (FAR 52.236-2) and "CHANGES" (FAR 52.243-4 and VAAR 852.236-88) of GENERAL CONDITIONS.
- C. Re-Survey: Thirty days before expected partial or final inspection date, the Contractor and COR together shall make a thorough re-survey of the areas of buildings involved. They shall furnish a report on conditions then existing, of resilient flooring, doors, windows, walls and other surfaces as compared with conditions of same as noted in first condition survey report:
  - Re-survey report shall also list any damage caused by 1. Contractor to such flooring and other surfaces, despite protection measures; and, will form basis for determining extent of repair work required of Contractor to restore damage caused by Contractor's workmen in executing work of this contract.
- D. Protection: Provide the following protective measures:
  - Wherever existing roof surfaces are disturbed they shall be protected against water infiltration. In case of leaks, they shall be repaired immediately upon discovery.
  - 2. Temporary protection against damage for portions of existing structures and grounds where work is to be done, materials handled and equipment moved and/or relocated.
  - 3. Protection of interior of existing structures at all times, from damage, dust and weather inclemency. Wherever work is performed, floor surfaces that are to remain in place shall be adequately protected prior to starting work, and this protection shall be maintained intact until all work in the area is completed.

#### INFECTION PREVENTION MEASURES 1.8

Α. Implement the requirements of VAMC's Infection Control Risk Assessment (ICRA) team and Section ICRA Group may monitor dust

> in the vicinity of the construction work and require the Contractor to take corrective action immediately if the safe levels are exceeded.

- Establish and maintain a dust control program as part of the В. contractor's infection preventive measures in accordance with the guidelines provided by ICRA Group. Prior to start of work, prepare a plan detailing project-specific dust protection measures, including periodic status reports, and submit to Architect for review for compliance with contract requirements in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.
  - All personnel involved in the construction or renovation 1. activity shall be educated and trained in infection prevention measures established by the medical center.
- C. Medical center Infection Control personnel shall monitor for airborne disease (e.g. aspergillosis) as appropriate during construction. A baseline of conditions may be established by the medical center prior to the start of work and periodically during the construction stage to determine impact of construction activities on indoor air quality. In addition:
  - The COR and VAMC Infection Control personnel shall review pressure differential monitoring documentation to verify that pressure differentials in the construction zone and in the patient-care rooms are appropriate for their settings. The requirement for negative air pressure in the construction zone shall depend on the location and type of activity. Upon notification, the contractor shall implement corrective measures to restore proper pressure differentials as needed.
  - In case of any problem, the medical center, along with 2. . assistance from the contractor, shall conduct an environmental assessment to find and eliminate the source.
- In general, following preventive measures shall be adopted during construction to keep down dust and prevent mold.
  - Dampen debris to keep down dust and provide temporary construction partitions in existing structures where directed by COR. Blank off ducts and diffusers to prevent circulation of dust into occupied areas during construction.
  - 2. Do not perform dust producing tasks within occupied areas without the approval of the COR. For construction in any areas that will remain jointly occupied by the medical Center and Contractor's workers, the Contractor shall.
    - Provide dust proof two-hour fire-rated temporary drywall construction barriers to completely separate construction from the operational areas of the hospital in order to contain dirt debris and dust. Barriers shall be sealed and made presentable (tape, bed, sand, and paint) on hospital occupied side. Install a self-closing rated door in a metal frame, commensurate with the partition, to allow worker access. Maintain negative air at all times. A fire retardant polyethylene, 6-mil thick or greater plastic barrier meeting local fire codes may be used

> where dust control is the only hazard, and an agreement is reached with the COR and Medical Center. HEPA filtration is required where the exhaust dust b. may reenter the breathing zone. Contractor shall verify that construction exhaust to exterior is not reintroduced to the medical center through intake vents, or building openings. Install HEPA (High Efficiency Particulate Accumulator) filter vacuum system rated at 95% capture of 0.3 microns including pollen, mold spores and dust particles. Insure continuous negative air pressures occurring within the work area. HEPA filters should have ASHRAE 85 or other prefilter to extend the useful life of the HEPA. Provide both primary and secondary filtrations units. Exhaust hoses shall be heavy duty, flexible steel reinforced and exhausted so that dust is not reintroduced to the medical center.

- Adhesive Walk-off/Carpet Walk-off Mats, minimum (36" c.  $\times$  36"), shall be used at all interior transitions from the construction area to occupied medical center area. These mats shall be changed as often as required to maintain clean work areas directly outside construction area at all times.
- d. Vacuum and wet mop all transition areas from construction to the occupied medical center at the end of each workday. Vacuum shall utilize HEPA filtration. Maintain surrounding area frequently. Remove debris as they are created. Transport these outside the construction area in containers with tightly fitting lids.
- The contractor shall not haul debris through patiente. care areas without prior approval of the COR. When approved, debris shall be hauled in enclosed dust proof containers or wrapped in plastic and sealed with duct tape. No sharp objects should be allowed to cut through the plastic. Wipe down the exterior of the containers with a damp rag to remove dust. All equipment, tools, material, etc. transported through occupied areas shall be made free from dust and moisture by vacuuming and wipe down.
- f. Using a HEPA vacuum, clean inside the barrier and vacuum ceiling tile prior to replacement. Any ceiling access panels opened for investigation beyond sealed areas shall be sealed immediately when unattended.
- There shall be no standing water during construction. This includes water in equipment drip pans and open containers within the construction areas. All accidental spills must be cleaned up and dried within 12 hours. Remove and dispose of porous materials that remain damp for more than 72 hours.
- At completion, remove construction barriers and ceiling protection carefully, outside of normal work hours. Vacuum and clean all surfaces free of dust after the removal.
- Ε. Final Cleanup:

> Upon completion of project, or as work progresses, remove 1. all construction debris from above ceiling, vertical shafts and utility chases that have been part of the construction.

- Perform HEPA vacuum cleaning of all surfaces in the 2. construction area. This includes walls, ceilings, cabinets, furniture (built-in or free standing), partitions, flooring, etc.
- All new air ducts shall be cleaned prior to final 3. inspection.

#### DISPOSAL AND RETENTION 1.9

- Materials and equipment accruing from work removed and from demolition of buildings or structures, or parts thereof, shall be disposed of as follows:
  - Reserved items which are to remain property of the Government are noted on drawings or in specifications as items to be stored. Items that remain property of the Government shall be removed or dislodged from present locations in such a manner as to prevent damage which would be detrimental to re-installation and reuse. Store such items where directed by COR.
  - 2. Items not reserved shall become property of the Contractor and be removed by Contractor from Medical Center.
  - Items of portable equipment and furnishings located in rooms and spaces in which work is to be done under this contract shall remain the property of the Government. When rooms and spaces are vacated by the Department of Veterans Affairs during the alteration period, such items which are NOT required by drawings and specifications to be either relocated or reused will be removed by the Government in advance of work to avoid interfering with Contractor's operation.

#### 1.10 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES, AND IMPROVEMENTS

The Contractor shall protect from damage all existing Α. improvements and utilities on the medical center property. The Contractor shall repair any damage to those facilities, resulting from failure to comply with the requirements of this contract or failure to exercise reasonable care in performing the work. If the Contractor fails or refuses to repair the damage promptly, the Contracting Officer may have the necessary work performed and charge the cost to the Contractor.

#### 1.11 RESTORATION

Remove, cut, alter, replace, patch and repair existing work as Α. necessary to install new work. Except as otherwise shown or specified, do not cut, alter or remove any structural work, and do not disturb any ducts, plumbing, steam, gas, or electric work without approval of the COR. Existing work to be altered or extended and that is found to be defective in any way, shall be reported to the COR before it is disturbed. Materials and workmanship used in restoring work, shall conform in type and

- quality to that of original existing construction, except as otherwise shown or specified.
- Upon completion of contract, deliver work complete and undamaged. В. Existing work (walls, ceilings, partitions, floors, mechanical and electrical work, lawns, paving, roads, walks, etc.) disturbed or removed as a result of performing required new work, shall be patched, repaired, reinstalled, or replaced with new work, and refinished and left in as good condition as existed before commencing work.
- At Contractor's own expense, Contractor shall immediately restore to service and repair any damage caused by Contractor's workmen to existing piping and conduits, wires, cables, etc., of utility services or of fire protection systems and communications systems (including telephone) which are indicated on drawings and which are not scheduled for discontinuance or abandonment.
- Expense of repairs to such utilities and systems not shown on D. drawings or locations of which are unknown will be covered by adjustment to contract time and price in accordance with clause entitled "CHANGES" (FAR 52.243-4 and VAAR 852.236-88) and "DIFFERING SITE CONDITIONS" (FAR 52.236-2) of GENERAL CONDITIONS.

#### 1.12 AS-BUILT DRAWINGS

- The contractor shall maintain two full size sets of as-built drawings which will be kept current during construction of the project, to include all contract changes, modifications and clarifications.
- В. All variations shall be shown in the same general detail as used in the contract drawings. To ensure compliance, as-built drawings shall be made available for the COR's review, as often as requested.
- C. Contractor shall deliver two approved completed sets of as-built drawings to the COR within 15 calendar days after each completed phase and after the acceptance of the project by the COR.
- Paragraphs A, B, & C shall also apply to all shop drawings.

#### 1.13 USE OF ROADWAYS

For hauling, use only established public roads and roads on Medical Center property. When necessary to cross curbing, sidewalks, or similar construction, they must be protected by well-constructed bridges.

#### 1.14 TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT

- Use of new installed mechanical and electrical equipment to Α. provide heat, ventilation, plumbing, light and power will be permitted subject to compliance with the following provisions:
  - Permission to use each unit or system must be given by COR. If the equipment is not installed and maintained in

- accordance with the following provisions, the COR will withdraw permission for use of the equipment.
- Electrical installations used by the equipment shall be 2. . completed in accordance with the drawings and specifications to prevent damage to the equipment and the electrical systems, i.e. transformers, relays, circuit breakers, fuses, conductors, motor controllers and their overload elements shall be properly sized, coordinated and adjusted. Voltage supplied to each item of equipment shall be verified to be correct and it shall be determined that motors are not overloaded. The electrical equipment shall be thoroughly cleaned before using it and again immediately before final inspection including vacuum cleaning and wiping clean interior and exterior surfaces.
- Units shall be properly lubricated, balanced, and aligned. 3. Vibrations must be eliminated.
- 4. Automatic temperature control systems for preheat coils shall function properly and all safety controls shall function to prevent coil freeze-up damage.
- 5. The air filtering system utilized shall be that which is designed for the system when complete, and all filter elements shall be replaced at completion of construction and prior to testing and balancing of system.
- 6. All components of heat production and distribution system, metering equipment, condensate returns, and other auxiliary facilities used in temporary service shall be cleaned prior to use; maintained to prevent corrosion internally and externally during use; and cleaned, maintained and inspected prior to acceptance by the Government. Boilers, pumps, feedwater heaters and auxiliary equipment must be operated as a complete system and be fully maintained by operating personnel. Boiler water must be given complete and continuous chemical treatment.
- Prior to final inspection, the equipment or parts used which show В. wear and tear beyond normal, shall be replaced with identical replacements, at no additional cost to the Government.
- C. This paragraph shall not reduce the requirements of the mechanical and electrical specifications sections.

#### 1.15 TEMPORARY USE OF EXISTING ELEVATORS

- Use of existing elevators for handling building materials and Α. Contractor's personnel will be permitted subject to following provisions:
  - Contractor makes all arrangements with the COR for use of elevators. The COR will ascertain that elevators are in proper condition. Contractor may use elevators Nos. 5 and 6 in Building No.1.
  - Contractor shall cover and provide maximum protection for the following elevator components:
    - Entrance jambs, heads soffits and threshold plates.
    - Entrance columns, canopy, return panels and inside b. surfaces of car enclosure walls.
    - c. Finish flooring.

#### 1.16 TEMPORARY TOILETS

Contractor may have, for use of Contractor's workmen, such toilet accommodations as may be assigned to Contractor by the COR. Contractor shall keep such places clean and be responsible for any damage done thereto by Contractor's workmen. Failure to maintain satisfactory condition in toilets will deprive Contractor of the privilege to use such toilets.

#### 1.17 AVAILABILITY AND USE OF UTILITY SERVICES

- The Government shall make all reasonably required amounts of Α. utilities available to the Contractor from existing outlets and supplies, as specified in the contract. The Contractor shall carefully conserve any utilities furnished without charge.
- The Contractor, at Contractor's expense and in a workmanlike manner satisfactory to the Contracting Officer, shall install and maintain all necessary temporary connections and distribution lines. Before final acceptance of the work by the Government, the Contractor shall remove all the temporary connections, distribution lines, and associated paraphernalia.
- C. The Contractor shall be supplied with utilities for this construction project as no cost to the Contractor, with the exception of those items listed in paragraph 1.17E.
- Heat: Furnish temporary heat necessary to prevent injury to work D. and materials through dampness and cold. Use of open salamanders or any temporary heating devices which may be fire hazards or may smoke and damage finished work, will not be permitted. Maintain minimum temperatures as specified for various materials.
- Ε. Electricity (for Construction and Testing): Furnish all temporary electric services.
  - Obtain electricity by connecting to the Medical Center electrical distribution system. The Contractor shall meter and pay for electricity required for electric cranes and hoisting devices, electrical welding devices and any electrical heating devices providing temporary heat. Electricity for all other uses is available at no cost to the Contractor.
- Water (for Construction and Testing): Furnish temporary water F. service.
  - Obtain water by connecting to the Medical Center water distribution system. Provide reduced pressure backflow preventer at each connection. Water is available at no cost to the Contractor.
  - 2. Maintain connections, pipe, fittings and fixtures and conserve water-use so none is wasted. Failure to stop leakage or other wastes will be cause for revocation (at COR's discretion) of use of water from Medical Center's system.

#### 1.18 TESTS

Pre-test mechanical and electrical equipment and systems and make Α. corrections required for proper operation of such systems before requesting final tests. Final test will not be conducted unless pre-tested.

- Conduct final tests required in various sections of В. specifications in presence of an authorized representative of the Contracting Officer. Contractor shall furnish all labor, materials, equipment, instruments, and forms, to conduct and record such tests.
- Mechanical and electrical systems shall be balanced, controlled C. and coordinated. A system is defined as the entire complex which must be coordinated to work together during normal operation to produce results for which the system is designed. For example, air conditioning supply air is only one part of entire system which provides comfort conditions for a building. Other related components are return air, exhaust air, steam, chilled water, refrigerant, hot water, controls and electricity, etc. Another example of a complex which involves several components of different disciplines is a boiler installation. Efficient and acceptable boiler operation depends upon the coordination and proper operation of fuel, combustion air, controls, steam, feedwater, condensate and other related components.
- All related components as defined above shall be functioning when D. any system component is tested. Tests shall be completed within a reasonably short period of time during which operating and environmental conditions remain reasonably constant.
- Individual test result of any component, where required, will only be accepted when submitted with the test results of related components and of the entire system.

#### INSTRUCTIONS

- Contractor shall furnish Maintenance and Operating manuals and verbal instructions when required by the various sections of the specifications and as hereinafter specified.
- Manuals: Maintenance and operating manuals (two copies each) for each separate piece of equipment shall be delivered to the COR coincidental with the delivery of the equipment to the job site. Manuals shall be complete, detailed guides for the maintenance and operation of equipment. They shall include complete information necessary for starting, adjusting, maintaining in continuous operation for long periods of time and dismantling and reassembling of the complete units and sub-assembly components. Manuals shall include an index covering all component parts clearly cross-referenced to diagrams and illustrations. Illustrations shall include "exploded" views showing and identifying each separate item. Emphasis shall be placed on the use of special tools and instruments. The function of each piece of equipment, component, accessory and control shall be clearly and thoroughly explained. All necessary precautions for the

> operation of the equipment and the reason for each precaution shall be clearly set forth. Manuals must reference the exact model, style and size of the piece of equipment and system being furnished. Manuals referencing equipment similar to but of a different model, style, and size than that furnished will not be accepted.

Instructions: Contractor shall provide qualified, factory-trained C. manufacturers' representatives to give detailed instructions to assigned Department of Veterans Affairs personnel in the operation and complete maintenance for each piece of equipment. All such training will be at the job site. These requirements are more specifically detailed in the various technical sections. Instructions for different items of equipment that are component parts of a complete system, shall be given in an integrated, progressive manner. All instructors for every piece of component equipment in a system shall be available until instructions for all items included in the system have been completed. This is to assure proper instruction in the operation of inter-related systems. All instruction periods shall be at such times as scheduled by the COR and shall be considered concluded only when the COR is satisfied in regard to complete and thorough coverage. The Department of Veterans Affairs reserves the right to request the removal of, and substitution for, any instructor who, in the opinion of the COR, does not demonstrate sufficient qualifications in accordance with requirements for instructors above.

#### 1.20 GOVERNMENT-FURNISHED PROPERTY

- The Government shall deliver to the Contractor, the Government-furnished property shown on the drawings.
- Equipment furnished by Government to be installed by Contractor В. will be furnished to Contractor at the Medical Center.
- C. Storage space for equipment will be provided by the Government and the Contractor shall be prepared to unload and store such equipment therein upon its receipt at the Medical Center.
- D. Notify Contracting Officer in writing, 60 days in advance, of date on which Contractor will be prepared to receive equipment furnished by Government. Arrangements will then be made by the Government for delivery of equipment.
  - Immediately upon delivery of equipment, Contractor shall arrange for a joint inspection thereof with a representative of the Government. At such time the Contractor shall acknowledge receipt of equipment described, make notations, and immediately furnish the Government representative with a written statement as to its condition or shortages.
  - 2. Contractor thereafter is responsible for such equipment until such time as acceptance of contract work is made by the Government.
- Equipment furnished by the Government will be delivered in a Ε. partially assembled (knock down) condition in accordance with

> existing standard commercial practices, complete with all fittings, fastenings, and appliances necessary for connections to respective services installed under contract. All fittings and appliances (i.e., couplings, ells, tees, nipples, piping, conduits, cables, and the like) necessary to make the connection between the Government furnished equipment item and the utility stub-up shall be furnished and installed by the contractor at no additional cost to the Government.

- Completely assemble and install the Government furnished F. equipment in place ready for proper operation in accordance with specifications and drawings.
- Furnish supervision of installation of equipment at construction G. site by qualified factory trained technicians regularly employed by the equipment manufacturer.

#### 1.21 RELOCATED ITEMS

- Contractor shall disconnect, dismantle as necessary, remove and reinstall in new location, all existing equipment and items indicated by symbol "R" or otherwise shown to be relocated by the Contractor.
- Perform relocation of such equipment or items at such times and in such a manner as directed by the COR.
- Suitably cap existing service lines, such as steam, condensate C. return, water, drain, gas, air, vacuum and/or electrical, whenever such lines are disconnected from equipment to be relocated. Remove abandoned lines in finished areas and cap as specified herein before under paragraph "Abandoned Lines".
- D. Provide all mechanical and electrical service connections, fittings, fastenings and any other materials necessary for assembly and installation of relocated equipment; and leave such equipment in proper operating condition.
- Ε. All service lines such as noted above for relocated equipment shall be in place at point of relocation ready for use before any existing equipment is disconnected. Make relocated existing equipment ready for operation or use immediately after reinstallation.

END OF SECTION 01 00 00

#### SECTION 01 04 50 CUTTING AND PATCHING

#### **PART 1 - GENERAL**

#### 1.1 DESCRIPTION

- A. Section includes:
  - 1. Information described under this section:

Definitions Coordination Submittals Performance

#### 1.2 **DEFINITIONS**

- A. "CUTTING AND PATCHING" includes cutting into existing construction to provide for the installation or performance of other work and subsequent fitting and patching required to restore surfaces to their original condition.
- B. "CUTTING AND PATCHING" is performed for coordination of the work, to uncover work for access or inspection, to obtain samples for testing, to permit alterations to be performed or for other similar purposes.
- C. "CUTTING AND PATCHING" performed during the manufacture of projects, or during the initial fabrication, erection or installation processes is not considered to be "cutting and patching" under this definition. Drilling of holes to install fasteners and similar operations are also not considered to be "cutting and patching".
- D. "REMOVALS," "DEMOLITION" and "SELECTIVE DEMOLITION" are recognized as related-but-separate categories of work, which may or may not require cutting and patching as defined in this section.

#### 1.3 SUBMITTALS

- A. PROCEDURAL PROPOSAL FOR CUTTING AND PATCHING:
  - 1. Submit (to the COR) the proposed procedures for cutting and patching at least 2 weeks prior to the timework will be performed.
  - 2. Include the following information, as applicable, in the submittal.
    - a. Describe nature of the work and how it is to be performed, indicating why cutting and patching cannot be avoided.
    - b. Describe anticipated results of the work in terms of changes to existing work, including structural, operational, and visual changes as well as other significant elements.
    - c. List products to be used and firms that will perform work.
    - d. Give dates when work is expected to be performed.
    - e. List utilities that will be disturbed or otherwise be affected by work, including those that will be relocated and those that will be out-of-service temporarily.
    - f. Indicate how long utility service will be disrupted. List utilities that will be disturbed or otherwise be affected by work, including those that will be relocated and those that will be out-of-service temporarily.
    - g. Indicate how long utility service will be disrupted.
    - h. Describe protection to existing plant, equipment, and products.

 Where cutting and patching of structural work involves the addition of reinforcement, submit details and engineering calculations to show how that reinforcement is integrated with original structure to satisfy requirements.

j. Approval by the COR to proceed with cutting and patching work does not waive the COR's right to later require complete removal and replacement of work found to be cut and patched in an unsatisfactory manner.

#### 1.4 QUALITY ASSURANCE

A. REQUIREMENTS FOR STRUCTURAL WORK: Do not cut and patch structural work without COR's review and written approval.

#### B. OPERATIONAL AND SAFETY LIMITATIONS:

- 1. Do not cut and patch operational elements of safety-related components in a manner that would result in a reduction of their capacity to perform in the manner intended, including energy performance, or that would result in increased maintenance, or decreased operational life or decreased safety.
- 2. Provide any or all of the following as required for specific work being undertaken:
  - a. Shoring, bracing, and sheeting.
  - b. Primary operational systems and equipment.
  - c. Water/moisture/vapor/air/smoke barriers, membranes and flashings.
  - d. Noise and vibration control elements and systems.
  - e. Control, communications, conveying, and electrical wiring systems.

#### C. VISUAL REQUIREMENTS:

- 1. Do not cut and patch work exposed on the building's exterior or in its occupied spaces, in a manner that would, in the COR's opinion, result in lessening the building's aesthetic qualities.
- 2. Do not cut and patchwork in a manner that would result in substantial visual evidence of cut and patch work.
- 3. Remove and replace work judged by the COR to be cut and patched in a visually unsatisfactory manner.
- D. If possible, retain the original installer or fabricator, or another recognized experienced and specialized firm to cut and patch exposed work.

#### 1.5 COORDINATION

- A. The mechanical and electrical subcontractors shall be responsible for the timely and accurate layout of their work.
- B. The General Contractor shall be responsible for all cutting operations of new and existing surfaces, including walls, floors, and ceilings as required for the proper completion of the work.
  - 1. Contractor shall provide appropriate firestopping to close openings around pipes, conduit, and other drilled openings.
  - 2. Any holes drilled incorrectly are to be patched by the contractor at the expense of the subcontractor responsible.
  - The Contractor shall fill all depressions in concrete slabs revealed after cutting operations.
- C. The contractor shall be responsible for all patching of areas of cutting. Patching shall be done in a manner to repair surfaces disturbed by cutting to their original condition.

#### **PART 2 - PRODUCTS**

#### 2.1 MATERIALS

#### A. General:

- 1. Except as otherwise indicated, or as directed by the COR, use materials for cutting and patching that are identical to existing materials.
- 2. If identical materials are not available, or cannot be used, use materials that match existing adjacent surfaces to the fullest extent possible with regard to visual effect.
- 3. Use materials for cutting and patching that will result in equal-or-better performance characteristics.

#### **PART 3 - EXECUTION**

#### 3.1 INSPECTION

A. Before the start of cutting work, meet at the work site with all parties involved in cutting and patching including mechanical and electrical trades.

Review areas of potential interference and conflict between the various trades.

Coordinate layout of the work and resolve potential conflicts before proceeding with the work.

#### 3.2 PREPARATION

A. TEMPORARY SUPPORT: To prevent failure provide temporary support of work to be cut.

#### B. PROTECTION:

- 1. Protect other work during cutting and patching to prevent damage.
- 2. Protect existing products, personnel, and equipment from harm and dust.
- 3. Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.

#### 3.3 PERFORMANCE

A. GENERAL: Employ skilled workers to perform cutting and patching work.

#### B. CUTTING:

- 1 Cut the work using methods that are least likely to damage work to be retained or adjoining work.
- 3. Where possible, review proposed procedures with the original installer; comply with original installer's recommendations.
- 4. By-pass utility services such as pipe and conduit, before cutting, where such utility services are shown or required to be removed, relocated or abandoned.
  - a. Cut off conduit and pipe in walls or partitions to be removed.
  - After by-pass and cutting, cap, valve or plug and seal tight remaining portion of pipe and conduit to prevent entrance of moisture or other foreign matter.

#### C. PATCHING:

- 1. Patch with seams which are durable and as invisible as possible.
- 2. Comply with specified tolerances for the work.

- Restore exposed finishes of patched areas and where necessary extend finish restoration into retained adjoining work in a manner which will eliminate evidence of patching and refinishing.
- b. Where removal of walls or partitions extends from one finished, area into another finished area, patch, and repair floor and wall surfaces in the new space to provide an even surface of uniform color and appearance.
- c. Where patch occurs in a smooth painted surface, extend final paint coat over entire unbroken surface containing patch, after patched area has received prime and base coat.
- d. Patch, repair, or rehang existing ceilings as necessary to provide an even plane surface of uniform appearance.

#### 3.4 CLEANING

- A. Thoroughly clean areas and spaces where work is performed or used as access to work.
- B. Remove completely paint, mortar, oils, putty and items of similar nature. Thoroughly clean piping, conduit, and similar features before painting of other finishing is applied.
- C. Restore damaged pipe covering to its original condition.

#### 3.5 MISCELLANEOUS ITEMS

- A. HOLES:
  - 1. Provide all holes and do all cutting for the work in a neat manner.
  - 2. Do not cut holes in structural steel without approval of the COR.
  - 3. Drill holes in masonry or concrete with tools that will not spall, crack, or otherwise damage the structure.
  - 4. Close all unused holes in an approved manner.
  - 5. Coordinate the work of subcontractors and other contractors in locating, verifying, and cutting all holes.

#### B. SLEEVES AND LINTELS:

- Provide pipe sleeves or lintels for all openings required in masonry walls and concrete slabs.
- 2. Size sleeves and/or openings to allow job-installed insulation to be place continuously through sleeve and/or opening.
- Provide all floor openings with pipe sleeves with 2" projection above finished floor.
- 4. Fabricate sleeves from black steel Schedule 40 pipe or as indicated on the drawings.
- 5. Fabricate lintels from structural steel shapes or as indicated on the drawings.

#### END OF SECTION 01 04 50

## SECTION 01 06 10 SAFETY & HEALTH REGULATIONS

#### PART 1 - OSHA, EPA, & NFPA REQUIREMENTS

1.1 All contractor and subcontractor personnel are responsible for compliance with applicable local, state and federal safety and health regulations, including those specifically incorporated into this Section.

#### 1.2 GENERAL

- A. Contractors are required to comply with the Occupational Safety and Health Act of 1970. This will include the safety and health standard found in CFR 1910 for general industry and 1926 for construction. Copies of those standards can be acquired from the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20420. Failure to comply with these standards may result in work stoppage and a request to the Area Director of OSHA for a Compliance Officer to inspect your work site.
- B. In addition, Contractor will be required to comply with other applicable Medical Center policies and safety regulations. These policies and regulations will be presented to the Contractor at the pre-construction meeting. Each of the Contractor's employees will be required to read the statement of policies and regulations and sign an acknowledgment that such policies and regulations are understood. Signed acknowledgment will be returned to the Contracting Officer.
- C. Contractors involved with the removal, alteration, or disturbance of asbestos type insulation or materials will be required to comply strictly with the regulations found in CFR 1910.1001 and the appropriate EPA regulations regarding disposal of asbestos. Assistance in identifying asbestos can be requested from the Medical Center's Industrial Hygienist and the COR.
- D. Contractors entering locations of asbestos contamination (i.e. pipe basements) shall be responsible for providing respiratory protection to their employees and ensuring respirators are worn in accordance with OSHA (CFR 1910.1001 (g)). Asbestos contaminated areas shall be defined on project drawings. The minimum equipment requirements will be a half-mask air-purifying respirator equipped with high efficiency filters and disposable coveralls.
- E. Contractor, along with other submittals, and at least two weeks prior to bringing any materials on-site, must submit a complete list of chemicals the Contractor will use and MSDS for all hazardous materials as defined in OSHA 1910.1200 (d) Hazard Determination. Contracting Officer shall have final approval of all materials brought on site.
- F. The contractor will be held solely responsible for the safety and health of their employees and protection of the work environment. The contractor will also be held responsible to protect the

health and safety of the VA Community (patients, staff, and visitors) from the unwanted effects of construction. VA staff will monitor the contractor's performance in complying with all safety and health aspects of the project. Severe or constant violations may result in an immediate work stoppage or request for a Compliance Officer from the Occupational Safety and Health Administration.

G. During all phases of demolition, construction and alterations, Contractors are required to understand and strictly follow the National Fire Protection Association (NFPA) 241 "Standard for Safeguarding Construction, Alteration and Demolition Operations". The Medical Center's Safety and Occupational Health Specialist and/or Industrial Hygienist will closely monitor the work area for compliance. Appropriate action will be taken for non-compliance.

#### PART 2 - SPECIFIC VA MEDICAL CENTER FIRE & SAFETY POLICIES, PROCEDURES

#### 2.1 INTRODUCTION

- A. The safety and fire protection of patients, employees, members of the public and government is one of continuous concern to this Medical Center.
- B. Contractors, their supervisors and employees are required to comply with Medical Center policies to ensure the occupational safety and health of all. Failure to comply may result in work stoppage.
- C. Contractors are to comply with the requirements found in NFPA #51B, "Fire Prevention During Welding, Cutting and Other Hot Work".
- D. Questions regarding occupational safety and health issues can be addressed to the COR. The Medical Center Safety and Occupational Health Specialist and/or Industrial Hygienist will advice the COR when requested.

#### 2.2 HAZARD COMMUNICATION

- A. Contractors shall comply with OSHA Standard 29 CFR 1926.59 "Hazard Communication".
- B. Copies of Material Safety Data Sheets covering all hazardous materials to be used by the contractor shall be submitted to the COR prior to bringing them on VA property.
- C. Contractors shall inform the COR of the hazards to which VA personnel and patients may be exposed.
- D. Contractors shall have a written Hazard Communication Program available at the construction site, which details how the Contractor will comply with 29 CFR 1926.59.

VA-528A7-12-706 REFERENCE STANDARDS 01 09 00-2

#### 2.3 FIRES

All fires must be reported. In the event of a fire in the work area, use the nearest pull box station and also notify Medical Center staff in the immediate area. Be sure to give the exact location from where you are calling and the nature of the emergency. If a Contractor experiences a fire that was rapidly extinguished by your staff, you still must notify the COR within an hour of the event such that an investigation of the fire can be accomplished.

# 2.4 FIRE ALARMS, SMOKE DETECTION AND SPRINKLER SYSTEM

If the nature of the work requires the deactivation of the fire alarm, smoke detection or sprinkler system, you must notify the COR. Notification must be made well in advance such that ample time can be allowed to deactivate the system and provide alternative measures for fire protection. Under no circumstance is a Contractor allowed to deactivate any of the fire protection systems in this Medical Center.

#### 2.5 SMOKE DETECTORS

False alarms will not be tolerated. The Contractor and workers are required to be familiar with the location of the smoke detectors in the work area. When performing cutting, burning or welding or any other operations that may cause smoke or dust, you must take steps to temporarily cover smoke detectors in order to prevent false alarms. Failure to take the appropriate action will result in the Contracting Officer assessing actual costs for government response for each false alarm that is preventable. Prior to covering the smoke detectors, the Contractor will notify the COR, who will also be notified when the covers are removed.

# 2.6 HOT WORK PERMIT

- A. Hot work is defined as operations including, but not limited to, cutting, welding, thermal welding, brazing, soldering, grinding, thermal spraying, thawing pipes, or any similar situation. If such work is required, the Contractor must notify the COR no less than one day in advance of such work.
- B. All hot work will be performed in compliance with the Medical Center's policy regarding Hot Work Permits and NFPA 241, Safeguarding Construction, Alternation, and Demolition Operations, and NFPA 51B, Fire Prevention in Use of Cutting and Welding Processes, and applicable OSHA standards. A hot work permit will only be issued to individuals familiar with these regulations.
- C. A hot work permit will only be issued when the following conditions are met:
  - Combustible materials are located a minimum of 25 feet from the work site, or protected by flameproof covers or shielded with metal or fire-resistant quards or curtains.
  - 2. Openings or cracks in walls, floors, or ducts within 25 feet of the site are covered to prevent the passage of sparks to adjacent areas.

3. Where cutting or welding is done near walls, partitions, ceiling, or roof of combustible construction, fire resistant guards or shields are provided to prevent ignition.

- 4. Cutting or welding on pipes or other metal in contact with combustible walls, ceilings or roofs is not undertaken if the work is close enough to cause ignition by conduction.
- 5. Fully charged and operable fire extinguishers, appropriate for the type of possible fire, are available at the work area.
- 6. When cutting or welding is done in close proximity to a sprinkler head, a wet rag is laid over the head during operation.
- 7. Assure that nearby personnel are protected against heat, sparks, cut off, etc.
- 8. Assure that a fire watch is at the site. Make a final check-up 30 minutes after completion of operations to detect and extinguish any smoldering fires.
- D. A fire watch shall be provided by the Contractor whenever cutting, welding, or performing other hot work. Fire watcher(s) shall:
  - Have fire-extinguishing equipment readily available and be trained in its use.
  - 2. Be familiar with facilities and procedures for sounding an alarm in the event of fire.
  - 3. Watch for fires in all exposed areas, sound the fire alarm immediately, and try to extinguish only within the capability of the portable extinguishing equipment available. In all cases if a fire is detected the alarm shall be activated even if the fire is extinguished.
  - 4. Maintain the watch for at least a half-hour after completion of operations to detect and extinguish smoldering fires.
- E. A "Hot Work Permit" will be issued only for the period necessary to perform such work. In the event the time necessary will exceed one day, a "Hot Work Permit" may be issued for the period needed; however, the COR will inspect the area daily. Hot work permit will apply only to the location identified on the permit. If additional areas involve hot work, then additional permits must be requested.
- F. Contractors will not be allowed to perform hot work processes without the appropriate permit.
- G. Any work involving the Medical Center's fire protection system will require 24 hour notification to the COR. Under no circumstances will the Contractor or employee attempt to alter or tamper with the existing fire protection system.
- H. The COR will be notified within 30 minutes of the completion of all hot work to perform an inspection of the area to confirm that sparks or drops of hot metal are not present.

#### 2.7 TEMPORARY ENCLOSURES

Only non-combustible materials will be used to construct temporary enclosures or barriers at this Medical Center. Plastic materials and fabrics used to construct dust barriers must conform to NFPA #701, Standard Methods of Fire Tests for Flame-Resistant Textiles and Films.

## 2.8 FLAMMABLE LIQUIDS

All flammable liquids will be kept in approved safety containers. Only the amount necessary for your immediate work will be allowed in the building. Flammable liquids must be removed from the building at the end of each day.

# 2.9 COMPRESSED GAS CYLINDERS

Compressed gas shall be secured in an upright position at all times. A suitable cylinder cart will be used to transport compressed gas cylinders. Only those compressed gas cylinders necessary for immediate work will be allowed in occupied buildings. All other compressed gas cylinders will be stored outside of buildings in a designated area. Contractor will comply with applicable standards compressed gas cylinders found in 29 CFR 1910 and 1926 (OSHA).

# 2.10 INTERNAL COMBUSTION ENGINE-POWERED EQUIPMENT

Equipment powered by an internal combustion engine such as saws, compressors, generators and etc. will not be used in an occupied building. Special consideration may be given for unoccupied buildings only if the OSHA and NFPA requirements have been met.

# 2.11 POWDER ACTIVATED TOOLS

The operator of powder activated tools must be trained and certified to use them. Powder activated tools will be kept in a secured manner at all times. When not in use, the tools will be locked up. When in use, the operator will have the tool under his immediate control.

# 2.12 TOOLS

- A. Under no circumstances are equipment, tools and other items of work to be left unattended for any reason. All tools, equipment and items of work must be under the immediate control of your employee.
- B. If for some reason a work area must be left unattended, then it will be required that tools and other equipment be placed in an appropriate box or container and locked. All tool boxes, containers or any other device used for the storage of tool and equipment, will be provided with a latch and padlock. All tool boxes, containers or any other device used for the storage of tools and equipment, will be locked at all times except for putting in and removing tools.
- C. All doors to work areas will be closed and locked when rooms are left unattended. Failure to comply with this directive will be considered a violation of VA Regulations 1.218 (b), "Failure to

comply with signs of a directive and restrictive nature posted for safety purposes," subject to a \$50.00 fine. Subsequent similar violations may result in both imposition of such a fine as well as the Contracting Officer taking action under the Contract's "Accident Prevention Clause" (FAR 52.236-13) to suspend all contract work until violations such may be satisfactorily resolved or under FAR 52.236-5 "Material and Workmanship Clause" to remove from the work site any personnel deemed by the Contracting Officer to be careless to the point of jeopardizing the welfare of Facility patients or staff.

- D. Report to the VA Police Department any tools or equipment that are missing.
- E. Tools and equipment found unattended will be confiscated and removed from the work area.

#### 2.13 LADDERS

It is required that ladders not be left unattended in an upright position. Ladders must be attended at all times or taken down and chained securely to a stationary object.

## 2.14 SCAFFOLDS

All scaffolds will be attended at all times. When not in use, an effective barricade (fence) will be erected around the scaffold to prevent use by unauthorized personnel. (Reference OSHA 1926. Subpart L)

# 2.15 EXCAVATIONS

The contractor shall comply with OSHA 1926 Subpart P. An OSHA "competent person" must be on site during the excavation. The contractor shall coordinate with the COR and utility companies prior to the excavation to identify underground utilities tanks etc. All excavations left unattended will be provided with a barricade suitable to prevent entry by unauthorized persons.

# 2.16 STORAGE

Make prior arrangements with the COR for the storage of building materials. Storage will not be allowed to accumulate in the Medical Center buildings.

# 2.17 TRASH AND DEBRIS

Remove all trash and debris from the work area on a daily basis. Trash and debris will not be allowed to accumulate inside or outside of the buildings. The Contractor is responsible for making arrangements for removal of trash from the Medical Center facility.

# 2.18 PROTECTION OF FLOORS

It may be necessary at times to take steps to protect floors from dirt, debris, paint, etc. A tarp or other protective covering may be used. However, the Contractor must maintain a certain amount of floor space

for the safe passage of pedestrian traffic. Common sense must be used in this matter.

#### 2.19 SIGNS

Signs must be placed at the entrance to work areas warning people of the work. Signs must be suitable for the condition of the work. Small pieces of paper with printing or writing are not acceptable. The VAMC Safety Officer can be consulted in this matter.

#### 2.20 ACCIDENTS AND INJURIES

Contractors must report all accidents and injuries involving your employees. The Contractor may use the VAMC Emergency Department for emergency care.

## 2.21 CONFINED SPACE ENTRY

- A. Contractor will be informed that the workplace contains permit required confined space and that permit space entry is allowed only through compliance with a permit space program meeting the requirements of 29 CFR 1910.146 and 1926.21 (b)(6).
- B. Contractor will be apprised of the elements including the hazards identified and the Medical Center's (last employer) experience with the space that makes the space in question a permit space.
- C. Contractor will be apprised of any precautions or procedures that the Medical Center has implemented for the protection of employees in or near permit space where Contractor personnel will be working.
- D. Medical Center and Contractor will coordinate entry operations when both Medical Center personnel and Contractor personnel will be working in or near permit spaces as required by 29 CFR 1910.146 (d)(ii) and 1926.21 (b)(6).
- E. Contractor will obtain any available information regarding permit space hazards and entry operation from the Medical Center.
- F. At the conclusion of the entry operations the Medical Center and Contractor will discuss any hazards confronted or created in permit spaces.
- G. The Contractor is responsible for complying with 29 CFR 1910.246 (d) through (g) and 1926.21 (b)(6). The Medical Center, upon request, will provide rescue and emergency services required by 29 CFR 1910.246 (k) and 1926.21 (b)(6).

PART 3 - INTERIM LIFE SAFETY MEASURES MATRIX

Existing		Interim Life Safety Measures													
Deficiencies/Conditions		A	В	С	D	E	F	G	Н	I	ſ	K	L	M	N
Code Deficiencies															
1. Patient room problem	door latching														

2.	Lacking a code complying				1				1	1		
۷.	barrier											
3.	Fire exit stairs discharge											
	improper											
4.	Excessive distance to exit											
5.	Lack of two remote exits											
6.	Nonconforming building											
	const											
7.	Vertical openings not											
	protected											
8.	Large openings in fire											
	barriers											
9.	Corridor walls open at top											
10.	Hazardous areas not											
	protected											
	ruction Related Issues											
11.	Blocking off an exit											
12.	Rerouting emergency room											
tr	raffic											
13.	Renovation of occupied											
fl	.oor											
14.	Replacing fire alarm											
	rstem											
15.	Installing sprinkler											
	rstem											
	Modifying smoke/fire											
	rriers											
17.												
	enance and Testing						1					
18.	Taking fire alarm system											
	f-line											
19.												
	f-line											
	20. Disconnecting alarm											
devices												

# Interim Life Safety Measures

- A. Ensuring egress
- B. Emergency forces access
- C. Emergency forces notification
- D. Ensuring operational life safety systems
- E. Temporary construction
- F. Additional fire fighting equipment
- G. Prohibiting smoking
- H. Controlling combustible loading
- I. Conducting 2 fire drills per shift in all areas
- J. Conducting 2 fire drills per shift in local area
- K. Increased hazard surveillance
- L. Compartmentation training of personnel
- M. Conducting organizational training on life safety
- N. Conducting additional training on incident response

END OF SECTION 01 06 10

# SECTION 01 09 00 REFERENCE STANDARDS

#### PART 1 - GENERAL

## 1.1 DESCRIPTION

This section specifies the availability and source of references and standards specified in the project manual under paragraphs APPLICABLE PUBLICATIONS and/or shown on the drawings.

1.2 AVAILABILITY OF SPECIFICATIONS LISTED IN THE GSA INDEX OF FEDERAL SPECIFICATIONS, STANDARDS AND COMMERCIAL ITEM DESCRIPTIONS FPMR PART 101-29

(FAR 52.211-1) (AUG 1998)

- A. The GSA Index of Federal Specifications, Standards and Commercial Item Descriptions, FPMR Part 101-29 and copies of specifications, standards, and commercial item descriptions cited in the solicitation may be obtained for a fee by submitting a request to GSA Federal Supply Service, Specifications Section, Suite 8100, 470 East L'Enfant Plaza, SW, Washington, DC 20407, Telephone (202) 619-8925, Facsimile (202) 619-8978.
- B. If the General Services Administration, Department of Agriculture, or Department of Veterans Affairs issued this solicitation, a single copy of specifications, standards, and commercial item descriptions cited in this solicitation may be obtained free of charge by submitting a request to the addressee in paragraph (a) of this provision. Additional copies will be issued for a fee.
- 1.3 AVAILABILITY FOR EXAMINATION OF SPECIFICATIONS NOT LISTED IN THE GSA INDEX OF FEDERAL SPECIFICATIONS, STANDARDS AND COMMERCIAL ITEM DESCRIPTIONS

(FAR 52.211-4) (JUN 1988)

The specifications and standards cited in this solicitation can be examined at the following location:

DEPARMENT OF VETERANS AFFAIRS

Office of Construction & Facilities Management

Facilities Quality Service (00CFM1A)

811 Vermont Avenue, NW - Room 462

Washington, DC 20420

Telephone Numbers: (202) 461-8217 or (202) 461-8292

Between 9:00 AM - 3:00 PM

1.4 AVAILABILITY OF SPECIFICATIONS NOT LISTED IN THE GSA INDEX OF FEDERAL SPECIFICATIONS, STANDARDS AND COMMERCIAL ITEM DESCRIPTIONS (FAR 52.211-3) (JUN 1988)

The specifications cited in this solicitation may be obtained from the associations or organizations listed below.

AA Aluminum Association Inc.

http://www.aluminum.org

AABC Associated Air Balance Council

http://www.aabchq.com

```
AAMA American Architectural Manufacturer's Association
      http://www.aamanet.org
AATCC American Association of Textile Chemists and Colorists
      http://www.aatcc.org
ACGIH American Conference of Governmental Industrial Hygienists
     http://www.acgih.org
ACI
     American Concrete Institute
     http://www.aci-int.net
ADC
     Air Diffusion Council
     http://flexibleduct.org
AGA American Gas Association
     http://www.aga.org
AGC Associated General Contractors of America
     http://www.agc.org
AGMA American Gear Manufacturers Association, Inc.
     http://www.agma.org
AHAM Association of Home Appliance Manufacturers
     http://www.aham.org
AISC American Institute of Steel Construction
     http://www.aisc.org
AISI American Iron and Steel Institute
     http://www.steel.org
AMCA Air Movement and Control Association, Inc.
     http://www.amca.org
ANSI American National Standards Institute, Inc.
      http://www.ansi.org
APA
     The Engineered Wood Association
      http://www.apawood.org
ARI
     Air-Conditioning and Refrigeration Institute
     http://www.ari.org
ASCE American Society of Civil Engineers
     http://www.asce.org
ASHRAE American Society of Heating, Refrigerating, and
     Air-Conditioning Engineers
     http://www.ashrae.org
ASME American Society of Mechanical Engineers
     http://www.asme.org
ASSE American Society of Sanitary Engineering
     http://www.asse-plumbing.org
ASTM American Society for Testing and Materials
     http://www.astm.org
AWI Architectural Woodwork Institute
     http://www.awinet.org
AWS American Welding Society
     http://www.aws.org
AWWA American Water Works Association
     http://www.awwa.org
BHMA Builders Hardware Manufacturers Association
     http://www.buildershardware.com
CAGI Compressed Air and Gas Institute
     http://www.cagi.org
CGA
     Compressed Gas Association, Inc.
      http://www.cganet.com
CISCA Ceilings and Interior Systems Construction Association
      http://www.cisca.org
CISPI Cast Iron Soil Pipe Institute
     http://www.cispi.org
```

```
CRA
      California Redwood Association
      http://www.calredwood.org
CRSI Concrete Reinforcing Steel Institute
     http://www.crsi.org
      Cooling Technology Institute
CTI
     http://www.cti.org
DHI
     Door and Hardware Institute
     http://www.dhi.org
EGSA Electrical Generating Systems Association
     http://www.egsa.org
     Edison Electric Institute
EEI
     http://www.eei.org
EPA
     Environmental Protection Agency
     http://www.epa.gov
ETL
     ETL Testing Laboratories, Inc.
     http://www.et1.com
FAA
     Federal Aviation Administration
     http://www.faa.gov
FCC
     Federal Communications Commission
      http://www.fcc.gov
FPS
     The Forest Products Society
      http://www.forestprod.org
GANA Glass Association of North America
      http://www.cssinfo.com/info/gana.html/
     Factory Mutual Insurance
      http://www.fmglobal.com
GΑ
      Gypsum Association
      http://www.gypsum.org
     General Services Administration
GSA
     http://www.gsa.gov
     Hydraulic Institute
HΙ
     http://www.pumps.org
HPVA Hardwood Plywood & Veneer Association
     http://www.hpva.org
ICBO International Conference of Building Officials
     http://www.icbo.org
ICEA Insulated Cable Engineers Association Inc.
     http://www.icea.net
ICAC Institute of Clean Air Companies
     http://www.icac.com
IEEE Institute of Electrical and Electronics Engineers
     http://www.ieee.org\
IPCEA Insulated Power Cable Engineers Association
    Manufacturers Standardization Society of the Valve and Fittings
MSS
      Industry Inc.
      http://www.mss-hq.com
NAAMM National Association of Architectural Metal Manufacturers
     http://www.naamm.org
NAPHCC Plumbing-Heating-Cooling Contractors Association
     http://www.phccweb.org.org
     National Bureau of Standards
      See - NIST
NBBPVI National Board of Boiler and Pressure Vessel Inspectors
      http://www.nationboard.org
NEC
      National Electric Code
      See - NFPA National Fire Protection Association
```

```
NEMA National Electrical Manufacturers Association
      http://www.nema.org
NFPA National Fire Protection Association
      http://www.nfpa.org
NHLA National Hardwood Lumber Association
     http://www.natlhardwood.org
NIH National Institute of Health
     http://www.nih.gov
NIST National Institute of Standards and Technology
     http://www.nist.gov
NLMA Northeastern Lumber Manufacturers Association, Inc.
     http://www.nelma.org
NPA National Particleboard Association
     18928 Premiere Court
     Gaithersburg, MD 20879
     (301) 670-0604
NSF
     National Sanitation Foundation
     http://www.nsf.org
NWWDA Window and Door Manufacturers Association
     http://www.nwwda.org
OSHA Occupational Safety and Health Administration
      Department of Labor
      http://www.osha.gov
PCA
     Portland Cement Association
      http://www.portcement.org
PPI
      The Plastic Pipe Institute
      http://www.plasticpipe.org
RFCI The Resilient Floor Covering Institute
      http://www.rfci.com
     Redwood Inspection Service
RIS
     See - CRA
RMA
    Rubber Manufacturers Association, Inc.
     http://www.rma.org
     Steel Door Institute
SDI
     http://www.steeldoor.org
IGMA Insulating Glass Manufacturers Alliance
     http://www.igmaonline.org
SMACNA Sheet Metal and Air-Conditioning Contractors
     National Association, Inc.
      http://www.smacna.org
SSPC The Society for Protective Coatings
     http://www.sspc.org
     Steel Tank Institute
STI
     http://www.steeltank.com
     Tile Council of America, Inc.
TCA
     http://www.tileusa.com
TEMA Tubular Exchange Manufacturers Association
     http://www.tema.org
UBC
      The Uniform Building Code
      See ICBO
      Underwriters' Laboratories Incorporated
UL
      http://www.ul.com
      Underwriters' Laboratories of Canada
ULC
      http://www.ulc.ca
WCLIB West Coast Lumber Inspection Bureau
      6980 SW Varns Road, P.O. Box 23145
```

Portland, OR 97223 (503) 639-0651

WRCLA Western Red Cedar Lumber Association P.O. Box 120786
New Brighton, MN 55112

(612) 633-4334

WWPA Western Wood Products Association

http://www.wwpa.org

END OF SECTION 01 09 00



# SECTION 01 09 40 DEFINITIONS

#### PART 1 - GENERAL

## 1.1 SUMMARY

- A. SECTION INCLUDES:
  - 1. Information described under this section:
    - a. Definition of terms
    - b. Format and interpretations

#### 1.2 DESCRIPTION

- A. This section defines certain terms used in the specifications and other documents and explains the following as used in the contract documents:
  - 1. Organization
    - a. Format
    - b. Use
    - c. Language
    - d. Conventions

#### 1.3 DEFINITIONS

- A. Certain terms used in the Contract Documents are defined in this article.
- B. Definitions contained in this section are not necessarily complete but are general for the work.
  - The term "Architect" and "Architect Engineer" refers to:
     IPD Engineering

One Webster's Landing Syracuse, NY, 13202, or their duly authorized representative.

- 2. INDICATED:
  - a. Shown on drawings by notes, graphics, or documents.
  - b. Terms such as "SHOWN", "NOTED", "SCHEDULED", and "SPECIFIED" have same meaning as "indicated" and are used to assist the reader in locating particular information
- 3. APPROVE:
  - a. Where used in conjunction with Architect's response to submittals, requests, applications, inquiries, reports and claims by Contractor, the meaning of term "approved" will be held to limitations of Architect's responsibilities and duties.
  - b. In no case will "approval" by Architect be interpreted as a release of Contractor from responsibilities to fulfill requirements of contract documents.
- 4. PROJECT AREA: Space available to contractor at location of project for performance of the work.
- 5. PRODUCT: Materials, equipment, and systems.
- 6. FURNISH: Supply and deliver to the job site, ready for unpacking, assembly, and installation as applicable in each instance, unless otherwise specified in greater detail.

7. INSTALL: Used to describe the following operations at the project site:

- a. Handling
- b. Storage
- c. Unpacking
- d. Assembly
- e. Erection
- f. Placing
- q. Anchoring
- h. Applying
- i. Connecting
- j. Working to dimension
- k. Finishing
- 1. Curing
- m. Protecting
- n. Cleaning
- o. Similar operations as applicable in each instance or unless otherwise specified in greater detail.
- 8. PROVIDE: Furnish and install, complete and ready for the intended use, as applicable in each instance or furnish labor and materials required for installation of.
- 9. INSTALLER:
  - a. The entity (person or firm) engaged by Contractor or its subcontractor or sub-subcontractor for performance of a particular unit of work at project site, including:
    - 1) Installation.
    - 2) Erection.
    - Application.
    - 4) Similar required operations.
  - b. It is a general requirement that such entities (Installers) be expert in operations they are engaged to perform.
- 10. "SUITABLE", "REASONABLE", "PROPER", "CORRECT" and "NECESSARY": Such terms shall mean as suitable, reasonable, proper, correct, or necessary for the purpose intended as required by the contract documents, subject to the judgment of the COR.
- 11. "INCLUDING", "SUCH AS": These terms shall always be taken in the most inclusive sense, namely, "including, but not limited to," and "such as, but not limited to".
- 12. "EXPOSED": Any item or surface, exterior or interior, which can be seen by a person outside the building, or a person inside any usable space within the building during normal activity.
- 13. "HEREIN" shall mean the contents of particular Section where this term appears.
- 14. "SECTION" shall mean one (1) of the portions of divisions of the Specifications.
- 15. "CONCEALED" where used in connection with painting of accessories, etc., shall mean that they are hidden from sight as in trenches, chases, furred spaces, pipe shafts or hung ceilings.

# END OF SECTION 01 09 40

VA-528A7-12-706 DEFINITIONS 01 09-40-2

# SECTION 01 33 23 SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES

# **PART 1 - GENERAL**

# 1.1 RELATED ARTICLES

A. Refer to Articles titled SPECIFICATIONS AND DRAWINGS FOR CONSTRUCTION (FAR 52.236-21) and, SPECIAL NOTES (VAAR 852.236-91), in GENERAL CONDITIONS.

# 1.2 GENERAL INFORMATION

- A. For the purposes of this contract, samples, test reports, certificates, and manufacturers' literature and data shall also be subject to the previously referenced requirements. The following text refers to all items collectively as SUBMITTALS.
- B. Submit for approval, all of the items specifically mentioned under the separate sections of the specification, with information sufficient to evidence full compliance with contract requirements. Materials, fabricated articles and the like to be installed in permanent work shall equal those of approved submittals. After an item has been approved, no change in brand or make will be permitted unless:
  - Satisfactory written evidence is presented to, and approved by Contracting Officer, that manufacturer cannot make scheduled delivery of approved item or;
  - 2. Item delivered has been rejected and substitution of a suitable item is an urgent necessity or;
  - 3. Other conditions become apparent which indicates approval of such substitute item to be in best interest of the Government.
- C. The Government reserves the right to require additional submittals, whether or not particularly mentioned in this contract. If additional submittals beyond those required by the contract are furnished pursuant to request therefore by Contracting Officer, adjustment in contract price and time will be made in accordance with Articles titled CHANGES (FAR 52.243-4) and CHANGES - SUPPLEMENT (VAAR 852.236-88) of the GENERAL CONDITIONS.
- D. Schedules called for in specifications and shown on shop drawings shall be submitted for use and information of Department of Veterans Affairs and Architect-Engineer. However, the Contractor shall assume responsibility for coordinating and verifying schedules.
- E. The COR and Architect-Engineer assumes no responsibility for checking schedules or layout drawings for exact sizes, exact numbers and detailed positioning of items.

#### 1.3 **SCHEDULE**

A. Forward submittals in sufficient time to permit proper consideration and approval action by Government. Time submission to assure adequate lead time for procurement of contract - required items. Delays attributable to untimely and rejected submittals will not serve as a basis for extending contract time for completion.

Contractor shall not begin work until all submittals have been В. returned marked "No exception taken" or "make corrections noted".

#### 1.4 **SUBMITTAL FORMAT**

- Submittals will receive consideration only when: Α.
  - Submittal is accompanied by a transmittal letter signed by Contractor. Except samples, all submittals shall be submitted electronically, in .pdf format, including the Submittal Cover Sheet, transmittal, and all attachments. Samples shall be sent via first class mail (or hand delivered).
  - Submittal is accompanied by a copy of the "Submittal Cover 2. Sheet" (included at the end of this section), fully executed and signed by the Contractor.
  - Manufacturer's data, information, and catalogs shall be marked to indicate specific items submitted for approval.
  - 4. Each submittal shall be labeled to indicate the name and location of the project, name of Contractor, manufacturer, contract number and ASTM or Federal Specification Number as applicable and location(s) on project.
  - 5. Required certificates shall be signed by an authorized representative of manufacturer or supplier of material, and by Contractor. Each drawing shall have marked thereon, proper descriptive title, including project name, contractor name, location, project number, manufacturer's name, reference to contract drawing number, detail Section Number, and Specification Section Number.
- в. Submittal drawings (shop, erection or setting drawings) and schedules, required for work of various trades, shall be checked before submission by technically qualified employees of Contractor for accuracy, completeness and compliance with contract requirements. These drawings and schedules shall be stamped and signed by Contractor certifying to such check.
- C. Coordination Drawing
  - The Contractor is responsible for preparing a coordination drawing, for the purposes of coordinating the ceilings, HVAC, plumbing, fire protection, electrical, communications, building structure. The Architect -Engineer will provide a base drawing (mylar and electronic format) for the Contractor and Subcontractors to show their prospective system on. This drawing shall be submitted to the Architect for approval.

#### 1.5 **PROCEDURE**

All submittals, including cover sheet and transmittal, shall be submitted electronically, in .pdf format, for approval to the Architect - Engineer with copies to the COR and CO.

- В. Submittals will be reviewed for compliance with contract requirements by Architect-Engineer, and action thereon will be taken by COR on behalf of the Contracting Officer.
- C. If a submittal has been disapproved, resubmit new submittal as soon as possible after notification of disapproval. Such new submittal shall be marked "Resubmittal" in addition to containing other previously specified information required on label and in transmittal letter.
- Approved samples will be kept on file by the Architect Engineer D. until completion of contract.
- Ε. Three originals of all color charts and samples shall be submitted for approval to:

**IPD** Engineering One Webster's Landing Syracuse, NY 13202 ATTN: Sam Gramet

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 33 23



# SECTION 01 74 19 CONSTRUCTION WASTE MANAGEMENT

## PART 1 - GENERAL

## 1.1 DESCRIPTION

- A. This section specifies the requirements for the management of non-hazardous building construction and demolition waste.
- B. Waste disposal in landfills shall be minimized to the greatest extent possible. Of the inevitable waste that is generated, as much of the waste material as economically feasible shall be salvaged, recycled or reused.
- C. Contractor shall use all reasonable means to divert construction and demolition waste from landfills and incinerators, and facilitate their salvage and recycle not limited to the following:
  - 1. Waste Management Plan development and implementation.
  - 2. Techniques to minimize waste generation.
  - 3. Sorting and separating of waste materials.
  - 4. Salvage of existing materials and items for reuse or resale.
  - 5. Recycling of materials that cannot be reused or sold.
- D. At a minimum the following waste categories shall be diverted from landfills:
  - 1. Inerts (eg, concrete, masonry and asphalt).
  - 2. Clean dimensional wood and palette wood.
  - 3. Engineered wood products (plywood, particle board and I-joists, etc).
  - 4. Metal products (eg, steel, wire, beverage containers, etc).
  - 5. Cardboard, paper and packaging.
  - 6. Plastics (eg, ABS, PVC).
  - 7. Carpet and/or pad.
  - 8. Gypsum board.
  - 9. Insulation.
  - 10. Paint.

# 1.2 RELATED WORK

- A. Section 02 41 00, DEMOLITION.
- B. Section 01 00 00, GENERAL REQUIREMENTS.

# 1.3 QUALITY ASSURANCE

- A. Contractor shall practice efficient waste management when sizing, cutting and installing building products. Processes shall be employed to ensure the generation of as little waste as possible. Construction /Demolition waste includes products of the following:
  - 1. Excess or unusable construction materials.
  - 2. Packaging used for construction products.

- 3. Poor planning and/or layout.
- 4. Construction error.
- 5. Over ordering.
- 6. Weather damage.
- 7. Contamination.
- 8. Mishandling.
- 9. Breakage.
- B. Establish and maintain the management of non-hazardous building construction and demolition waste set forth herein. Conduct a site assessment to estimate the types of materials that will be generated by demolition and construction.
- C. Contractor shall develop and implement procedures to reuse and recycle new materials to a minimum of 50 percent (by weight).
- D. Contractor shall be responsible for implementation of any special programs involving rebates or similar incentives related to recycling. Any revenues or savings obtained from salvage or recycling shall accrue to the Contractor.
- E. Contractor shall provide all demolition, removal and legal disposal of materials. Contractor shall ensure that facilities used for recycling, reuse and disposal shall be permitted for the intended use to the extent required by local, state, federal regulations. The Whole Building Design Guide website http://www.wbdg.org provides a Construction Waste Management Database that contains information on companies that haul, collect, and process recyclable debris from construction projects.
- F. Contractor shall assign a specific area to facilitate separation of materials for reuse, salvage, recycling, and return. Such areas are to be kept neat and clean and clearly marked in order to avoid contamination or mixing of materials.
- G. Contractor shall provide on-site instructions and supervision of separation, handling, salvaging, recycling, reuse and return methods to be used by all parties during waste generating stages.
- H. Record on daily reports any problems in complying with laws, regulations and ordinances with corrective action taken.

# 1.4 TERMINOLOGY

- A. Class III Landfill: A landfill that accepts non-hazardous resources such as household, commercial and industrial waste resulting from construction, remodeling, repair and demolition operations.
- B. Clean: Untreated and unpainted; uncontaminated with adhesives, oils, solvents, mastics and like products.

C. Construction and Demolition Waste: Includes all non-hazardous resources resulting from construction, remodeling, alterations, repair and demolition operations.

- D. Dismantle: The process of parting out a building in such a way as to preserve the usefulness of its materials and components.
- E. Disposal: Acceptance of solid wastes at a legally operating facility for the purpose of land filling (includes Class III landfills and inert fills).
- F. Inert Backfill Site: A location, other than inert fill or other disposal facility, to which inert materials are taken for the purpose of filling an excavation, shoring or other soil engineering operation.
- G. Inert Fill: A facility that can legally accept inert waste, such as asphalt and concrete exclusively for the purpose of disposal.
- H. Inert Solids/Inert Waste: Non-liquid solid resources including, but not limited to, soil and concrete that does not contain hazardous waste or soluble pollutants at concentrations in excess of water-quality objectives established by a regional water board, and does not contain significant quantities of decomposable solid resources.
- I. Mixed Debris: Loads that include commingled recyclable and non-recyclable materials generated at the construction site.
- J. Mixed Debris Recycling Facility: A solid resource processing facility that accepts loads of mixed construction and demolition debris for the purpose of recovering re-usable and recyclable materials and disposing non-recyclable materials.
- K. Permitted Waste Hauler: A company that holds a valid permit to collect and transport solid wastes from individuals or businesses for the purpose of recycling or disposal.
- L. Recycling: The process of sorting, cleansing, treating, and reconstituting materials for the purpose of using the altered form in the manufacture of a new product. Recycling does not include burning, incinerating or thermally destroying solid waste.
  - 1. On-site Recycling Materials that are sorted and processed on site for use in an altered state in the work, i.e. concrete crushed for use as a sub-base in paving.
  - 2. Off-site Recycling Materials hauled to a location and used in an altered form in the manufacture of new products.
- M. Recycling Facility: An operation that can legally accept materials for the purpose of processing the materials into an altered form for the manufacture of new products. Depending on the types of materials accepted and operating procedures, a recycling facility may or may not be required to have a solid waste facilities permit or be regulated by the local enforcement agency.

N. Reuse: Materials that are recovered for use in the same form, onsite or off-site.

- O. Return: To give back reusable items or unused products to vendors for credit.
- P. Salvage: To remove waste materials from the site for resale or re-use by a third party.
- Q. Source-Separated Materials: Materials that are sorted by type at the site for the purpose of reuse and recycling.
- R. Solid Waste: Materials that have been designated as non-recyclable and are discarded for the purposes of disposal.
- S. Transfer Station: A facility that can legally accept solid waste for the purpose of temporarily storing the materials for reloading onto other trucks and transporting them to a landfill for disposal, or recovering some materials for re-use or recycling.

## 1.5 SUBMITTALS

- A. In accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES, furnish the following:
- B. Prepare and submit to the A/E a written construction demolition waste management plan. The plan shall include, but not be limited to, the following information:
  - 1. Procedures to be used for debris management.
  - 2. Techniques to be used to minimize waste generation.
  - 3. Analysis of the estimated job site waste to be generated:
    - a. List of each material and quantity to be salvaged, reused, recycled.
    - b. List of each material and quantity proposed to be taken to a landfill.
  - 4. Detailed description of the Means/Methods to be used for material handling.
    - a. On site: Material separation, storage, protection where applicable.
    - b. Off site: Transportation means and destination. Include list of materials.
      - Description of materials to be site-separated and self-hauled to designated facilities.
      - Description of mixed materials to be collected by designated waste haulers and removed from the site.
    - c. The names and locations of mixed debris reuse and recycling facilities or sites
    - d. The names and locations of trash disposal landfill facilities or sites.
    - e. Documentation that the facilities or sites are approved to receive the materials.
- C. Designated Manager responsible for instructing personnel, supervising, documenting and administer over meetings relevant to the Waste Management Plan.
- D. Monthly summary of construction and demolition debris diversion and disposal, quantifying all materials generated at the work site and disposed of or diverted from disposal through recycling.

#### 1.6 APPLICABLE PUBLICATIONS

Publications listed below form a part of this specification to the extent referenced. Publications are referenced by the basic designation only. In the event that criteria requirements conflict, the most stringent requirements shall be met.

A. U.S. Green Building Council (USGBC):
LEED Green Building Rating System for New Construction

#### 1.7 RECORDS

Maintain records to document the quantity of waste generated; the quantity of waste diverted through sale, reuse, or recycling; and the quantity of waste disposed by landfill or incineration. Records shall be kept in accordance with the LEED Reference Guide and LEED Template.

# PART 2 - PRODUCTS

## 2.1 MATERIALS

- A. List of each material and quantity to be salvaged, recycled, reused.
- B. List of each material and quantity proposed to be taken to a landfill.
- C. Material tracking data: Receiving parties, dates removed, transportation costs, weight tickets, tipping fees, manifests, invoices, net total costs or savings.

# PART 3 - EXECUTION

# 3.1 COLLECTION

- A. Provide all necessary containers, bins and storage areas to facilitate effective waste management.
- B. Clearly identify containers, bins and storage areas so that recyclable materials are separated from trash and can be transported to respective recycling facility for processing.
- C. Hazardous wastes shall be separated, stored, disposed of according to local, state, federal regulations.

# 3.2 DISPOSAL

A. Contractor shall be responsible for transporting and disposing of materials that cannot be delivered to a source-separated or mixed materials recycling facility to a transfer station or disposal facility that can accept the materials in accordance with state and federal regulations.

B. Construction or demolition materials with no practical reuse or that cannot be salvaged or recycled shall be disposed of at a landfill or incinerator.

#### 3.3 REPORT

- A. With each application for progress payment, submit a summary of construction and demolition debris diversion and disposal including beginning and ending dates of period covered.
- B. Quantify all materials diverted from landfill disposal through salvage or recycling during the period with the receiving parties, dates removed, transportation costs, weight tickets, manifests, invoices. Include the net total costs or savings for each salvaged or recycled material.
- C. Quantify all materials disposed of during the period with the receiving parties, dates removed, transportation costs, weight tickets, tipping fees, manifests, invoices. Include the net total costs for each disposal.

END OF SECTION 01 74 19

# SECTION 02 41 00 DEMOLITION

## PART 1 - GENERAL

#### 1.1 DESCRIPTION:

This section specifies demolition and removal of portions of existing construction as indicated or required.

## 1.2 RELATED WORK:

- A. Safety Requirements: GENERAL CONDITIONS Article, ACCIDENT PREVENTION.
- B. Disconnecting utility services prior to demolition: Section 01 00 00, GENERAL REQUIREMENTS.
- C. Reserved items that are to remain the property of the Government: Section 01 00 00, GENERAL REQUIREMENTS.
- D. Asbestos Removal: Section 02 82 11, REMOVAL AND DISPOSAL OF ASBESTOS.
- E. Infectious Control: Section 01 00 00, GENERAL REQUIREMENTS, Article 1.8, INFECTION PREVENTION MEASURES and Section 00 72 01, INFECTION CONTROL.

# 1.3 PROTECTION:

- A. Perform demolition in such manner as to eliminate hazards to persons and property; to minimize interference with use of adjacent areas, utilities and structures or interruption of use of such utilities; and to provide free passage to and from such adjacent areas of structures. Comply with requirements of GENERAL CONDITIONS Article, ACCIDENT PREVENTION.
- B. Provide safeguards, including warning signs, barricades, temporary fences, warning lights, and other similar items that are required for protection of all personnel during demolition and removal operations. Comply with requirements of Section 01 00 00, GENERAL REQUIREMENTS, Article 1.10 PROTECTION OF EXISTING VEGETATION, STRUCTURES, EQUIPMENT, UTILITIES AND IMPROVEMENTS.
- C. Prevent spread of flying particles and dust. Sprinkle rubbish and debris with water to keep dust to a minimum. Do not use water if it results in hazardous or objectionable condition such as, but not limited to; ice, flooding, or pollution. Vacuum and dust the work area daily.
- D. Wherever a cutting torch or other equipment that might cause a fire is used, provide and maintain fire extinguishers nearby ready for immediate use. Instruct all possible users in use of fire extinguishers.

E. Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The contractor shall take necessary precautions to avoid damages to existing items to remain in place, to be reused, or to remain the property of the Medical Center; any damaged items shall be repaired or replaced as approved by the COR. The Contractor shall coordinate the work of this section with all other work and shall construct and maintain shoring, bracing, and supports as required. The Contractor shall ensure that structural elements are not overloaded and shall be responsible for increasing structural supports or adding new supports as may be required as a result of any cutting, removal, or demolition work performed under this contract. Do not overload structural elements. Provide new supports and reinforcement for existing construction weakened by demolition or removal works. Repairs, reinforcement, or structural replacement must have COR's approval.

F. The work shall comply with the requirements of Section 01 00 00, GENERAL REQUIREMENTS, Article 1.7 INFECTION PREVENTION MEASURES, Section 00 72 01, INFECTION CONTROL.

## 1.4 UTILITY SERVICES:

- A. Demolish and remove outside utility service lines shown to be removed.
- B. Remove abandoned outside utility lines that would interfere with installation of new utility lines and new construction.

# PART 2 - PRODUCTS (NOT USED)

# PART 3 - EXECUTION

## 3.1 DEMOLITION:

- A. Completely demolish and remove portions of existing construction, including all appurtenances related or connected thereto, as required to complete the work and as indicated in the drawings.
- B. Debris, including brick, concrete, stone, metals and similar materials shall become property of Contractor and shall be disposed of by him daily, off the Medical Center to avoid accumulation at the site. Contractor shall dispose debris in compliance with applicable federal, state or local permits, rules and/or regulations.
- C. Remove and legally dispose of all materials, other than earth to remain as part of project work, from any trash dumps shown. Materials removed shall become property of contractor and shall be disposed of in compliance with applicable federal, state or local permits, rules and/or regulations. The removal of hazardous material shall be referred to Hazardous Materials specifications.
- D. Remove existing utilities as indicated or uncovered by work and terminate in a manner conforming to the nationally recognized code covering the specific utility and approved by the COR. When

VA-528A7-12-706 DEMOLITION 02 41 00-2

Utility lines are encountered that are not indicated on the drawings, the COR shall be notified prior to further work in that area.

# 3.2 CLEAN-UP:

On completion of work of this section and after removal of all debris, leave site in clean condition satisfactory to COR. Clean-up shall include disposal of all items and materials not required to remain property of the Government as well as all debris and rubbish resulting from demolition operations.

END OF SECTION 02 41 00

VA-528A7-12-706 DEMOLITION 02 41 00-3



# SECTION 05 50 00 METAL FABRICATIONS

## PART 1 - GENERAL

## 1.1 DESCRIPTION

- A. This section specifies items and assemblies fabricated from structural steel shapes and other materials as shown and specified.
- B. Items specified.
  - 1. Frames: (24E)

## 1.2 RELATED WORK

A. Prime and finish painting: Section 09 91 00, PAINTING.

#### 1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Shop Drawings:
  - 1. Each item specified, showing complete detail, location in the project, material and size of components, method of joining various components and assemblies, finish, and location, size and type of anchors.
  - 2. Mark items requiring field assembly for erection identification and furnish erection drawings and instructions.
  - 3. Provide templates and rough-in measurements as required.
- C. Manufacturer's Certificates:
  - 1. Live load designs as specified.
- D. Design Calculations for specified live loads including dead loads.
- E. Furnish setting drawings and instructions for installation of anchors to be preset into concrete and masonry work, and for the positioning of items having anchors to be built into concrete or masonry construction.

# 1.4 QUALITY ASSURANCE

- A. Each manufactured product shall meet, as a minimum, the requirements specified, and shall be a standard commercial product of a manufacturer regularly presently manufacturing items of type specified.
- B. Each product type shall be the same and be made by the same manufacturer.
- C. Assembled product to the greatest extent possible before delivery to the site.

# 1.5 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

В.	American	Society	of	Mechanical	Engineers	(ASME):
	B18.2.2-870	(R2005)		Square a	nd Hex Nuts	

C.	A36/A36M-05	
	A47-99(R2004)	
	A48-03	,
	A53-06	. Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and
		Seamless
		. Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
	A269-07	. Seamless and Welded Austenitic Stainless Steel Tubing for General Service
	A307-07	. Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength
		. Seamless, Welded, and Heavily Cold Worked Austenitic Stainless
	•	Steel Pipes
	A653/A653M-07	. Steel Sheet, Zinc Coated (Galvanized) or Zinc-Iron Alloy Coated
	•	(Galvannealed) by the Hot-Dip Process
	A786/A786M-05	· · · ·
		. Packaged Dry, Hydraulic-Cement Grout (Nonshrink)
		. Insect Screening and Louver Cloth Woven from Vinyl-Coated
		Glass Yarns
	F436-07	. Hardened Steel Washers
	F468-06	. Nonferrous Bolts, Hex Cap Screws, and Studs for General Use
	F1667-05	. Driven Fasteners: Nails, Spikes and Staples
D.	American Welding Society	
	D1.1-04	<u> </u>
	D1.3-98	. Structural Welding Code Sheet Steel
Ε.	National Association of	Architectural Metal Manufacturers (NAAMM)
	AMP 500-505-1988	. Metal Finishes Manual
	MBG 531-00	. Metal Bar Grating Manual
	MBG 532-00	. Heavy Duty Metal Bar Grating Manual
F.	Structural Steel Paintin	ng Council (SSPC):
	SP 1-05	
	SP 2-05	
	•· = •• ······	

# PART 2 - PRODUCTS

# 2.1 MATERIALS

A. Structural Steel: ASTM A36.

- B. Steel Pipe: ASTM A53.
  - 1. Galvanized for exterior locations.
  - 2. Type S, Grade A unless specified otherwise.
  - 3. NPS (inside diameter) as shown.
- C. Primer Paint: As specified in Section 09 91 00, PAINTING.
- D. Modular Channel Units:
  - 1. Factory fabricated, channel shaped, cold formed sheet steel shapes, complete with fittings bolts and nuts required for assembly.
  - 2. Form channel with in turned pyramid shaped clamping ridges on each side.
  - 3. Provide case hardened steel nuts with serrated grooves in the top edges designed to be inserted in the channel at any point and be given a quarter turn so as to engage the channel clamping ridges. Provide each nut with a spring designed to hold the nut in place.
  - 4. Factory finish channels and parts with oven baked primer when exposed to view. Channels fabricated of ASTM A525, G90 galvanized steel may have primer omitted in concealed locations. Finish screws and nuts with zinc coating.
  - 5. Fabricate snap-in closure plates to fit and close exposed channel openings of not more than 0.3 mm (0.0125 inch) thick stainless steel.
- E. Grout: ASTM C1107, pourable type.

## 2.2 HARDWARE

- A. Rough Hardware:
  - 1. Furnish rough hardware with a standard plating, applied after punching, forming and assembly of parts; galvanized, cadmium plated, or zinc-coated by electro-galvanizing process. Galvanized G-90 where specified.
  - 2. Use G90 galvanized coating on ferrous metal for exterior work unless non-ferrous metal or stainless is used.
- B. Fasteners:
  - 1. Bolts with Nuts:
    - a. ASME B18.2.2.
    - b. ASTM A307 for 415 MPa (60,000 psi) tensile strength bolts.
    - c. ASTM F468 for nonferrous bolts.
    - d. ASTM F593 for stainless steel.
  - 2. Screws: ASME B18.6.1.
  - 3. Washers: ASTM F436, type to suit material and anchorage.
  - 4. Nails: ASTM F1667, Type I, style 6 or 14 for finish work.

# 2.3 FABRICATION GENERAL

- A. Material
  - 1. Use material as specified. Use material of commercial quality and suitable for intended purpose for material that is not named or its standard of quality not specified.
  - 2. Use material free of defects which could affect the appearance or service ability of the finished product.

# B. Size:

- 1. Size and thickness of members as shown.
- 2. When size and thickness is not specified or shown for an individual part, use size and thickness not less than that used for the same component on similar standard commercial items or in accordance with established shop methods.

## C. Connections

- 1. Except as otherwise specified, connections may be made by welding, riveting or bolting.
- 2. Field riveting will not be approved.
- 3. Design size, number and placement of fasteners, to develop a joint strength of not less than the design value.
- 4. Holes, for rivets and bolts: Accurately punched or drilled and burrs removed.
- 5. Size and shape welds to develop the full design strength of the parts connected by welds and to transmit imposed stresses without permanent deformation or failure when subject to service loadings.
- 6. Use Rivets and bolts of material selected to prevent corrosion (electrolysis) at bimetallic contacts. Plated or coated material will not be approved.
- 7. Use stainless steel connectors for removable members machine screws or bolts.

# D. Fasteners and Anchors

- 1. Use methods for fastening or anchoring metal fabrications to building construction as shown or specified.
- 2. Where fasteners and anchors are not shown, design the type, size, location and spacing to resist the loads imposed without deformation of the members or causing failure of the anchor or fastener, and suit the sequence of installation.
- 3. Use material and finish of the fasteners compatible with the kinds of materials which are fastened together and their location in the finished work.
- 4. Fasteners for securing metal fabrications to new construction only, may be by use of threaded or wedge type inserts or by anchors for welding to the metal fabrication for installation before the concrete is placed or as masonry is laid.
- 5. Fasteners for securing metal fabrication to existing construction or new construction may be expansion bolts, toggle bolts, power actuated drive pins, welding, self drilling and tapping screws or bolts.

## E. Workmanship

# 1. General:

- a. Fabricate items to design shown.
- b. Furnish members in longest lengths commercially available within the limits shown and specified.
- c. Fabricate straight, true, free from warp and twist, and where applicable square and in same plane.
- d. Provide holes, sinkages and reinforcement shown and required for fasteners and anchorage items.
- e. Provide openings, cut-outs, and tapped holes for attachment and clearances required for work of other trades.
- f. Prepare members for the installation and fitting of hardware.
- g. Cut openings in gratings and floor plates for the passage of ducts, sumps, pipes, conduits and similar items. Provide reinforcement to support cut edges.

h. Fabricate surfaces and edges free from sharp edges, burrs and projections which may cause injury.

# 2. Welding:

- a. Weld in accordance with AWS.
- b. Welds shall show good fusion, be free from cracks and porosity and accomplish secure and rigid joints in proper alignment.
- c. Where exposed in the finished work, continuous weld for the full length of the members joined and have depressed areas filled and protruding welds finished smooth and flush with adjacent surfaces.
- d. Finish welded joints to match finish of adjacent surface.

# 3. Joining:

- a. Miter or butt members at corners.
- b. Where frames members are butted at corners, cut leg of frame member perpendicular to surface, as required for clearance.

#### 4. Anchors:

- a. Where metal fabrications are shown to be preset in concrete, weld 32 x 3 mm (1-1/4 by 1/8 inch) steel strap anchors, 150 mm (6 inches) long with 25 mm (one inch) hooked end, to back of member at 600 mm (2 feet) on center, unless otherwise shown.
- b. Where metal fabrications are shown to be built into masonry use 32 x 3 mm (1-1/4 by 1/8 inch) steel strap anchors, 250 mm (10 inches) long with 50 mm (2 inch) hooked end, welded to back of member at 600 mm (2 feet) on center, unless otherwise shown.

# 5. Cutting and Fitting:

- a. Accurately cut, machine and fit joints, corners, copes, and miters.
- b. Fit removable members to be easily removed.
- c. Design and construct field connections in the most practical place for appearance and ease of installation.
- d. Fit pieces together as required.
- e. Fabricate connections for ease of assembly and disassembly without use of special tools.
- f. Joints firm when assembled.
- g. Conceal joining, fitting and welding on exposed work as far as practical.
- h. Do not show rivets and screws prominently on the exposed face.
- i. The fit of components and the alignment of holes shall eliminate the need to modify component or to use exceptional force in the assembly of item and eliminate the need to use other than common tools.

# F. Finish:

- 1. Finish exposed surfaces in accordance with NAAMM Metal Finishes Manual.
- 3. Steel and Iron: NAAMM AMP 504.

# A. Shop Prime Painting:

- 1) Surfaces of Ferrous metal:
  - a) Items not specified to have other coatings.
  - b) Galvanized surfaces specified to have prime paint.
  - c) Remove all loose mill scale, rust, and paint, by hand or power tool cleaning as defined in SSPC-SP2 and SP3.
  - d) Clean of oil, grease, soil and other detrimental matter by use of solvents or cleaning compounds as defined in SSPC-SP1.
  - e) After cleaning and finishing apply one coat of primer as specified in Section 09 91 00, PAINTING.
- 2) Non ferrous metals: Comply with MAAMM-500 series.

## 2.4 SUPPORTS

- A. General:
  - 1. Fabricate ASTM A36 structural steel shapes as shown.
  - 2. Use clip angles or make provisions for welding hangers and braces to overhead construction.
  - 3. Field connections may be welded or bolted.

#### PART 3 - EXECUTION

# 3.1 INSTALLATION, GENERAL

- A. Set work accurately, in alignment and where shown, plumb, level, free of rack and twist, and set parallel or perpendicular as required to line and plane of surface.
- B. Items set into concrete or masonry.
  - 1. Provide temporary bracing for such items until concrete or masonry is set.
  - 2. Place in accordance with setting drawings and instructions.
  - 3. Build strap anchors, into masonry as work progresses.
- C. Set frames of gratings, covers, corner guards, trap doors and similar items flush with finish floor or wall surface and, where applicable, flush with side of opening.
- D. Field weld in accordance with AWS.
  - 1. Design and finish as specified for shop welding.
  - 2. Use continuous weld unless specified otherwise.
- E. Install anchoring devices and fasteners as shown and as necessary for securing metal fabrications to building construction as specified. Power actuated drive pins may be used except for removable items and where members would be deformed or substrate damaged by their use.
- F. Spot prime all abraded and damaged areas of zinc coating as specified and all abraded and damaged areas of shop prime coat with same kind of paint used for shop priming.
- G. Isolate aluminum from dissimilar metals and from contact with concrete and masonry materials as required to prevent electrolysis and corrosion.

# 3.2 INSTALLATION OF SUPPORTS

- A. Anchorage to structure.
  - 1. Secure angles or channels and clips to overhead structural steel by continuous welding unless bolting is shown.
  - 2. Secure supports to concrete inserts by bolting or continuous welding as shown.
  - 3. Secure supports to mid height of concrete beams when inserts do not exist with expansion bolts and to slabs, with expansion bolts. unless shown otherwise.
  - 4. Secure steel plate or hat channels to studs as detailed.

# 3.3 CLEAN AND ADJUSTING

A. Adjust movable parts including hardware to operate as designed without binding or deformation of the members centered in the opening or frame and, where applicable, contact surfaces fit tight and even without forcing or warping the components.

B. Clean after installation exposed prefinished and plated items and items fabricated from stainless steel, aluminum and copper alloys, as recommended by the metal manufacture and protected from damage until completion of the project.

END OF SECTION 05 50 00



# SECTION 07 84 00 FIRESTOPPING

#### PART 1 GENERAL

#### 1.1 DESCRIPTION

- A. Closures of openings in walls, floors, and roof decks against penetration of flame, heat, and smoke or gases in fire resistant rated construction.
- B. Closure of openings in walls against penetration of gases or smoke in smoke partitions.

#### 1.2 RELATED WORK

A. Fire and smoke damper assemblies in ductwork: Section 23 31 00, HVAC DUCTS AND CASINGS.

#### 1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturers literature, data, and installation instructions for types of firestopping and smoke stopping used.
- C. List of FM, UL, or WH classification number of systems installed.
- D. Certified laboratory test reports for ASTM E814 tests for systems not listed by FM, UL, or WH proposed for use.

#### 1.4 DELIVERY AND STORAGE

- A. Deliver materials in their original unopened containers with manufacturer's name and product identification.
- B. Store in a location providing protection from damage and exposure to the elements.

## 1.5 WARRANTY

Firestopping work subject to the terms of the Article "Warranty of Construction", FAR clause 52.246-21, except extend the warranty period to five years.

## 1.6 QUALITY ASSURANCE

 ${\tt FM}$ , UL, or WH or other approved laboratory tested products will be acceptable.

## 1.7 APPLICABLE PUBLICATIONS

A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by the basic designation only.

В.	American	Society	for	Testing	and	Materials	(ASTM):	
	E84-07 Surface Burning Characteristics of Building Materials							
	E814-06 Fire Tests of Through-Penetration Fire Stops							

- C. Factory Mutual Engineering and Research Corporation (FM):
  Annual Issue Approval Guide Building Materials
- D. Underwriters Laboratories, Inc. (UL):
  Annual Issue Building Materials Directory
  Annual Issue Fire Resistance Directory
  1479-03.....Fire Tests of Through-Penetration Firestops
- E. Warnock Hersey (WH):
  Annual Issue Certification Listings

#### PART 2 - PRODUCTS

#### 2.1 FIRESTOP SYSTEMS

- A. Use either factory built (Firestop Devices) or field erected (through-Penetration Firestop Systems) to form a specific building system maintaining required integrity of the fire barrier and stop the passage of gases or smoke.
- B. Through-penetration firestop systems and firestop devices tested in accordance with ASTM E814 or UL 1479 using the "F" or "T" rating to maintain the same rating and integrity as the fire barrier being sealed. "T" ratings are not required for penetrations smaller than or equal to 100 mm (4 in) nominal pipe or 0.01 m² (16 sq. in.) in overall cross sectional area.
- C. Products requiring heat activation to seal an opening by its intumescence shall exhibit a demonstrated ability to function as designed to maintain the fire barrier.
- D. Firestop sealants used for firestopping or smoke sealing shall have following properties:
  - 1. Contain no flammable or toxic solvents.
  - 2. Have no dangerous or flammable out gassing during the drying or curing of products.
  - 3. Water-resistant after drying or curing and unaffected by high humidity, condensation or transient water exposure.
  - 4. When used in exposed areas, shall be capable of being sanded and finished with similar surface treatments as used on the surrounding wall or floor surface.
- E. Firestopping system or devices used for penetrations by glass pipe, plastic pipe or conduits, unenclosed cables, or other non-metallic materials shall have following properties:
  - 1. Classified for use with the particular type of penetrating material used.
  - 2. Penetrations containing loose electrical cables, computer data cables, and communications cables protected using firestopping systems that allow unrestricted cable changes without damage to the seal.

VA-528A7-12-706 FIRESTOPPING 07 84 00-2

3. Intumescent products which would expand to seal the opening and act as fire, smoke, toxic fumes, and, water sealant.

- F. Maximum flame spread of 25 and smoke development of 50 when tested in accordance with ASTM E84.
- G. FM, UL, or WH rated or tested by an approved laboratory in accordance with ASTM E814.
- H. Materials to be asbestos free.

#### 2.2 SMOKE STOPPING IN SMOKE PARTITIONS

- A. Use silicone sealant in smoke partitions as specified in Section 07 92  $\,$  00, JOINT SEALANTS.
- B. Use mineral fiber filler and bond breaker behind sealant.
- C. Sealants shall have a maximum flame spread of 25 and smoke developed of 50 when tested in accordance with E84.
- D. When used in exposed areas capable of being sanded and finished with similar surface treatments as used on the surrounding wall or floor surface.

#### PART 3 - EXECUTION

#### 3.1 EXAMINATION

Submit product data and installation instructions, as required by article, submittals, after an on site examination of areas to receive firestopping.

#### 3.2 PREPARATION

- A. Remove dirt, grease, oil, loose materials, or other substances that prevent adherence and bonding or application of the firestopping or smoke stopping materials.
- B. Remove insulation on insulated pipe for a distance of 150 mm (six inches) on either side of the fire rated assembly prior to applying the firestopping materials unless the firestopping materials are tested and approved for use on insulated pipes.

#### 3.3 INSTALLATION

- A. Do not begin work until the specified material data and installation instructions of the proposed firestopping systems have been submitted and approved.
- B. Install firestopping systems with smoke stopping in accordance with FM, UL, WH, or other approved system details and installation instructions.
- C. Install smoke stopping seals in smoke partitions.

VA-528A7-12-706 FIRESTOPPING 07 84 00-3

## 3.4 CLEAN-UP AND ACCEPTANCE OF WORK

- A. As work on each floor is completed, remove materials, litter, and debris.
- B. Do not move materials and equipment to the next-scheduled work area until completed work is inspected and accepted by the COR.
- C. Clean up spills of liquid type materials.

END OF SECTION 07 84 00

VA-528A7-12-706 FIRESTOPPING 07 84 00-4

# SECTION 07 92 00 JOINT SEALANTS

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION:

Section covers all sealant and caulking materials and their application, wherever required for complete installation of building materials or systems.

#### 1.2 RELATED WORK:

A. Color of sealants: See material schedule on drawings.

## 1.3 QUALITY CONTROL:

- A. Installer Qualifications: An experienced installer who has specialized in installing joint sealants similar in material, design, and extent to those indicated for this Project and whose work has resulted in joint-sealant installations with a record of successful in-service performance.
- B. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.
- C. VOC: Acrylic latex and Silicon sealants shall have less than  $50 \mathrm{g}/\mathrm{l}$  VOC content.

## 1.4 SUBMITTALS:

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's installation instructions for each product used.
- C. Cured samples of exposed sealants for each color where required to match adjacent material.
- D. Manufacturer's Literature and Data:
  - Caulking compound
  - 2. Primers
  - 3. Sealing compound, each type, including compatibility when different sealants are in contact with each other.

## 1.5 PROJECT CONDITIONS:

- A. Environmental Limitations:
  - 1. Do not proceed with installation of joint sealants under following conditions:
    - a. When ambient and substrate temperature conditions are outside limits permitted by joint sealant manufacturer or are below 4.4 °C (40 °F).
    - b. When joint substrates are wet.

- B. Joint-Width Conditions:
  - 1. Do not proceed with installation of joint sealants where joint widths are less than those allowed by joint sealant manufacturer for applications indicated.
- C. Joint-Substrate Conditions:
  - Do not proceed with installation of joint sealants until contaminants capable of interfering with adhesion are removed from joint substrates.

#### 1.6 DELIVERY, HANDLING, AND STORAGE:

- A. Deliver materials in manufacturers' original unopened containers, with brand names, date of manufacture, shelf life, and material designation clearly marked thereon.
- B. Carefully handle and store to prevent inclusion of foreign materials.
- C. Do not subject to sustained temperatures exceeding  $5^{\circ}$  C  $(40^{\circ}$  F) or less than  $32^{\circ}$  C  $(90^{\circ}$  F).

#### 1.7 DEFINITIONS:

- A. Definitions of terms in accordance with ASTM C717 and as specified.
- B. Back-up Rod: A type of sealant backing.
- C. Bond Breakers: A type of sealant backing.
- D. Filler: A sealant backing used behind a back-up rod.

## 1.8 WARRANTY:

- A. Warranty exterior sealing against leaks, adhesion, and cohesive failure, and subject to terms of "Warranty of Construction", FAR clause 52.246-21, except that warranty period shall be extended to two years.
- B. General Warranty: Special warranty specified in this Article shall not deprive Government of other rights Government may have under other provisions of Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of Contract Documents.

## 1.9 APPLICABLE PUBLICATIONS:

- A. Publications listed below form a part of this specification to extent referenced. Publications are referenced in text by basic designation only.
- B. American Society for Testing and Materials (ASTM):

C509-06 Elastomeric Cellular Preformed Gasket and Sealing Material.

C612-04 Mineral Fiber Block and Board Thermal Insulation.

C717-07 Standard Terminology of Building Seals and Sealants.

C834-05 Latex Sealants.

C919-02.	Use of Sealants in Acoustical Applications.
C920-05	Elastomeric Joint Sealants.
C1021-08	Laboratories Engaged in Testing of Building Sealants.
C1193-05	Standard Guide for Use of Joint Sealants.
C1330-02 (R2007)	Cylindrical Sealant Backing for Use with Cold Liquid Applied
	Sealants.
D1056-07	Specification for Flexible Cellular Materials—Sponge or Expanded
	Rubber.
E84-08	Surface Burning Characteristics of Building Materials.

Sealant, Waterproofing and Restoration Institute (SWRI). The Professionals' Guide

#### PART 2 - PRODUCTS

#### 2.1 SEALANTS:

- A. S-1:
  - 1. ASTM C920 silicone.
  - 2. Type S.
  - 3. Class 25.
  - 4. Grade NS.
  - 5. Shore A hardness of 25-30.
  - 6. Non-yellowing, mildew resistant.

### 2.2 COLOR:

A. Caulking shall be light gray or white, unless specified otherwise.

## 2.3 JOINT SEALANT BACKING:

- A. General: Provide sealant backings of material and type that are nonstaining; are compatible with joint substrates, sealants, primers, and other joint fillers; and are approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.
- B. Cylindrical Sealant Backings: ASTM C1330, of type indicated below and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance:
  - 1. Type C: Closed-cell material with a surface skin.
- C. Elastomeric Tubing Sealant Backings: Neoprene, butyl, EPDM, or silicone tubing complying with ASTM D1056, nonabsorbent to water and gas, and capable of remaining resilient at temperatures down to minus 32° C (minus 26° F). Provide products with low compression set and of size and shape to provide a secondary seal, to control sealant depth, and otherwise contribute to optimum sealant performance.
- D. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from

adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

#### 2.4 FILLER:

- A. Mineral fiber board: ASTM C612, Class 1.
- B. Thickness same as joint width.
- C. Depth to fill void completely behind back-up rod.

#### 2.5 PRIMER:

- A. As recommended by manufacturer of caulking or sealant material.
- B. Stain free type.

#### 2.6 CLEANERS-NON POUROUS SURFACES:

Chemical cleaners acceptable to manufacturer of sealants and sealant backing material, free of oily residues and other substances capable of staining or harming joint substrates and adjacent non-porous surfaces and formulated to promote adhesion of sealant and substrates.

#### PART 3 - EXECUTION

#### 3.1 INSPECTION:

- A. Inspect substrate surface for bond breaker contamination and unsound materials at adherent faces of sealant.
- B. Coordinate for repair and resolution of unsound substrate materials.
- C. Inspect for uniform joint widths and that dimensions are within tolerance established by sealant manufacturer.

#### 3.2 PREPARATIONS:

- A. Prepare joints in accordance with manufacturer's instructions and SWRI.
- B. Clean surfaces of joint to receive caulking or sealants leaving joint dry to the touch, free from frost, moisture, grease, oil, wax, lacquer paint, or other foreign matter that would tend to destroy or impair adhesion.
  - 1. Clean porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants.
  - 2. Remove loose particles remaining from above cleaning operations by vacuuming or blowing out joints with oil-free compressed air.

 Clean nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants.

- a. Metal.
- b. Glass.
- c. Porcelain enamel.
- d. Glazed surfaces of ceramic tile.
- C. Do not cut or damage joint edges.
- D. Apply masking tape to face of surfaces adjacent to joints before applying primers, caulking, or sealing compounds.
  - Do not leave gaps between ends of sealant backings.
  - 2. Do not stretch, twist, puncture, or tear sealant backings.
  - 3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.
- E. Apply primer to sides of joints wherever required by compound manufacturer's printed instructions.
  - 1. Apply primer prior to installation of back-up rod or bond breaker tape.
  - 2. Use brush or other approved means that will reach all parts of joints.
- F. Take all necessary steps to prevent three sided adhesion of sealants.

## 3.3 BACKING INSTALLATION:

- A. Install back-up material, to form joints enclosed on three sides as required for specified depth of sealant.
- B. Where deep joints occur, install filler to fill space behind the back-up rod and position the rod at proper depth.
- C. Cut fillers installed by others to proper depth for installation of back-up rod and sealants.
- D. Install back-up rod, without puncturing the material, to a uniform depth, within plus or minus 3 mm (1/8 inch) for sealant depths specified.
- E. Where space for back-up rod does not exist, install bond breaker tape strip at bottom (or back) of joint so sealant bonds only to two opposing surfaces.
- F. Take all necessary steps to prevent three sided adhesion of sealants.

#### 3.4 SEALANT DEPTHS AND GEOMETRY:

- A. At widths up to 6 mm (1/4 inch), sealant depth equal to width.
- B. At widths over 6 mm (1/4 inch), sealant depth 1/2 of width up to 13 mm (1/2 inch) maximum depth at center of joint with sealant

thickness at center of joint approximately 1/2 of depth at adhesion surface.

#### 3.5 INSTALLATION:

#### A. General:

- 1. Apply sealants and caulking only when ambient temperature is between  $5^{\circ}$  C and  $38^{\circ}$  C ( $40^{\circ}$  and  $100^{\circ}$  F).
- 2. Do not use sealant type listed by manufacture as not suitable for use in locations specified.
- 3. Apply caulking and sealing compound in accordance with manufacturer's printed instructions.
- 4. Avoid dropping or smearing compound on adjacent surfaces.
- 5. Fill joints solidly with compound and finish compound smooth.
- 6. Tool joints to concave surface unless shown or specified otherwise.
- 7. Apply compounds with nozzle size to fit joint width.
- 8. Test sealants for compatibility with each other and substrate. Use only compatible sealant.
- B. For application of sealants, follow requirements of ASTM C1193 unless specified otherwise.
- C. Where gypsum board partitions are of sound rated, fire rated, or smoke barrier construction, follow requirements of ASTM C919 only to seal all cut-outs and intersections with the adjoining construction unless specified otherwise.
  - 1. Apply a 6 mm (1/4 inch) minimum bead of sealant each side of runners (tracks), including those used at partition intersections with dissimilar wall construction.
  - 2. Coordinate with application of gypsum board to install sealant immediately prior to application of gypsum board.
  - 3. Partition intersections: Seal edges of face layer of gypsum board abutting intersecting partitions, before taping and finishing or application of veneer plaster-joint reinforcing.
  - 4. Openings: Apply a 6 mm (1/4 inch) bead of sealant around all cut-outs to seal openings of electrical boxes, ducts, pipes and similar penetrations. To seal electrical boxes, seal sides and backs.
  - 5. Control Joints: Before control joints are installed, apply sealant in back of control joint to reduce flanking path for sound through control joint.

## 3.6 FIELD QUALITY CONTROL:

- A. Inspect joints for complete fill, for absence of voids, and for joint configuration complying with specified requirements.
- B. Replace caulking and sealant which has voids, improper joint configuration, poor adhesion, poor tooling, or other defects.

#### 3.7 CLEANING:

A. Fresh compound accidentally smeared on adjoining surfaces: Scrape off immediately and rub clean with a solvent as recommended by the caulking or sealant manufacturer.

- After filling and finishing joints, remove masking tape.
- C. Leave adjacent surfaces in a clean and unstained condition.

#### LOCATIONS: 3.8

Sanitary Joints: Α.

1. Walls to Plumbing Fixtures: Type S-1

Counter Tops to Walls: Type S-1
 All other joints: Type S-1

END OF SECTION 07 92 00

07 92 00-7 VA-528A7-12-706 JOINT SEALANTS



## SECTION 09 91 00 PAINTING

#### PART 1-GENERAL

#### 1.1 DESCRIPTION

- A. Section specifies field painting.
- B. Section specifies prime coats which may be applied in shop under other sections.
- C. Painting includes shellacs, stains, varnishes, coatings specified, and striping or markers and identity markings.

#### 1.2 RELATED WORK

- A. Shop prime painting of steel and ferrous metals: Division 05 METALS, Division 23 HEATING, VENTILATION AND AIR-CONDITIONING, Division 26 ELECTRICAL.
- B. Type of Finish and Color Finish Coat: See Material Schedule and Room Finish Schedule on drawings.

#### 1.3 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:

  Before work is started, or sample panels are prepared, submit manufacturer's literature, the current Master Painters Institute (MPI) "Approved Product List" indicating brand label, product name and product code as of the date of contract award, will be used to determine compliance with the submittal requirements of this specification. The Contractor may choose to use subsequent MPI "Approved Product List", however, only one list may be used for the entire contract and each coating system is to be from a single manufacturer. All coats on a particular substrate must be from a single manufacturer. No variation from the MPI "Approved Product List" where applicable is acceptable.

### C. Samples:

- 1. After painters' materials have been approved and before work is started submit samples showing each type of finish and color specified.
- Panels to show color: Composition board, 100 by 250 by 3 mm (4 inch by 10 inch by 1/8 inch).
- 3. Panel to show transparent finishes: Wood of same species and grain pattern as wood approved for use, 100 by 250 by 3 mm (4 inch by 10 inch face by 1/4 inch) thick minimum, and where both flat and edge grain will be exposed, 250 mm (10 inches) long by sufficient size, 50 by 50 mm (2 by 2 inch) minimum or actual wood member to show complete finish.
- 4. Attach labels to panel stating the following:

- a. Federal Specification Number or manufacturers name and product number of paints used.
- b. Specification code number specified in Section 09 06 00, SCHEDULE FOR FINISHES.
- c. Product type and color.
- d. Name of project.
- 5. Strips showing not less than 50 mm (2 inch) wide strips of undercoats and 100 mm (4 inch) wide strip of finish coat.

#### 1.4 DELIVERY AND STORAGE

- A. Deliver materials to site in manufacturer's sealed container marked to show following:
  - 1. Name of manufacturer.
  - 2. Product type.
  - 3. Batch number.
  - 4. Instructions for use.
  - 5. Safety precautions.
- B. In addition to manufacturer's label, provide a label legibly printed as following:
  - Federal Specification Number, where applicable, and name of material.
  - 2. Surface upon which material is to be applied.
  - If paint or other coating, state coat types; prime, body or finish.
- C. Maintain space for storage, and handling of painting materials and equipment in a neat and orderly condition to prevent spontaneous combustion from occurring or igniting adjacent items.
- D. Store materials at site at least 24 hours before using, at a temperature between 18 and 30 degrees C (65 and 85 degrees F).

## 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below form a part of this specification to the extent referenced. Publications are referenced in the text by basic designation only.
- B. American Conference of Governmental Industrial Hygienists (ACGIH):

ACGIH TLV-BKLT-2008 Threshold Limit Values (TLV) for Chemical

Substances and Physical

Agents and Biological Exposure Indices

BEIs)

ACGIH TLV-DOC-2008 Documentation of Threshold Limit Values

and Biological Exposure Indices, (Seventh

Edition)

- D. American Society for Testing and Materials (ASTM):
  D260-86 Boiled Linseed Oil
- E. Commercial Item Description (CID):

```
A-A-1555 Water Paint, Powder (Cementitious, White and Colors) (WPC) (cancelled)
A-A-3120 Paint, For Swimming Pools (RF) (cancelled)
```

F. Federal Specifications (Fed Spec):

TT-P-1411A Paint, Copolymer-Resin, Cementitious (For Waterproofing Concrete and Masonry Walls) (CEP)

G. Master Painters Institute (MPI):

```
No. 4-07
                      Interior/ Exterior Latex Block Filler
No. 18-07
                     Organic Zinc Rich Primer
No. 31-07
                     Polyurethane, Moisture Cured, Clear Gloss (PV)
No. 36-07
                     Knot Sealer
No. 43-07
                     Interior Satin Latex, MPI Gloss Level 4
No. 45-07
                     Interior Primer Sealer
                   Interior Enamel Undercoat
No. 46-07
No. 47-07
                     Interior Alkyd, Semi-Gloss, MPI Gloss Level 5
                      (AK)
                      Interior Latex Primer Sealer
No. 50-07
No. 54-07
                      Interior Latex, Semi-Gloss, MPI Gloss Level 5
No. 90-07 Interior Wood Stain, Semi-Transpare:
No. 91-07 Wood Filler Paste
No. 95-07 Fast Drying Metal Primer
No. 114-07 Interior Latex, Gloss (LE) and (LG)
No. 135-07 Non-Cementitious Galvanized Primer
No. 139-07 Interior High Performance Tator (CD)
                      (LE)
                      Interior Wood Stain, Semi-Transparent (WS)
                      Interior High Performance Latex, MPI Gloss
                       Level 3 (LL)
```

H. Steel Structures Painting Council (SSPC):

SSPC SP 1-04 (R2004) Solvent Cleaning
SSPC SP 2-04 (R2004) Hand Tool Cleaning
SSPC SP 3-04 (R2004) Power Tool Cleaning

## PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. All materials shall be as manufactured by Pittsburgh Paints. NO EXCEPTIONS.
- B. Identity Markers Options:
  - 1. Pressure sensitive vinyl markers.
  - 2. Snap-on coil plastic markers.
- C. Interior/Exterior Latex Block Filler: MPI 4.
- D. Organic Zinc Rich Coating (HR): MPI 18.
- E. Polyurethane, Moisture Cured, Clear Gloss: MPI 31.
- F. Knot Sealer: MPI 36.
- G. Interior Satin Latex: MPI 43.
- H. Interior Primer Sealer: MPI 45.

- I. Interior Enamel Undercoat: MPI 46.
- J. Interior Alkyd, Semi-Gloss (AK): MPI 47.
- K. Interior Latex Primer Sealer: MPI 50.
- L. Interior Latex, Semi-Gloss, MPI Gloss Level 5 (LE): MPI 54.
- M. Interior Wood Stain, Semi-Transparent (WS): MPI 90.
- N. Wood Filler Paste: MPI 91.
- O. Fast Drying Metal Primer: MPI 95.
- P. Interior Latex, Gloss (LE) and (LG): MPI 114.
- Q. Waterborne Galvanized Primer: MPI 134.
- R. Non-Cementitious Galvanized Primer: MPI 135.
- S. Interior High Performance Latex, MPI Gloss Level 3 (LL): MPI 139.

#### 2.2 PAINT PROPERTIES

- A. Use ready-mixed (including colors), except two component polyurethanes, polyesters, paints having metallic powders packaged separately and paints requiring specified additives.
- B. Where no requirements are given in the referenced specifications for primers, use primers with pigment and vehicle, compatible with substrate and finish coats specified.

## 2.3 REGULATORY REQUIREMENTS

- A. Paint materials shall conform to the restrictions of the local Environmental and Toxic Control jurisdiction.
  - 1. Volatile Organic Compounds (VOC): VOC content of paint materials shall not exceed local, state, or Federal requirements.
  - 2. Lead-Base Paint:
    - a. Comply with Section 410 of the Lead-Based Paint Poisoning Prevention Act, as amended, and with implementing regulations promulgated by Secretary of Housing and Urban Development.
    - Regulations concerning prohibition against use of lead-based paint in federal and federally assisted construction, or rehabilitation of residential structures are set forth in Subpart F, Title 24, Code of Federal Regulations, and Department of Housing and Urban Development.
  - 3. Asbestos: Materials shall not contain asbestos.
  - 4. Chromate, Cadmium, Mercury, and Silica: Materials shall not contain zinc-chromate, strontium-chromate, Cadmium, mercury or mercury compounds or free crystalline silica.
  - 5. Human Carcinogens: Materials shall not contain any of the ACGIH-BKLT and ACGHI-DOC confirmed or suspected human carcinogens.

6. Comply with the Regional Ozone Transport Commission (OTC) regulations regarding Volatile Organic Content (VOC).

#### PART 3 - EXECUTION

## 3.1 JOB CONDITIONS

- A. Safety: Observe required safety regulations and manufacturer's warning and instructions for storage, handling and application of painting materials.
  - 1. Take necessary precautions to protect personnel and property from hazards due to falls, injuries, toxic fumes, fire, explosion, or other harm.
  - 2. Deposit soiled cleaning rags and waste materials in metal containers approved for that purpose. Dispose of such items off the site at end of each days work.
- B. Atmospheric and Surface Conditions:
  - L. Do not apply coating when air or substrate conditions are:
    - a. Less than 3°C (5°F) above dew point.
    - b. Below 10°C (50°F) or over 35°C (95°F), unless specifically pre-approved by the Contracting Officer and the product manufacturer. Under no circumstances shall application conditions exceed manufacturer recommendations.
  - 2. Maintain interior temperatures until paint dries hard.
  - 3. Do not paint in direct sunlight or on surfaces that the sun will soon warm.
  - 4. Apply only on clean, dry and frost free surfaces.

## 3.2 SURFACE PREPARATION

- A. Method of surface preparation is optional, provided results of finish painting produce solid even color and texture specified with no overlays.
- B. General:
  - 1. Remove prefinished items not to be painted such as lighting fixtures, escutcheon plates, hardware, trim, and similar items for reinstallation after paint is dried.
  - Remove items for reinstallation and complete painting of such items and adjacent areas when item or adjacent surface is not accessible or finish is different.
  - 3. See other sections of specifications for specified surface conditions and prime
  - 4. Clean surfaces for painting with materials and methods compatible with substrate and specified finish. Remove any residue remaining from cleaning agents used. Do not use solvents, acid, or steam on concrete and masonry.
- C. Wood:
  - 1. Sand to a smooth even surface and then dust off.
  - 2. Sand surfaces showing raised grain smooth between each coat.
  - 3. Wipe surface with a tack rag prior to applying finish.

- 4. Surface painted with an opaque finish:
  - a. Coat knots, sap and pitch streaks with MPI 36 (Knot Sealer) before applying paint.
  - b. Apply two coats of MPI 36 (Knot Sealer) over large knots.
- 5. After application of prime or first coat of stain, fill cracks, nail and screw holes, depressions and similar defects with wood filler paste. Sand the surface to make smooth and finish flush with adjacent surface.
- 6. Before applying finish coat, reapply wood filler paste if required, and sand surface to remove surface blemishes. Finish flush with adjacent surfaces.
- 7. Fill open grained wood such as oak, walnut, ash and mahogany with MPI 91 (Wood Filler Paste), colored to match wood color.
  - a. Thin filler in accordance with manufacturer's instructions for application.
  - b. Remove excess filler, wipe as clean as possible, dry, and sand as specified.

#### D. Ferrous Metals:

- Remove oil, grease, soil, drawing and cutting compounds, flux and other detrimental foreign matter in accordance with SSPC-SP 1 (Solvent Cleaning).
- Remove all mill scale, rust, and paint, by hand or power tool cleaning, as defined in SSPC-SP 2 (Hand Tool Cleaning) and SSPC-SP 3 (Power Tool Cleaning).
   Remove all paint and coatings from existing door frames to expose bare metal.
- 3. Fill dents, holes and similar voids and depressions in flat exposed surfaces of hollow steel doors and frames, access panels, roll-up steel doors and similar items specified to have semi-gloss or gloss finish with TT-F-322D (Filler, Two-Component Type, For Dents, Small Holes and Blow-Holes). Finish flush with adjacent surfaces.
  - a. This includes flat head countersunk screws used for permanent anchors.
  - b. Do not fill screws of item intended for removal such as glazing beads.
- 4. Spot prime abraded and damaged areas in shop prime coat which expose bare metal with same type of paint used for prime coat. Feather edge of spot prime to produce smooth finish coat.
- 5. Spot prime abraded and damaged areas which expose bare metal of factory finished items with paint as recommended by manufacturer of item.
- E. Zinc-Coated (Galvanized) Metal Surfaces Specified Painted:
  - Clean surfaces to remove grease, oil and other deterrents to paint adhesion in accordance with SSPC-SP 1 (Solvent Cleaning).
  - Spot coat abraded and damaged areas of zinc-coating which expose base metal on hot-dip zinc-coated items with MPI 18 (Organic Zinc Rich Coating). Prime or spot prime with MPI 134 (Waterborne Galvanized Primer) or MPI 135 (Non-Cementitious Galvanized Primer) depending on finish coat compatibility.
- F. Masonry, Concrete, and Cement Plaster:
  - 1. Clean and remove dust, dirt, oil, grease efflorescence, form release agents, laitance, and other deterrents to paint adhesion.
  - 2. Use emulsion type cleaning agents to remove oil, grease, paint and similar products. Use of solvents, acid, or steam is not permitted.
  - 3. Remove loose mortar in masonry work.

4. Replace mortar and fill open joints, holes, cracks and depressions with new mortar. Finish to match adjacent surfaces.

## G. Gypsum Board:

- 1. Remove efflorescence, loose and chalking plaster or finishing materials.
- 2. Remove dust, dirt, and other deterrents to paint adhesion.
- 3. Fill holes, cracks, and other depressions with CID-A-A-1272A (Spackling Compound) finished flush with adjacent surface, with texture to match texture of adjacent surface. Patch holes over 25 mm (1-inch) in diameter as specified in Section for plaster or gypsum board.

#### 3.3 PAINT PREPARATION

- A. Thoroughly mix painting materials to ensure uniformity of color, complete dispersion of pigment and uniform composition.
- B. Do not thin unless necessary for application and when finish paint is used for body and prime coats. Use materials and quantities for thinning as specified in manufacturer's printed instructions.
- C. Remove paint skins, then strain paint through commercial paint strainer to remove lumps and other particles.
- D. Mix two component and two part paint and those requiring additives in such a manner as to uniformly blend as specified in manufacturer's printed instructions unless specified otherwise.
- E. For tinting required to produce exact shades specified, use color pigment recommended by the paint manufacturer.

## 3.4 APPLICATION

- A. Start of surface preparation or painting will be construed as acceptance of the surface as satisfactory for the application of materials.
- B. Unless otherwise specified, apply paint in three coats; prime, body, and finish. When two coats applied to prime coat are the same, first coat applied over primer is body coat and second coat is finish coat.
- C. Apply each coat evenly and cover substrate completely.
- D. Allow not less than 48 hours between application of succeeding coats, except as allowed by manufacturer's printed instructions, and approved by COR.
- E. Finish surfaces to show solid even color, free from runs, lumps, brush marks, laps, holidays, or other defects.
- F. Apply by brush, roller or spray, except as otherwise specified.
- G. Do not spray paint in existing occupied spaces unless approved by COR, except in spaces sealed from existing occupied spaces.

1. Apply painting materials specifically required by manufacturer to be applied by spraying.

- In areas, where paint is applied by spray, mask or enclose with polyethylene, or similar air tight material with edges and seams continuously sealed including items specified in WORK NOT PAINTED, motors, controls, telephone, and electrical equipment, fronts of sterilizes and other recessed equipment and similar pre-finished items.
- H. Do not paint operable items in closed position.

#### 3.5 PRIME PAINTING

- A. After surface preparation prime surfaces before application of body and finish coats, except as otherwise specified.
- B. Spot prime and apply body coat to damaged and abraded painted surfaces before applying succeeding coats.
- C. Additional field applied prime coats over shop or factory applied prime coats are not required except for exterior exposed steel apply an additional prime coat.
- D. Prime rebates for stop and face glazing of wood, and for face glazing of steel.
- E. Wood and Wood Particleboard:
  - 1. Use same kind of primer specified for exposed face surface.
    - a. Interior wood except for transparent finish: MPI 45 (Interior Primer Sealer) or MPI 46 (Interior Enamel Undercoat), thinned if recommended by manufacturer.
    - b. Transparent finishes as specified under Transparent Finishes on Wood.
  - 2. Apply one coat of sealer MPI 45 (Interior Primer Sealer) or MPI 46 (Interior Enamel Undercoat) as soon as delivered to site to surfaces of unfinished woodwork, except concealed surfaces of shop fabricated or assembled millwork and surfaces specified to have varnish, stain or natural finish.
- F. Metals:
  - 1. Steel and Iron: MPI 95 (Fast Drying Metal Primer) finish is specified
  - 2. Zinc-Coated Steel and Iron: MPI 134 (Waterborne Galvanized Primer) or MPI 135 (Non-Cementitious Galvanized Primer)
  - 3. Aluminum scheduled to be painted: MPI 95 (Fast Drying Metal Primer)
  - 4. Machinery not factory finished: MPI 9 (Exterior Alkyd Enamel (EO))
- G. Gypsum Board:
  - 1. Primer: MPI 50(Interior Latex Primer Sealer)
- H. Concrete Masonry Units:
  - MPI 4 (Block Filler) on interior surfaces
- I. Cement Plaster Interior Surfaces of Ceilings and Walls:
  - 1. MPI 50 (Interior Latex Primer Sealer, MPI Gloss Level 3 (LL) except use two coats where substrate has aged less than six months.

#### 3.6 INTERIOR FINISHES

A. Apply following finish coats over prime coats in spaces or on surfaces specified in the material schedule in the drawings.

#### B. Metal Work:

- 1. Apply to exposed surfaces.
- 2. Omit body and finish coats on surfaces concealed after installation.
- 3. Ferrous Metal, Galvanized Metal, and Other Metals Scheduled:
  - a. Apply two coats of MPI 54 (Interior Latex, Semi-Gloss (LE)) unless specified otherwise.

## C. Gypsum Board:

1. One coat of MPI 50 (Interior Latex Primer Sealer) plus two coats of MPI 139 (Interior High Performance Latex, MPI Gloss Level 3 (LL)); Omit primer sealer on previously paint gypsum board.

#### D. Plaster:

- 1. One coat of MPI 50 (Interior Latex Primer Sealer) plus one coat of MPI 139 (Interior High Performance Latex, MPI Gloss level 3 (LL)).
- E. Masonry and Concrete Walls:
  - 1. Over MPI 4 (Interior/Exterior Latex Block Filler) on CMU surfaces
  - 2. Two coats of MPI 54 (Interior Latex, Semi-Gloss, MPI Gloss Level 5 (LE))

#### F. Wood:

- 1. Sanding:
  - a. Use 220-grit sandpaper.
  - b. Sand sealers and varnish/polyurethane between coats.
  - Sand enough to scarify surface to assure good adhesion of subsequent coats, to level roughly applied sealer and varnish, and to knock off "whiskers" of any raised grain as well as dust particles.

#### 2. Sealers:

- a. Apply sealers specified except sealer may be omitted where pigmented, penetrating, or wiping stains containing resins are used.
- b. Allow manufacturer's recommended drying time before sanding, but not less than 24 hours or 36 hours in damp or muggy weather.
- c. Sand as specified.

## 3. Paint Finish:

- a. One coat of MPI 45 (Interior Primer Sealer) or MPI 46 (Interior Enamel Undercoat) plus two coats of MPI 47 (Interior Alkyd, Semi-Gloss (AK)) (SG).
- 4. Transparent Finishes on Wood Except Floors.
  - a. Natural Finish:
    - 1) One coat of sealer as written in 2.1 E.
    - Two coats of MPI 71 (Polyurethane, Moisture Cured, and Clear Flat (PV), MPI 31 (Polyurethane, Moisture Cured, Clear Gloss (PV); or see drawings & finish schedule.
  - b. Stain Finish:

- 1) One coat of MPI 90 (Interior Wood Stain, Semi-Transparent (WS)).
- Use wood stain of type and color required to achieve finish specified. Do not use varnish type stains.
- 3) One coat of sealer as written in 2.1 E.
- 4) Two coats of MPI 71 (Polyurethane, Moisture Cured, Clear Flat (PV) or MPI 31 (Polyurethane Moisture Cured, Clear Gloss (PV)); see drawings & finish schedule.

#### 3.7 REFINISHING EXISTING PAINTED SURFACES

- A. Clean, patch and repair existing surfaces as specified under surface preparation.
- B. Remove and reinstall items as specified under surface preparation.
- C. Remove existing finishes or apply separation coats to prevent non compatible coatings from having contact.
- D. Patched or Replaced Areas in Surfaces and Components: Apply spot prime and body coats as specified for new work to repaired areas or replaced components.
- E. Except where scheduled for complete painting apply finish coat over plane surface to nearest break in plane, such as corner, reveal, or frame.
- F. Within the project area, repaint all existing painted surfaces in existing rooms where alterations occur, unless noted otherwise.
- G. Refinish areas as specified for new work to match adjoining work unless specified or scheduled otherwise.
- H. Sand or dull glossy surfaces prior to painting.
- I. Sand existing coatings to a feather edge so that transition between new and existing finish will not show in finished work.

## 3.8 PAINT COLOR

- A. Color and gloss of finish coats is specified in the Material Schedule on drawing A-1 and the Room Finish Schedule on drawing A-3.
- B. For additional requirements regarding color see Articles, REFINISHING EXISTING PAINTED SURFACE and MECHANICAL AND ELECTRICAL FIELD PAINTING SCHEDULE.
- C. Coat Colors:
  - 1. Color of priming coat: Lighter than body coat.
  - 2. Color of body coat: Lighter than finish coat.
  - 3. Color prime and body coats to not show through the finish coat and to mask surface imperfections or contrasts.

- D. Painting, Caulking, Closures, and Fillers Adjacent to Casework:
  - 1. Paint to match color of casework where casework has a paint finish.
  - 2. Paint to match color of wall where casework is stainless steel, plastic laminate, or varnished wood.

#### 3.9 MECHANICAL AND ELECTRICAL WORK FIELD PAINTING SCHEDULE

- A. Field painting of mechanical and electrical consists of cleaning, touching-up abraded shop prime coats, and applying prime, body and finish coats to materials and equipment if not factory finished in space scheduled to be finished.
- B. Paint various systems specified in Divisions 15 and 16.
- C. Paint after tests have been completed.
- D. Omit prime coat from factory prime-coated items.
- E. Finish painting of mechanical and electrical equipment is not required when located in interstitial spaces, above suspended ceilings, in concealed areas such as pipe and electric closets, chases, shafts and furred spaces.
- F. Omit field painting of items specified in paragraph, Building and Structural WORK NOT PAINTED.
- G. Color:
  - 1. Paint items having no color specified in the Material and Room Finish Schedules to match surrounding surfaces.
  - 2. Paint colors as specified in the Materials and Room Finish Schedules except for following:
    - a. Gray: Heating, ventilating, air conditioning and refrigeration equipment (except as required to match surrounding surfaces).
    - Federal Safety Red: Exposed fire protection piping hydrants, post indicators, electrical conducts containing fire alarm control wiring, and fire alarm equipment.
- H. Apply paint systems on properly prepared and primed surface as follows:
  - 1. Interior Locations:
    - a. Apply two coats of MPI 47 (Interior Alkyd, Semi-Gloss (AK)) to following items:
      - 1) Metal under  $94^{\circ}\text{C}$  ( $200^{\circ}\text{F}$ ) of items such as bare piping, fittings, hangers and supports.
      - 2) Equipment and systems such as hinged covers and frames for control cabinets and boxes, castiron radiators, electric conduits and panel boards.
      - 3) Heating, ventilating, air conditioning, plumbing equipment, and machinery having shop prime coat and not factory finished.

#### 3.10 BUILDING AND STRUCTURAL WORK FIELD PAINTING

A. Painting and finishing of interior work except as specified under Paragraph B, below.

- 1. Painting and finishing of new and existing work including colors and gloss of finish selected is specified in the Material and Room Finish Schedules.
- 2. Painting of disturbed, damaged and repaired or patched surfaces when entire space is not scheduled for complete repainting or refinishing.
- 3. Painting of ferrous metal and galvanized metal.
- 4. Identity painting and safety painting.
- B. Building and Structural Work not painted:
  - Prefinished items:
    - Casework, doors, wall rails and corner guards, metal panels, wall covering, and similar items specified factory finished under other sections
    - b. Factory finished equipment.
  - 2. Finished surfaces:
    - a. Hardware except ferrous metal.
    - b. Anodized aluminum, stainless steel, chromium plating, copper, and brass, except as otherwise specified.
    - c. Signs, fixtures, and other similar items integrally finished.
  - 3. Concealed surfaces:
    - a. Inside chases, shafts, interstitial spaces, and above ceilings, except as otherwise specified.
    - b. Inside walls or other spaces behind access doors or panels.
    - c. Surfaces concealed behind permanently installed casework and equipment.
  - 4. Moving and operating parts:
    - a. Shafts, chains, gears, mechanical and electrical operators, linkages, and sprinkler heads, and sensing devices.
    - b. Tracks for overhead or coiling doors, shutters, and grilles.
  - 5. Labels:
    - a. Code required label, such as Underwriters Laboratories Inc., Inchcape Testing Services, Inc., or Factory Mutual Research Corporation.
    - b. Identification plates, instruction plates, performance rating, and nomenclature.

#### 3.11 IDENTITY PAINTING SCHEDULE

- A. Identify designated service in accordance with ANSI Al3.1, unless specified otherwise, on exposed piping, piping above removable ceilings, piping in accessible pipe spaces, interstitial spaces, and piping behind access panels.
  - 1. Legend may be identified using 2.1 G options or by stencil applications.
  - 2. Apply legends adjacent to changes in direction, on branches, where pipes pass through walls or floors, adjacent to operating accessories such as valves, regulators, strainers and cleanouts a minimum of 40 feet apart on straight runs of piping. Identification next to plumbing fixtures is not required.
  - 3. Locate Legends clearly visible from operating position.

- 4. Use arrow to indicate direction of flow.
- 5. Legend name in full or in abbreviated form as follows:

PIPING	COLOR EXPOSEI	OF O PIPING	COLOR BACKGR		COLOR LETTER		LEGENI ABBREV	O TIATIONS
Chilled Water Su	pply			Green		White		CHWS
Chilled Water Re	turn			Green		White		CHWR
High Pressure St	eam			Yello	W	Black		HPS
High Pressure Co	ndensate	Return		Yello	W	Black		HPC
Low Pressure Ste	am			Yello	W	Black		LPS
Low Pressure Con	densate l	Return		Yello	W	Black		LPC
Hot Glycol Solut	ion Supp	ly		Yello	W	Black		HGS
Hot Glycol Solut	ion Retu	rn		Yello	W	Black		HGR
Pumped Condensat	e			Black				PC
Vent Line				Yello	W	Black		Vent
Cold Water (Dome	stic)	White		Green		White		DCW
Hot Water (Domes	tic)							
Supply		White		Yello	W	Black		DHW
Return		White		Yello	W	Black		DHWR
Sanitary Waste				Green		White		San Waste
Sanitary Vent			Green		White		San Vent	
Storm Drainage				Green		White		St Drain
Fire Protection	Water							
Sprinkler				Red		White		Auto Spr
Standpipe				Red		White		Stand
Sprinkler				Red		White		Drain

- B. Fire and Smoke Partitions:
  - 1. Identify partitions above ceilings on both sides of partitions except within shafts in letters not less than 64 mm (2 1/2 inches) high.
  - 2. Stenciled message: "SMOKE PARTITION" or, "FIRE PARTITION" as applicable.
  - 3. Locate not more than 6100 mm (20 feet) on center on corridor sides of partitions, and with a least one message per room on room side of partition.
  - 4. Use semi-gloss paint of color that contrasts with color of substrate.

## 3.12 PROTECTION CLEAN UP, AND TOUCH-UP

- A. Protect work from paint droppings and spattering by use of masking, drop cloths, removal of items or by other approved methods.
- B. Upon completion, clean paint from hardware, glass and other surfaces and items not required to be painted of paint drops or smears.
- C. Before final inspection, touch-up or refinished in a manner to produce solid even color and finish texture, free from defects in work which was damaged or discolored.

## END OF SECTION 09 91 00



# SECTION 23 05 11 COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. The requirements of this Section apply to all sections of Division 23.
- B. Definitions:
  - 1. Exposed: Piping, ductwork, and equipment exposed to view in finished rooms.
  - 2. Option or optional: Contractor's choice of an alternate material or method.
  - 3. RE: COR
  - 4. COR: Contracting Officer's Technical Representative.

## 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS

#### 1.3 QUALITY ASSURANCE

- A. Mechanical, electrical and associated systems shall be safe, reliable, efficient, durable, easily and safely operable and maintainable, easily and safely accessible, and in compliance with applicable codes as specified. The systems shall be comprised of high quality institutional-class and industrial-class products of manufacturers that are experienced specialists in the required product lines. All construction firms and personnel shall be experienced and qualified specialists in industrial and institutional HVAC or steam boiler plant construction, as applicable.
- B. Flow Rate Tolerance for HVAC Equipment: Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.

## C. Products Criteria:

- 1. Standard Products: Material and equipment shall be the standard products of a manufacturer regularly engaged in the manufacture of the products for at least 3 years. The design, model and size of each item shall have been in satisfactory and efficient operation on at least three installations for approximately three years. However, digital electronics devices, software and systems such as controls, instruments, computer work station, shall be the current generation of technology and basic design that has a proven satisfactory service record of at least three years. See other specification sections for any exceptions.
- 2. All items furnished shall be free from defects that would adversely affect the performance, maintainability and appearance of individual components and overall assembly.
- 3. Conform to codes and standards as required by the specifications. Conform to local codes, if required by local authorities such as the natural gas supplier, if the local codes are more stringent then those specified. Refer any conflicts to the COR (RE)/Contracting Officers Technical Representative (COR).

4. Multiple Units: When two or more units of materials or equipment of the same type or class are required, these units shall be products of one manufacturer.

- 5. Assembled Units: Manufacturers of equipment assemblies, which use components made by others, assume complete responsibility for the final assembled product.
- 6. Nameplates: Nameplate bearing manufacturer's name or identifiable trademark shall be securely affixed in a conspicuous place on equipment, or name or trademark cast integrally with equipment, stamped or otherwise permanently marked on each item of equipment.
- 7. Asbestos products or equipment or materials containing asbestos shall not be used.

## D. Equipment Service Organizations:

- 1. HVAC: Products and systems shall be supported by service organizations that maintain a complete inventory of repair parts and are located reasonably close to the site.
- E. HVAC Mechanical Systems Welding: Before any welding is performed, contractor shall submit a certificate certifying that welders comply with the following requirements:
  - 1. Qualify welding processes and operators for piping according to ASME "Boiler and Pressure Vessel Code", Section IX, "Welding and Brazing Qualifications".
  - 2. Comply with provisions of ASME B31 series "Code for Pressure Piping".
  - 3. Certify that each welder has passed American Welding Society (AWS) qualification tests for the welding processes involved, and that certification is current.

## F. Execution (Installation, Construction) Quality:

- Apply and install all items in accordance with manufacturer's written instructions. Refer
  conflicts between the manufacturer's instructions and the contract drawings and
  specifications to the COR for resolution. Provide written hard copies or computer files of
  manufacturer's installation instructions to the COR at least two weeks prior to commencing
  installation of any item. Installation of the item will not be allowed to proceed until the
  recommendations are received. Failure to furnish these recommendations is a cause for
  rejection of the material.
- 2. All items that require access, such as for operating, cleaning, servicing, maintenance, and calibration, shall be easily and safely accessible by persons standing at floor level, or standing on permanent platforms, without the use of portable ladders. Examples of these items include, but are not limited to: all types of valves, filters and strainers, transmitters, control devices. Prior to commencing installation work, refer conflicts between this requirement and contract drawings to the COR for resolution.
- 3. Provide complete layout drawings required by Paragraph, SUBMITTALS. Do not commence construction work on any system until the layout drawings have been approved.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, and with requirements in the individual specification sections.
- B. Contractor shall make all necessary field measurements and investigations to assure that the equipment and assemblies will meet contract requirements.

C. If equipment is submitted which differs in arrangement from that shown, provide drawings that show the rearrangement of all associated systems. Approval will be given only if all features of the equipment and associated systems, including accessibility, are equivalent to that required by the contract.

- D. Prior to submitting shop drawings for approval, contractor shall certify in writing that manufacturers of all major items of equipment have each reviewed drawings and specifications, and have jointly coordinated and properly integrated their equipment and controls to provide a complete and efficient installation.
- E. Upon request by Government, provide lists of previous installations for selected items of equipment. Include contact persons who will serve as references, with telephone numbers and e-mail addresses.
- F. Submittals and shop drawings for interdependent items, containing applicable descriptive information, shall be furnished together and complete in a group. Coordinate and properly integrate materials and equipment in each group to provide a completely compatible and efficient installation. Final review and approvals will be made only by groups.
- G. Manufacturer's Literature and Data: Submit under the pertinent section rather than under this section.
  - 1. Submit belt drive with the driven equipment. Submit selection data for specific drives when requested by the COR.
  - 2. Submit electric motor data and variable speed drive data with the driven equipment.
  - 3. Equipment and materials identification.
  - 4. Fire-stopping materials.
  - 5. Wall, floor, and ceiling plates.
- H. HVAC Maintenance Data and Operating Instructions:
  - 1. Maintenance and operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS, Article, INSTRUCTIONS, for systems and equipment.
  - Provide a listing of recommended replacement parts for keeping in stock supply, including sources of supply, for equipment. Include in the listing belts for equipment: Belt manufacturer, model number, size and style, and distinguished whether of multiple belt sets.

## 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. Air Conditioning and Refrigeration Institute (ARI): 430-99.....Central Station Air-Handling Units
- C. American National Standard Institute (ANSI): B31.1-2004 ....... Power Piping
- D. Rubber Manufacturers Association (ANSI/RMA):

  IP-20-2007 ...... Drives Using Classical V-Belts and Sheaves

	IP-21-1991(1997) Drives Using Double-V (Hexagonal) Belts IP-22-2007 Drives Using Narrow V-Belts and Sheaves
Ε.	Air Movement and Control Association (AMCA): 410-96Recommended Safety Practices for Air Moving Devices
F.	American Society of Mechanical Engineers (ASME): Boiler and Pressure Vessel Code (BPVC): Section I-2007
G.	American Society for Testing and Materials (ASTM):  A36/A36M-05
Н.	Manufacturers Standardization Society (MSS) of the Valve and Fittings Industry, Inc:  SP-58-2002
J.	National Electrical Manufacturers Association (NEMA): MG-1-2006 Motors and Generators
К.	National Fire Protection Association (NFPA):  31-06

## 1.6 DELIVERY, STORAGE AND HANDLING

- A. Protection of Equipment:
  - 1. Equipment and material placed on the job site shall remain in the custody of the Contractor until phased acceptance, whether or not the Government has reimbursed the Contractor for the equipment and material. The Contractor is solely responsible for the protection of such equipment and material against any damage.
  - 2. Place damaged equipment in first class, new operating condition; or, replace same as determined and directed by the COR. Such repair or replacement shall be at no additional cost to the Government.

3. Protect interiors of new equipment and piping systems against entry of foreign matter. Clean both inside and outside before painting or placing equipment in operation.

- 4. Existing equipment and piping being worked on by the Contractor shall be under the custody and responsibility of the Contractor and shall be protected as required for new work.
- B. Cleanliness of Piping and Equipment Systems:
  - 1. Exercise care in storage and handling of equipment and piping material to be incorporated in the work. Remove debris arising from cutting, threading and welding of piping.
  - 2. Piping systems shall be flushed, blown or pigged as necessary to deliver clean systems.
  - 3. Clean interior of all tanks prior to delivery for beneficial use by the Government.
  - 4. Contractor shall be fully responsible for all costs, damage, and delay arising from failure to provide clean systems.

#### PART 2 - PRODUCTS

#### 2.1 FACTORY-ASSEMBLED PRODUCTS

- A. Provide maximum standardization of components to reduce spare part requirements.
- B. Manufacturers of equipment assemblies that include components made by others shall assume complete responsibility for final assembled unit.
  - 1. All components of an assembled unit need not be products of same manufacturer.
  - 2. Constituent parts that are alike shall be products of a single manufacturer.
  - 3. Components shall be compatible with each other and with the total assembly for intended service.
  - 4. Contractor shall guarantee performance of assemblies of components, and shall repair or replace elements of the assemblies as required to deliver specified performance of the complete assembly.
- C. Components of equipment shall bear manufacturer's name and trademark, model number, serial number and performance data on a name plate securely affixed in a conspicuous place, or cast integral with, stamped or otherwise permanently marked upon the components of the equipment.
- D. Major items of equipment, which serve the same function, must be the same make and model. Exceptions will be permitted if performance requirements cannot be met.

## 2.2 COMPATIBILITY OF RELATED EQUIPMENT

Equipment and materials installed shall be compatible in all respects with other items being furnished and with existing items so that the result will be a complete and fully operational plant that conforms to contract requirements.

#### 2.3 BELT DRIVES

- A. Type: ANSI/RMA standard V-belts with proper motor pulley and driven sheave. Belts shall be constructed of reinforced cord and rubber.
- B. Dimensions, rating and selection standards: ANSI/RMA IP-20 and IP-21.

C. Minimum Horsepower Rating: Motor horsepower plus recommended ANSI/RMA service factor (not less than 20 percent) in addition to the ANSI/RMA allowances for pitch diameter, center distance, and arc of contact.

- D. Maximum Speed: 25 m/s (5000 feet per minute).
- E. Adjustment Provisions: For alignment and ANSI/RMA standard allowances for installation and take-up.
- F. Drives may utilize a single V-Belt (any cross section) when it is the manufacturer's standard.
- G. Multiple Belts: Matched to ANSI/RMA specified limits by measurement on a belt measuring fixture. Seal matched sets together to prevent mixing or partial loss of sets. Replacement, when necessary, shall be an entire set of new matched belts.
- H. Sheaves and Pulleys:
  - 1. Material: Pressed steel, or close grained cast iron.
  - 2. Bore: Fixed or bushing type for securing to shaft with keys.
  - 3. Balanced: Statically and dynamically.
  - 4. Groove spacing for driving and driven pulleys shall be the same.
  - 5. Minimum Diameter of V-Belt Sheaves (ANSI/RMA recommendations)in millimeters and inches:

Fract	ional	St	andard	High Capacity					
Horse	power								
Cross	Min. od	Cross	Min. od	Cross	Min. od				
Section	mm (in)	Section	mm (in)	Section	mm (in)				
2L	20 (0.8)	А	83 (3.25)	3V	67 (2.65)				
3L	38 (1.5)	В	146 (5.75)	4V	180 (7.10)				
4L	64 (2.5)	С	239 (9.40)	5V	318 (12.50)				
5L	89 (3.5)	D	345 (13.60)						
		E	554 (21.80)						

- I. Drive Types, Based on ARI 435:
  - 1. Provide adjustable-pitch or fixed-pitch drive as follows:
    - a. Fan speeds up to 1800 RPM: 7.5 kW (10 horsepower) and smaller.
    - b. Fan speeds over 1800 RPM: 2.2 kW (3 horsepower) and smaller.
  - 2. Provide fixed-pitch drives for drives larger than those listed above.
  - 3. The final fan speeds required to just meet the system CFM and pressure requirements, without throttling, shall be determined by adjustment of a temporary adjustable-pitch motor sheave or by fan law calculation if a fixed-pitch drive is used initially.

## 2.4 DRIVE GUARDS

A. For machinery and equipment, provide guards as shown in AMCA 410 for belts, chains, couplings, pulleys, sheaves, shafts, gears and other moving parts regardless of height above the floor to prevent damage to equipment and injury to personnel. Drive quards may be excluded where motors and drives are inside factory fabricated air handling unit casings.

B. V-belt and sheave assemblies shall be totally enclosed, firmly mounted, non-resonant. Guard shall be an assembly of minimum 22-gage sheet steel and expanded or perforated metal to permit observation of belts. 25 mm (one-inch) diameter hole shall be provided at each shaft centerline to permit speed measurement.

- C. Materials: Sheet steel, cast iron, expanded metal or wire mesh rigidly secured so as to be removable without disassembling pipe, duct, or electrical connections to equipment.
- D. Access for Speed Measurement: 25 mm (One inch) diameter hole at each shaft center.

#### 2.5 LIFTING ATTACHMENTS

Provide equipment with suitable lifting attachments to enable equipment to be lifted in its normal position. Lifting attachments shall withstand any handling conditions that might be encountered, without bending or distortion of shape, such as rapid lowering and braking of load.

#### 2.6 ELECTRIC MOTORS

- A. Provide all electrical wiring, conduit, and devices necessary for the proper connection, protection and operation of the systems. Provide special energy efficient motors as scheduled. Unless otherwise specified for a particular application use electric motors with the following requirements.
- B. Single-phase Motors: Capacitor-start type for hard starting applications. Motors for centrifugal fans and pumps may be split phase or permanent split capacitor (PSC).
- C. Poly-phase Motors: NEMA Design B, Squirrel cage, induction type. Each two-speed motor shall have two separate windings. Provide a time- delay (20 seconds minimum) relay for switching from high to low speed.
- D. Rating: Continuous duty at 100 percent capacity in an ambient temperature of 40 degrees centigrade (104 degrees F); minimum horsepower as shown on drawings; maximum horsepower in normal operation not to exceed nameplate rating without service factor.

## E. Special Requirements:

- 1. Where motor power requirements of equipment furnished deviate from power shown on plans, provide electrical service designed under the requirements of NFPA 70 without additional time or cost to the Government.
- 2. Assemblies of motors, starters, controls and interlocks on factory assembled and wired devices shall be in accordance with the requirements of this specification.
- 3. Wire and cable materials specified in the electrical division of the specifications shall be
  - a. Wiring material located where temperatures can exceed 71 degrees C (160 degrees F) shall be stranded copper with Teflon FEP insulation with jacket. This includes wiring on
  - b. Other wiring at boilers and to control panels shall be NFPA 70 designation THWN.

c. Provide shielded conductors or wiring in separate conduits for all instrumentation and control systems where recommended by manufacturer of equipment.

- 4. Select motor sizes so that the motors do not operate into the service factor at maximum required loads on the driven equipment. Motors on pumps shall be sized for non-overloading at all points on the pump performance curves.
- 5. Motors utilized with variable frequency drives shall be rated "inverter-ready" per NEMA Standard, MG1, Part 31.4.4.2. Provide motor shaft grounding apparatus that will protect bearings from damage from stray currents.
- F. Motor Efficiency and Power Factor: All motors, when specified as "high efficiency" by the project specifications on driven equipment, shall conform to efficiency and power factor requirements in Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT, with no consideration of annual service hours. Motor manufacturers generally define these efficiency requirements as "NEMA premium efficient" and the requirements generally exceed those of the Energy Policy Act of 1992 (EPACT). Motors not specified as "high efficiency" shall comply with EPACT.
- G. Insulation Resistance: Not less than one-half meg-ohm between stator conductors and frame, to be determined at the time of final inspection.

#### 2.7 VARIABLE SPEED MOTOR CONTROLLERS

- A. The combination of controller and motor shall be provided by the manufacturer of the driven equipment, such as fans, and shall be rated for 100 percent output performance. Multiple units of the same class of equipment, i.e. air handlers, fans, pumps, shall be product of a single manufacturer.
- B. Motors shall be energy efficient type and be approved by the motor controller manufacturer. The controller-motor combination shall be guaranteed to provide full motor nameplate horsepower in variable frequency operation. Both driving and driven motor/fan sheaves shall be fixed pitch.
- C. Controller shall not add any current or voltage transients to the input AC power distribution system, DDC controls, sensitive medical equipment, etc., nor shall be affected from other devices on the AC power system.

## 2.8 EQUIPMENT AND MATERIALS IDENTIFICATION

- A. Use symbols, nomenclature and equipment numbers specified, shown on the drawings and shown in the maintenance manuals. Identification for piping is specified in Section 09 91 00, PAINTING.
- B. Interior (Indoor) Equipment: Engraved nameplates, with letters not less than 48 mm (3/16-inch) high of brass with black-filled letters, or rigid black plastic with white letters specified in Section 09 91 00, PAINTING permanently fastened to the equipment. Identify unit components such as coils, filters, fans, etc.
- C. Control Items: Label all temperature and humidity sensors, controllers and control dampers. Identify and label each item as they appear on the control diagrams.

#### 2.09 HVAC PIPE AND EQUIPMENT SUPPORTS AND RESTRAINTS

A. Pipe Supports: Comply with MSS SP-58. Type Numbers specified refer to this standard. For selection and application comply with MSS SP-69.

- B. Attachment to Concrete Building Construction:
  - 1. Concrete insert: MSS SP-58, Type 18.
  - 2. Self-drilling expansion shields and machine bolt expansion anchors: Permitted in concrete not less than 102 mm (four inches) thick when approved by the COR for each job condition.
  - 3. Power-driven fasteners: Permitted in existing concrete or masonry not less than 102 mm (four inches) thick when approved by the COR for each job condition.
- C. Attachment to Steel Building Construction:
  - 1. Welded attachment: MSS SP-58, Type 22.
  - 2. Beam clamps: MSS SP-58, Types 20, 21, 28 or 29. Type 23 C-clamp may be used for individual copper tubing up to 23mm (7/8-inch) outside diameter.
- D. Hanger Rods: Hot-rolled steel, ASTM A36 or A575 for allowable load listed in MSS SP-58. For piping, provide adjustment means for controlling level or slope. Types 13 or 15 turn-buckles shall provide 38 mm (1-1/2 inches) minimum of adjustment and incorporate locknuts. All-thread rods are acceptable.
- E. Hangers Supporting Multiple Pipes (Trapeze Hangers): Galvanized, cold formed, lipped steel channel horizontal member, not less than 41 mm by 41 mm (1-5/8 inches by 1-5/8 inches), 2.7 mm (No. 12 gage), designed to accept special spring held, hardened steel nuts. Not permitted for steam supply and condensate piping.
  - 1. Allowable hanger load: Manufacturers rating less 91kg (200 pounds).
  - 2. Guide individual pipes on the horizontal member of every other trapeze hanger with 6 mm (1/4-inch) U-bolt fabricated from steel rod. Provide Type 40 insulation shield, secured by two 13mm (1/2-inch) galvanized steel bands, or preinsulated calcium silicate shield for insulated piping at each hanger.
- F. Supports for Piping Systems:
  - Select hangers sized to encircle insulation on insulated piping. Refer to Section 23 07 11,
    HVAC, PLUMBING, AND BOILER PLANT INSULATION for insulation thickness. To protect
    insulation, provide Type 39 saddles for roller type supports or preinsulated calcium silicate
    shields. Provide Type 40 insulation shield or preinsulated calcium silicate shield at all other
    types of supports and hangers including those for preinsulated piping.
  - 2. Piping Systems except High and Medium Pressure Steam (MSS SP-58):
    - a. Standard clevis hanger: Type 1; provide locknut.
    - b. Riser clamps: Type 8.
    - c. Wall brackets: Types 31, 32 or 33.
    - d. Roller supports: Type 41, 43, 44 and 46.
    - e. Saddle support: Type 36, 37 or 38.
    - f. Turnbuckle: Types 13 or 15. Preinsulate.
    - g. U-bolt clamp: Type 24.
    - h. Copper Tube:

> 1) Hangers, clamps and other support material in contact with tubing shall be painted with copper colored epoxy paint, plastic coated or taped with non adhesive isolation tape to prevent electrolysis.

- 2) For vertical runs use epoxy painted or plastic coated riser clamps.
- 3) For supporting tube to strut: Provide epoxy painted pipe straps for copper tube or plastic inserted vibration isolation
- 4) Insulated Lines: Provide pre-insulated calcium silicate shields sized for copper tube.

#### 2.10 PIPE PENETRATIONS

- A. Install sleeves during construction for other than blocked out floor openings for risers in mechanical bays.
- B. To prevent accidental liquid spills from passing to a lower level, provide the following:
  - 1. For sleeves: Extend sleeve 25 mm (one inch) above finished floor and provide sealant for watertight joint.
  - 2. For blocked out floor openings: Provide 40 mm (1-1/2 inch) angle set in silicone adhesive around opening.
  - 3. For drilled penetrations: Provide 40 mm (1-1/2 inch) angle ring or square set in silicone adhesive around penetration.
- C. Penetrations are not allowed through beams or ribs, but may be installed in concrete beam flanges. Any deviation from these requirements must receive prior approval of COR.
- D. Sheet Metal, Plastic, or Moisture-resistant Fiber Sleeves: Provide for pipe passing through floors, interior walls, and partitions, unless brass or steel pipe sleeves are specifically called for below.
- E. Cast Iron or Zinc Coated Pipe Sleeves: Provide for pipe passing through exterior walls below grade. Make space between sleeve and pipe watertight with a modular or link rubber seal. Seal shall be applied at both ends of sleeve.
- F. Galvanized Steel or an alternate Black Iron Pipe with asphalt coating Sleeves: Provide for pipe passing through concrete beam flanges, except where brass pipe sleeves are called for. Provide sleeve for pipe passing through floor of mechanical rooms, laundry work rooms, and animal rooms above basement. Except in mechanical rooms, connect sleeve with floor plate.
- G. Brass Pipe Sleeves: Provide for pipe passing through quarry tile, terrazzo or ceramic tile floors. Connect sleeve with floor plate.
- H. Sleeves are not required for wall hydrants for fire department connections or in drywall construction.
- I. Sleeve Clearance: Sleeve through floors, walls, partitions, and beam flanges shall be one inch greater in diameter than external diameter of pipe. Sleeve for pipe with insulation shall be large enough to

accommodate the insulation. Interior openings shall be caulked tight with fire stopping material and sealant to prevent the spread of fire, smoke, and gases.

J. Sealant and Adhesives: Shall be as specified in Section 07 92 00, JOINT SEALANTS.

#### 2.11 SPECIAL TOOLS AND LUBRICANTS

- A. Furnish, and turn over to the COR, special tools not readily available commercially, that are required for disassembly or adjustment of equipment and machinery furnished.
- B. Grease Guns with Attachments for Applicable Fittings: One for each type of grease required for each motor or other equipment.
- C. Tool Containers: Hardwood or metal, permanently identified for in tended service and mounted, or located, where directed by the COR.
- D. Lubricants: A minimum of 0.95 L (one quart) of oil, and 0.45 kg (one pound) of grease, of equipment manufacturer's recommended grade and type, in unopened containers and properly identified as to use for each different application.

## 2.12 WALL, FLOOR AND CEILING PLATES

- A. Material and Type: Chrome plated brass or chrome plated steel, one piece or split type with concealed hinge, with set screw for fastening to pipe, or sleeve. Use plates that fit tight around pipes, cover openings around pipes and cover the entire pipe sleeve projection.
- B. Thickness: Not less than 2.4 mm (3/32-inch) for floor plates. For wall and ceiling plates, not less than 0.64 mm (0.025-inch) for up to 80 mm (3-inch pipe), 0.89 mm (0.035-inch) for larger pipe.
- C. Locations: Use where pipe penetrates floors, walls and ceilings in exposed locations, in finished areas only. Use also where insulation ends on exposed water supply pipe drop from overhead. Provide a watertight joint in spaces where brass or steel pipe sleeves are specified.

## 2.14 ASBESTOS

Materials containing asbestos are not permitted.

## PART 3 - EXECUTION

## 3.1 ARRANGEMENT AND INSTALLATION OF EQUIPMENT AND PIPING

A. Coordinate location of piping, sleeves, inserts, hangers, ductwork and equipment. Locate piping, sleeves, inserts, hangers, ductwork and equipment clear of windows, doors, openings, light outlets, and other services and utilities. Prepare equipment layout drawings to coordinate proper location and personnel access of all facilities. Submit the drawings for review as required by Part 1. Follow manufacturer's published recommendations for installation methods not otherwise specified.

B. Operating Personnel Access and Observation Provisions: Select and arrange all equipment and systems to provide clear view and easy access, without use of portable ladders, for maintenance and operation of all devices including, but not limited to: all equipment items, valves, filters, strainers, transmitters, sensors, control devices. All gages and indicators shall be clearly visible by personnel standing on the floor or on permanent platforms. Do not reduce or change maintenance and operating space and access provisions that are shown on the drawings.

- C. Equipment and Piping Support: Coordinate structural systems necessary for pipe and equipment support with pipe and equipment locations to permit proper installation.
- D. Location of pipe sleeves, trenches and chases shall be accurately coordinated with equipment and piping locations.
- E. Cutting Holes:
  - 1. Cut holes through concrete and masonry by rotary core drill. Pneumatic hammer, impact electric, and hand or manual hammer type drill will not be allowed, except as permitted by COR where working area space is limited.
  - Locate holes to avoid interference with structural members such as beams or grade beams.
     Holes shall be laid out in advance and drilling done only after approval by COR. If the
     Contractor considers it necessary to drill through structural members, this matter shall be
     referred to COR for approval.
- F. Minor Piping: Generally, small diameter pipe runs from drips and drains, water cooling, and other service are not shown but must be provided.
- G. Protection and Cleaning:
  - 1. Equipment and materials shall be carefully handled, properly stored, and adequately protected to prevent damage before and during installation, in accordance with the manufacturer's recommendations and as approved by the COR. Damaged or defective items in the opinion of the COR, shall be replaced.
  - 2. Protect all finished parts of equipment, such as shafts and bearings where accessible, from rust prior to operation by means of protective grease coating and wrapping. Close pipe openings with caps or plugs during installation. Tightly cover and protect fixtures and equipment against dirt, water chemical, or mechanical injury. At completion of all work thoroughly clean fixtures, exposed materials and equipment.
- H. Install gages, thermometers, valves and other devices with due regard for ease in reading or operating and maintaining said devices. Locate and position thermometers and gages to be easily read by operator or staff standing on floor or walkway provided. Servicing shall not require dismantling adjacent equipment or pipe work.
- I. Work in Existing Building:

1. As specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, OPERATIONS AND STORAGE AREAS, make alterations to existing service piping at times that will least interfere with normal operation of the facility.

- 2. Cut required openings through existing masonry and reinforced concrete using diamond core drills. Use of pneumatic hammer type drills, impact type electric drills, and hand or manual hammer type drills, will be permitted only with approval of the COR. Locate openings that will least effect structural slabs, columns, ribs or beams. Refer to the COR for determination of proper design for openings through structural sections and opening layouts approval, prior to cutting or drilling into structure. After COR's approval, carefully cut opening through construction no larger than absolutely necessary for the required installation.
- J. Switchgear Drip Protection: Every effort shall be made to eliminate the installation of pipe above electrical and telephone switchgear. If this is not possible, encase pipe in a second pipe with a minimum of joints.

## K. Inaccessible Equipment:

- Where the Government determines that the Contractor has installed equipment not conveniently accessible for operation and maintenance, equipment shall be removed and reinstalled or remedial action performed as directed at no additional cost to the Government.
- 2. The term "conveniently accessible" is defined as capable of being reached without the use of ladders, or without climbing or crawling under or over obstacles such as motors, fans, pumps, belt guards, transformers, high voltage lines, piping, and ductwork.

## 3.2 TEMPORARY PIPING AND EQUIPMENT

- A. Continuity of operation of existing facilities will generally require temporary installation or relocation of equipment and piping.
- B. The Contractor shall provide all required facilities in accordance with the requirements of phased construction and maintenance of service. All piping and equipment shall be properly supported, sloped to drain, operate without excessive stress, and shall be insulated where injury can occur to personnel by contact with operating facilities. The requirements of Para. 3.1 apply.
- C. Temporary facilities and piping shall be completely removed and any openings in structures sealed. Provide necessary blind flanges and caps to seal open piping remaining in service.

## 3.3 RIGGING

- A. Design is based on application of available equipment. Openings in building structures are planned to accommodate design scheme.
- B. Alternative methods of equipment delivery may be offered by Contractor and will be considered by Government under specified restrictions of phasing and maintenance of service as well as structural integrity of the building.

C. Close all openings in the building when not required for rigging operations to maintain proper environment in the facility for Government operation and maintenance of service.

- D. Contractor shall provide all facilities required to deliver specified equipment and place on foundations. Attachments to structures for rigging purposes and support of equipment on structures shall be Contractor's full responsibility. Upon request, the Government will check structure adequacy and advise Contractor of recommended restrictions.
- E. Contractor shall check all clearances, weight limitations and shall offer a rigging plan designed by a Registered Professional Engineer. All modifications to structures, including reinforcement thereof, shall be at Contractor's cost, time and responsibility.
- F. Rigging plan and methods shall be referred to COR for evaluation prior to actual work.
- G. Restore building to original condition upon completion of rigging work.

### 3.4 PIPE AND EQUIPMENT SUPPORTS

- A. Where hanger spacing does not correspond with joist or rib spacing, use structural steel channels secured directly to joist and rib structure that will correspond to the required hanger spacing, and then suspend the equipment and piping from the channels. Drill or burn holes in structural steel only with the prior approval of the COR.
- B. Use of chain, wire or strap hangers; wood for blocking, stays and bracing; or, hangers suspended from piping above will not be permitted. Replace or thoroughly clean rusty products and paint with zinc primer.
- C. Use hanger rods that are straight and vertical. Turnbuckles for vertical adjustments may be omitted where limited space prevents use. Provide a minimum of 15 mm (1/2-inch) clearance between pipe or piping covering and adjacent work.
- D. HVAC Horizontal Pipe Support Spacing: Refer to MSS SP-69. Provide additional supports at valves, strainers, in-line pumps and other heavy components. Provide a support within one foot of each elbow.
- E. HVAC Vertical Pipe Supports:
  - 1. Up to 150 mm (6-inch pipe), 9 m (30 feet) long, bolt riser clamps to the pipe below couplings, or welded to the pipe and rests supports securely on the building structure.
  - 2. Vertical pipe larger than the foregoing, support on base elbows or tees, or substantial pipe legs extending to the building structure.

## F. Overhead Supports:

- 1. The basic structural system of the building is designed to sustain the loads imposed by equipment and piping to be supported overhead.
- 2. Provide steel structural members, in addition to those shown, of adequate capability to support the imposed loads, located in accordance with the final approved layout of equipment and piping.
- 3. Tubing and capillary systems shall be supported in channel troughs.

## G. Floor Supports:

1. Provide concrete bases, concrete anchor blocks and pedestals, and structural steel systems for support of equipment and piping. Anchor and dowel concrete bases and structural systems to resist forces under operating and seismic conditions (if applicable) without excessive displacement or structural failure.

- 2. Do not locate or install bases and supports until equipment mounted thereon has been approved. Size bases to match equipment mounted thereon plus 50 mm (2 inch) excess on all edges. Boiler foundations shall have horizontal dimensions that exceed boiler base frame dimensions by at least 150 mm (6 inches) on all sides. Refer to structural drawings. Bases shall be neatly finished and smoothed, shall have chamfered edges at the top, and shall be suitable for painting.
- 3. All equipment shall be shimmed, leveled, firmly anchored, and grouted with epoxy grout. Anchor bolts shall be placed in sleeves, anchored to the bases. Fill the annular space between sleeves and bolts with a granular material to permit alignment and realignment.

### 3.5 MECHANICAL DEMOLITION

- A. Rigging access, other than indicated on the drawings, shall be provided by the Contractor after approval for structural integrity by the COR. Such access shall be provided without additional cost or time to the Government. Where work is in an operating plant, provide approved protection from dust and debris at all times for the safety of plant personnel and maintenance of plant operation and environment of the plant.
- B. In an operating plant, maintain the operation, cleanliness and safety. Government personnel will be carrying on their normal duties of operating, cleaning and maintaining equipment and plant operation. Confine the work to the immediate area concerned; maintain cleanliness and wet down demolished materials to eliminate dust. Do not permit debris to accumulate in the area to the detriment of plant operation. Perform all flame cutting to maintain the fire safety integrity of this plant. Adequate fire extinguishing facilities shall be available at all times. Perform all work in accordance with recognized fire protection standards. Inspection will be made by personnel of the VA Medical Center, and Contractor shall follow all directives of the RE or COR with regard to rigging, safety, fire safety, and maintenance of operations.
- C. Completely remove all piping, wiring, conduit, and other devices associated with the equipment not to be re-used in the new work. This includes all pipe, valves, fittings, insulation, and all hangers including the top connection and any fastenings to building structural systems. Seal all openings, after removal of equipment, pipes, ducts, and other penetrations in roof, walls, floors, in an approved manner and in accordance with plans and specifications where specifically covered. Structural integrity of the building system shall be maintained. Reference shall also be made to the drawings and specifications of the other disciplines in the project for additional facilities to be demolished or handled.
- D. All valves including gate, globe, ball, butterfly and check, all pressure gages and thermometers with wells shall remain Government

property and shall be removed and delivered to COR and stored as directed. The Contractor shall remove all other material and equipment, devices and demolition debris under these plans and specifications. Such material shall be removed from Government property expeditiously and shall not be allowed to accumulate.

E. Asbestos Insulation Removal: Conform to Section 02 82 11, TRADITIONAL ASBESTOS ABATEMENT.

#### 3.6 CLEANING AND PAINTING

- A. Prior to final inspection and acceptance of the plant and facilities for beneficial use by the Government, the plant facilities, equipment and systems shall be thoroughly cleaned and painted. Refer to Section 09 91 00, PAINTING.
- B. In addition, the following special conditions apply:
  - Cleaning shall be thorough. Use solvents, cleaning materials and methods recommended by the manufacturers for the specific tasks. Remove all rust prior to painting and from surfaces to remain unpainted. Repair scratches, scuffs, and abrasions prior to applying prime and finish coats.
  - 2. Material And Equipment Not To Be Painted Includes:
    - a. Motors, controllers, control switches, and safety switches.
    - b. Control and interlock devices.
    - c. Regulators.
    - d. Pressure reducing valves.
    - e. Control valves and thermostatic elements.
    - f. Lubrication devices and grease fittings.
    - g. Copper, brass, aluminum, stainless steel and bronze surfaces.
    - h. Valve stems and rotating shafts.
    - i. Pressure gauges and thermometers.
    - j. Glass.
    - k. Name plates.
  - 3. Control and instrument panels shall be cleaned, damaged surfaces repaired, and shall be touched-up with matching paint obtained from panel manufacturer.
  - 4. Pumps, motors, steel and cast iron bases, and coupling guards shall be cleaned, and shall be touched-up with the same color as utilized by the pump manufacturer
  - 5. Temporary Facilities: Apply paint to surfaces that do not have existing finish coats.
  - 6. Paint shall withstand the following temperatures without peeling or discoloration:
    - a. Condensate and feedwater -- 38 degrees C (100 degrees F) on insulation jacket surface and 120 degrees C (250 degrees F) on metal pipe surface.
    - Steam -- 52 degrees C (125 degrees F) on insulation jacket surface and 190 degrees C (375 degrees F) on metal pipe surface.
  - 7. Final result shall be smooth, even-colored, even-textured factory finish on all items. Completely repaint the entire piece of equipment if necessary to achieve this.

## 3.7 IDENTIFICATION SIGNS

A. Provide laminated plastic signs, with engraved lettering not less than 5 mm (3/16-inch) high, designating functions, for all equipment, switches, motor controllers, relays, meters, control devices, including

automatic control valves. Nomenclature and identification symbols shall correspond to that used in maintenance manual, and in diagrams specified elsewhere. Attach by chain, adhesive, or screws.

- B. Factory Built Equipment: Metal plate, securely attached, with name and address of manufacturer, serial number, model number, size, performance.
- C. Pipe Identification: Refer to Section 09 91 00, PAINTING.

#### 3.8 MOTOR AND DRIVE ALIGNMENT

- A. Belt Drive: Set driving and driven shafts parallel and align so that the corresponding grooves are in the same plane.
- B. Direct-connect Drive: Securely mount motor in accurate alignment so that shafts are free from both angular and parallel misalignment when both motor and driven machine are operating at normal temperatures.

#### 3.9 LUBRICATION

- A. Lubricate all devices requiring lubrication prior to initial operation. Field-check all devices for proper lubrication.
- B. Equip all devices with required lubrication fittings or devices. Provide a minimum of one liter (one quart) of oil and 0.5 kg (one pound) of grease of manufacturer's recommended grade and type for each different application; also provide 12 grease sticks for lubricated plug valves. Deliver all materials to COR in unopened containers that are properly identified as to application.
- C. Provide a separate grease gun with attachments for applicable fittings for each type of grease applied.
- D. All lubrication points shall be accessible without disassembling equipment, except to remove access plates.

## 3.10 STARTUP AND TEMPORARY OPERATION

Start up equipment as described in equipment specifications. Verify that vibration is within specified tolerance prior to extended operation. Temporary use of equipment is specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, TEMPORARY USE OF MECHANICAL AND ELECTRICAL EQUIPMENT.

## 3.11 OPERATING AND PERFORMANCE TESTS

- A. Prior to the final inspection, perform required tests as specified in Section 01 00 00, GENERAL REQUIREMENTS, Article, TESTS, and Section 23 08 11, DEMONSTRATIONS AND TESTS FOR BOILER PLANT, and submit the test reports and records to the COR.
- B. Should evidence of malfunction in any tested system, or piece of equipment or component part thereof, occur during or as a result of tests, make proper corrections, repairs or replacements, and repeat tests at no additional cost to the Government.
- C. When completion of certain work or system occurs at a time when final control settings and adjustments cannot be properly made to make

performance tests, then make performance tests for heating systems and for cooling systems respectively during first actual seasonal use of respective systems following completion of work.

## 3.12 DEMONSTRATIONS AND TESTS, TEMPORARY BOILER PLANT EQUIPMENT

- A. Test prior to placing in service.
- B. Demonstrate to COR the proper operation of all equipment, instruments, operating and safety controls, and devices.
- C. Demonstrate to COR the proper operation of burners.
  - 1. Emissions within limits specified for new boilers on this project.
  - 2. Stable flame at all operating points with no pulsations.
  - 3. Smooth flame light off, with no delays, puffs or flashbacks.
  - 4. Turndown capability as specified.
- D. Develop full steam output capacity required.

#### 3.13 INSTRUCTIONS TO VA PERSONNEL

Provide in accordance with Article, INSTRUCTIONS, of Section 01 00 00, GENERAL REQUIREMENTS.

ENDOF SECTION 23 05 11

# SECTION 23 05 12 GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT

### PART 1 - GENERAL

#### 1.1 DESCRIPTION:

This section specifies the furnishing, installation and connection of motors for HVAC and steam generation equipment.

#### 1.2 SUBMITTALS:

- A. In accordance with Section, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, submit the following:
- B. Shop Drawings:
  - 1. Sufficient information, clearly presented, shall be included to determine compliance with drawings and specifications.
  - 2. Include electrical ratings, dimensions, mounting details, materials, horsepower, RPM, enclosure, starting characteristics, torque characteristics, code letter, full load and locked rotor current, service factor, and lubrication method.

### 1.3 APPLICABLE PUBLICATIONS:

- A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.
- B. National Electrical Manufacturers Association (NEMA):

MG 1-98..... Motors and Generators

MG 2-01.....Safety Standard and Guide for Selection, Installation and Use of Electric Motors and Generators

C. National Fire Protection Association (NFPA): 70-02.....National Electrical Code (NEC)

## PART 2 - PRODUCTS

## 2.1 MOTORS:

- A. For alternating current, fractional and integral horsepower motors, NEMA Publications MG 1 and MG 2 shall apply.
- B. Voltage ratings shall be as follows:
  - 1. Single phase:
    - a. Motors connected to 120-volt systems: 115 volts.
    - b. Motors connected to 208-volt systems: 200 volts.
    - c. Motors connected to 240 volt or 480 volt systems: 230/460 volts, dual connection.
  - 2. Three phase:
    - a. Motors connected to 208-volt systems: 200 volts.
    - b. Motors, less than 74.6 kW (100 HP), connected to 240 volt or 480 volt systems: 230/460 volts, dual connection.

C. Horsepower ratings shall be adequate for operating the connected loads continuously in the prevailing ambient temperatures in areas where the motors are installed, without exceeding the NEMA standard temperature rises for the motor insulation.

- D. Motor designs, as indicated by the NEMA code letters, shall be coordinated with the connected loads to assure adequate starting and running torque.
- E. Motor Enclosures:
  - 1. Shall be the NEMA types shown on the drawings for the motors.
  - 2. Where the types of motor enclosures are not shown on the drawings, they shall be the NEMA types, which are most suitable for the environmental conditions where the motors are being installed.
  - 3. Enclosures shall be primed and finish coated at the factory with manufacturer's prime coat and standard finish.
- F. Additional requirements for specific motors, as indicated in other sections, shall also apply.
- G. Energy-Efficient Motors (Motor Efficiencies): All permanently wired polyphase motors of 746 Watts or more shall meet the minimum full-load efficiencies as indicated in the following table, and as specified in this specification. Motors of 746 Watts or more with open, drip-proof or totally enclosed fan-cooled enclosures shall be NEMA premium efficiency type, unless otherwise indicated. Motors provided as an integral part of motor driven equipment are excluded from this requirement if a minimum seasonal or overall efficiency requirement is indicated for that equipment by the provisions of another section.

Min	imum Eff	iciencie	S	Minimum Efficiencies					
•	Open Drip	p-Proof		Totally Enclosed Fan-Cooled					
Rating	1200	1800	3600	Rating	1200	1800	3600		
kW (HP)	RPM	RPM	RPM	kW (HP)	RPM	RPM	RPM		
0.746 (1)	82.5%	85.5%	77.0%	0.746 (1)	82.5%	85.5%	77.0%		
1.12 (1.5)	86.5%	86.5%	84.0%	1.12 (1.5)	87.5%	86.5%	84.0%		
1.49 (2)	87.5%	86.5%	85.5%	1.49 (2)	88.5%	86.5%	85.5%		
2.24 (3)	88.5%	89.5%	85.5%	2.24 (3)	89.5%	89.5%	86.5%		
3.73 (5)	89.5%	89.5%	86.5%	3.73 (5)	89.5%	89.5%	88.5%		
5.60 (7.5)	90.2%	91.0%	88.5%	5.60 (7.5)	91.0%	91.7%	89.5%		
7.46 (10)	91.7%	91.7%	89.5%	7.46 (10)	91.0%	91.7%	90.2%		
11.2 (15)	91.7%	93.0%	90.2%	11.2 (15)	91.7%	92.4%	91.0%		
14.9 (20)	92.4%	93.0%	91.0%	14.9 (20)	91.7%	93.0%	91.0%		
18.7 (25)	93.0%	93.6%	91.7%	18.7 (25)	93.0%	93.6%	91.7%		

- H. Minimum Power Factor at Full Load and Rated Voltage: 90 percent at 1200 RPM, 1800 RPM and 3600 RPM.
- I. Premium efficiency motors shall be used where energy  $cost/kW \times (hours use/year) > 50$ .

## PART 3 - EXECUTION

### 3.1 INSTALLATION:

Install motors in accordance with manufacturer's recommendations, the NEC, NEMA, as shown on the drawings and/or as required by other sections of these specifications.

## 3.2 FIELD TESTS

Megger all motors after installation, before start-up. All shall test free from grounds.

END OF SECTION 23 05 12

THIS PAGE INTENTION	NALLY LEFT BLANK
/A-528A87-12-706	NOISE AND VIBRATION CONTROL FOR

### **SECTION 23 05 41**

## NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT

### PART 1 - GENERAL

### 1.1 DESCRIPTION

Noise criteria, seismic restraints for equipment, vibration tolerance and vibration isolation for HVAC and plumbing work.

### 1.2 RELATED WORK

- A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION: General mechanical requirements and items, which are common to more than one section of Division 23.
- B. Section 23 22 13, STEAM AND CONDENSATE HEATING PIPING: Requirements for flexible pipe connectors to reciprocating and rotating mechanical equipment.
- C. Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS: Requirements for optional Air Handling Unit internal vibration isolation.
- D. Section 23 31 00, HVAC DUCTS AND CASINGS: requirements for flexible duct connectors, sound attenuators and sound absorbing duct lining.
- E.SECTION 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC: requirements for sound and vibration tests.

### 1.3 QUALITY ASSURANCE

- A. Refer to article, QUALITY ASSURANCE in specification Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Noise Criteria:
  - 1. For equipment which has no sound power ratings scheduled on the plans, the contractor shall select equipment such that the fore-going noise criteria, local ordinance noise levels, and OSHA requirements are not exceeded. Selection procedure shall be in accordance with ASHRAE Fundamentals Handbook, Chapter 7, Sound and Vibration.
  - 2. In absence of specified measurement requirements, measure equipment noise levels three feet from equipment and at an elevation of maximum noise generation.
- C. Allowable Vibration Tolerances for Rotating, Non-reciprocating Equipment: Not to exceed a self-excited vibration maximum velocity of 5 mm per second (0.20 inch per second) RMS, filter in, when measured with a vibration meter on bearing caps of machine in vertical, horizontal and axial directions or measured at equipment mounting feet if bearings are concealed. Measurements for internally isolated fans and motors may be made at the mounting feet.

## 1.4 SUBMITTALS

- A. Submit in accordance with specification Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Vibration isolators:

- a. Floor mountings
- b. Hangers
- c. Snubbers
- d. Thrust restraints
- 2. Bases.
- 3. Seismic restraint provisions and bolting.
- C. Isolator manufacturer shall furnish with submittal load calculations for selection of isolators, including supplemental bases, based on lowest operating speed of equipment supported.

### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE):
  - 2005 ...... Fundamentals Handbook, Chapter 7, Sound and Vibration
- C. American Society for Testing and Materials (ASTM):
  - A123/A123M-02 ......Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products
  - A307-04.....Standard Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength
  - D2240-05 ...... Standard Test Method for Rubber Property Durometer Hardness
- D. Manufacturers Standardization (MSS):
  - SP-58-02 ......Pipe Hangers and Supports-Materials, Design and Manufacture
- E. Occupational Safety and Health Administration (OSHA):
  - 29 CFR 1910.95 ...... Occupational Noise Exposure

## PART 2 - PRODUCTS

## 2.1 GENERAL REQUIREMENTS

- A. Type of isolator, base, and minimum static deflection shall be as required for each specific equipment application as recommended by isolator or equipment manufacturer but subject to minimum requirements indicated herein and in the schedule on the drawings.
- B. Elastometric Isolators shall comply with ASTM D2240 and be oil resistant neoprene with a maximum stiffness of 60 durometer and have a straight-line deflection curve.
- C. Uniform Loading: Select and locate isolators to produce uniform loading and deflection even when equipment weight is not evenly distributed.
- D. Color code isolators by type and size for easy identification of capacity.

## 2.2 SEISMIC RESTRAINT REQUIREMENTS FOR EQUIPMENTS

A. Bolt pad mounted equipment, without vibration isolators, to the floor or other support using ASTM A307 standard bolting material.

- B. Floor mounted equipment, with vibration Isolators: Type SS. Where Type N isolators are used provide channel frame base horizontal restraints bolted to the floor, or other support, on all sides of the equipment Size and material required for the base shall be as recommended by the isolator manufacturer.
- C. On all sided of suspended equipment, provide bracing for rigid supports and provide restraints for resiliently supported equipment. The slack cable restraint method, Mason Industries, or equal, is acceptable.

### 2.3 VIBRATION ISOLATORS

- A. Floor Mountings:
  - 1. Double Deflection Neoprene (Type N): Shall include neoprene covered steel support plated (top and bottom), friction pads, and necessary bolt holes.
  - 2. Spring Isolators (Type S): Shall be free-standing, laterally stable and include acoustical friction pads and leveling bolts. Isolators shall have a minimum ratio of spring diameter-to-operating spring height of 1.0 and an additional travel to solid equal to 50 percent of rated deflection.
  - 3. Pads (Type D), Washers (Type W), and Bushings (Type L): Pads shall be felt, cork, neoprene waffle, neoprene and cork sandwich, neoprene and fiberglass, neoprene and steel waffle, or reinforced duck and neoprene. Washers and bushings shall be reinforced duck and neoprene. Size pads for a maximum load of 345 kPa (50 pounds per square inch).
- B. Hangers: Shall be combination neoprene and springs unless otherwise noted and shall allow for expansion of pipe.
  - Combination Neoprene and Spring (Type H): Vibration hanger shall contain a spring and double deflection neoprene element in series. Spring shall have a diameter not less than 0.8 of compressed operating spring height. Spring shall have a minimum additional travel of 50 percent between design height and solid height. Spring shall permit a 15 degree angular misalignment without rubbing on hanger box.
  - 2. Neoprene (Type HN): Vibration hanger shall contain a double deflection type neoprene isolation element. Hanger rod shall be separated from contact with hanger bracket by a neoprene grommet.
  - 3. Spring (Type HS): Vibration hanger shall contain a coiled steel spring in series with a neoprene grommet. Spring shall have a diameter not less than 0.8 of compressed operating spring height. Spring shall have a minimum additional travel of 50 percent between design height and solid height. Spring shall permit a 15 degree angular misalignment without rubbing on hanger box.
  - 5. Hanger supports for piping 50 mm (2 inches) and larger shall have a pointer and scale deflection indicator.
- C. Snubbers: Each spring mounted base shall have a minimum of four all-directional or eight two directional (two per side) seismic snubbers that are double acting. Elastomeric materials shall be shock absorbent neoprene bridge quality bearing pads, maximum 60 durometer, replaceable and have a minimum thickness of 6 mm (1/4 inch). Air gap between hard

and resilient material shall be not less than 3 mm (1/8 inch) nor more than 6 mm (1/4 inch). Restraints shall be capable of withstanding design load without permanent deformation.

D. Thrust Restraints (Type THR): Restraints shall provide a spring element contained in a steel frame with neoprene pads at each end attachment. Restraints shall have factory preset thrust and be field adjustable to allow a maximum movement of 6 mm (1/4 inch) when the fan starts and stops. Restraint assemblies shall include rods, angle brackets and other hardware for field installation.

### 2.4 BASES

- A. Rails (Type R): Design rails with isolator brackets to reduce mounting height of equipment and cradle machines having legs or bases that do not require a complete supplementary base. To assure adequate stiffness, height of members shall be a minimum of 1/12 of longest base dimension but not less than 100 mm (4 inches). Where rails are used with neoprene mounts for small fans or close coupled pumps, extend rails to compensate overhang of housing.
- B. Curb Mounted Isolation Base (Type CB): Fabricate from aluminum to fit on top of standard curb with overlap to allow water run-off and have wind and water seals which shall not interfere with spring action. Provide resilient snubbers with 6 mm (1/4 inch) clearance for wind resistance. Top and bottom bearing surfaces shall have sponge type weather seals. Integral spring isolators shall comply with Spring Isolator (Type S) requirements.

## PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Vibration Isolation:
  - 1. No metal-to-metal contact will be permitted between fixed and floating parts.
  - 2. Connections to Equipment: Allow for deflections equal to or greater than equipment deflections. Electrical, drain, piping connections, and other items made to rotating or reciprocating equipment (pumps, compressors, etc.) which rests on vibration isolators, shall be isolated from building structure for first three hangers or supports.
  - 3. Common Foundation: Mount each electric motor on same foundation as driven machine. Hold driving motor and driven machine in positive rigid alignment with provision for adjusting motor alignment and belt tension. Bases shall be level throughout length and width. Provide shims to facilitate pipe connections, leveling, and bolting.
  - 4. Provide heat shields where elastomers are subject to temperatures over 38 degrees C (100 degrees F).
  - B. Inspection and Adjustments: Check for vibration and noise transmission through connections, piping, ductwork, foundations, and walls. Adjust, repair, or replace isolators as required to reduce vibration and noise transmissions to specified levels.

## 3.2 ADJUSTING

A. Adjust vibration isolators after piping systems are filled and equipment is at operating weight.

- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4inch (6-mm) movement during start and stop.
- D. Adjust active height of spring isolators.
- E. Adjust snubbers according to manufacturer's recommendations.
- F. Torque anchor bolts according to equipment manufacturer's recommendations to resist seismic forces.

END OF SECTION 23 05 41

## SELECTION GUIDE FOR VIBRATION ISOLATORS

EQUIPMENT	0	N GRAD	ÞΕ	20FT	20FT FLOOR SPAN		30FT	0FT FLOOR SPAN 40F		40FT	FT FLOOR SPAN		50FT FLOOR		SPAN
	BAS E TYP E	ISOL TYP E	MIN DEF L	BAS E TYP E	ISOL TYP E	MIN DEF L	BAS E TYP E	ISOL TYP E	MIN DEF L	BAS E TYP E	ISOL TYP E	MIN DEF L	BAS E TYP E	ISOL TYP E	MIN DEF L
AIR HANDLING UNIT PACKAGES															
7-1/2 HP & OVER:															
501 RPM & OVER		D			S, THR	1.0		S, THR	1.0	R	S, THR	1.7	R	S, THR	1.7
IN-LINE CENTRIFUGAL AND VANE AXIAL FANS, FLOOR MOUNTED: (APR 9)															
UP THRU 50 HP:															
501 - & OVER		D			S	1.0		S	1.0	R	S	1.7	R	S	2.5

# SECTION 23 05 93 TESTING, ADJUSTING, AND BALANCING FOR HVAC

### PART 1 - GENERAL

### 1.1 DESCRIPTION

- A. Testing, adjusting, and balancing (TAB) of heating, ventilating and air conditioning (HVAC) systems. TAB includes the following:
  - 1. Planning systematic TAB procedures.
  - 2. Design Review Report.
  - 3. Systems Inspection report.
  - 4. Systems Readiness Report.
  - 5. Balancing air and water distribution systems; adjustment of total system to provide design performance; and testing performance of equipment and automatic controls.
  - 6. Recording and reporting results.

## B. Definitions:

- 1. Basic TAB used in this Section: Chapter 37, "Testing, Adjusting and Balancing" of ASHRAE Handbook, "HVAC Applications".
- 2. TAB: Testing, Adjusting and Balancing; the process of checking and adjusting HVAC systems to meet design objectives.
- 3. AABC: Associated Air Balance Council.
- 4. NEBB: National Environmental Balancing Bureau.
- 5. Hydronic Systems: Includes chilled water, heating hot water and glycol-water systems.
- 6. Air Systems: Includes all outside air, supply air, return air, exhaust air and relief air systems.
- 7. Flow rate tolerance: The allowable percentage variation, minus to plus, of actual flow rate from values (design) in the contract documents.

## 1.2 RELATED WORK

- A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION: General Mechanical Requirements.
- B. Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION: Piping and Equipment Insulation.
- C. Section 23 31 00, HVAC DUCTS AND CASINGS: Duct Leakage.
- D. Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC: Controls and Instrumentation Settings.

## 1.3 QUALITY ASSURANCE

- A. Refer to Articles, Quality Assurance and Submittals, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Qualifications:
  - 1. TAB Agency: The TAB agency shall be a subcontractor of the General Contractor and shall report to and be paid by the General Contractor.
  - 2. The TAB agency shall be either a certified member of AABC or certified by the NEBB to perform TAB service for HVAC, water balancing and vibrations and sound testing of

equipment. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the agency loses subject certification during this period, the General Contractor shall immediately notify the COR and submit another TAB firm for approval. Any agency that has been the subject of disciplinary action by either the AABC or the NEBB within the five years preceding Contract Award shall not be eligible to perform any work related to the TAB. All work performed in this Section and in other related Sections by the TAB agency shall be considered invalid if the TAB agency loses its certification prior to Contract completion, and the successor agency's review shows unsatisfactory work performed by the predecessor agency.

- 3. TAB Specialist: The TAB specialist shall be either a member of AABC or an experienced technician of the Agency certified by NEBB. The certification shall be maintained for the entire duration of duties specified herein. If, for any reason, the Specialist loses subject certification during this period, the General Contractor shall immediately notify the COR and submit another TAB Specialist for approval. Any individual that has been the subject of disciplinary action by either the AABC or the NEBB within the five years preceding Contract Award shall not be eligible to perform any duties related to the HVAC systems, including TAB. All work specified in this Section and in other related Sections performed by the TAB specialist shall be considered invalid if the TAB Specialist loses its certification prior to Contract completion and must be performed by an approved successor.
  - 4. TAB Specialist shall be identified by the General Contractor within 60 days after the notice to proceed. The TAB specialist will be coordinating, scheduling and reporting all TAB work and related activities and will provide necessary information as required by the COR. The responsibilities would specifically include:
  - a. Shall directly supervise all TAB work.
  - b. Shall sign the TAB reports that bear the seal of the TAB standard. The reports shall be accompanied by report forms and schematic drawings required by the TAB standard, AABC or NEBB.
  - c. Would follow all TAB work through its satisfactory completion.
  - d. Shall provide final markings of settings of all HVAC adjustment devices.
  - e. Permanently mark location of duct test ports.
- 5. All TAB technicians performing actual TAB work shall be experienced and must have done satisfactory work on a minimum of 3 projects comparable in size and complexity to this project. Qualifications must be certified by the TAB agency in writing.
- C. Test Equipment Criteria: The instrumentation shall meet the accuracy/calibration requirements established by AABC National Standards or by NEBB Procedural Standards for Testing, Adjusting and Balancing of Environmental Systems and instrument manufacturer. Provide calibration history of the instruments to be used for test and balance purpose.

### D. Tab Criteria:

- One or more of the applicable AABC, NEBB or SMACNA publications, supplemented by ASHRAE Handbook "HVAC Applications" Chapter 36, and requirements stated herein shall be the basis for planning, procedures, and reports.
- 2. Flow rate tolerance: Following tolerances are allowed. For tolerances not mentioned herein follow ASHRAE Handbook "HVAC Applications", Chapter 36, as a guideline. Air Filter resistance during tests, artificially imposed if necessary, shall be at least 90 percent of final values for pre-filters and after-filters.

> a. Air handling unit and all other fans, cubic meters/min (cubic feet per minute): Minus 5 percent to plus 10 percent.

- b. Minimum outside air: 0 percent to plus 10 percent.
- c. Heating hot water pumps and hot water coils: Minus 5 percent to plus 5 percent.
- d. Chilled water coils: 0 percent to plus 5 percent.
- 3. Systems shall be adjusted for energy efficient operation as described in PART 3.
- 4. Typical TAB procedures and results shall be demonstrated to the Engineer for one air distribution system and one hydronic system as follows:
  - a. When field TAB work begins.
  - b. During each partial final inspection and the final inspection for the project if requested by VA.

## 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Submit names and qualifications of TAB agency and TAB specialists within 60 days after the notice to proceed. Submit information on three recently completed projects and a list of proposed test equipment.
- C. For use by the Engineer staff, submit one complete set of applicable AABC or NEBB publications that will be the basis of TAB work.
- D. Submit Following for Review and Approval:
  - 1. Design Review Report within 45 days after the system layout on air and water side is completed by the Contractor.
  - 2. Systems inspection report on equipment and installation for conformance with design.
  - 3. Duct Air Leakage Test Report.
  - 4. Systems Readiness Report.
  - 5. Intermediate and Final TAB reports covering flow balance and adjustments and performance
  - 6. Include in final reports uncorrected installation deficiencies noted during TAB and applicable explanatory comments on test results that differ from design requirements.
- E. Prior to request for Final or Partial Final inspection, submit completed Test and Balance report for the area.

## 1.5 APPLICABLE PUBLICATIONS

- A. The following publications form a part of this specification to the extent indicated by the reference thereto. In text the publications are referenced to by the acronym of the organization.
- B. American Society of Heating, Refrigerating and Air Conditioning Engineers, Inc. (ASHRAE):
  - Adjusting, and Balancing and Chapter 47, Sound and Vibration Control
- C. Associated Air Balance Council (AABC): 2002 ...... AABC National Standards for Total System Balance

D.	National Environmental Ba. 7 <sup>th</sup> Edition 2005Pi		
		rocedural Standards for th	e Measurement and Assessment of
	2 <sup>nd</sup> Edition 1999Pı		uilding Systems Commissioning
Ε.	Sheet Metal and Air Condit (SMACNA):  3 <sup>rd</sup> Edition 2002		
	3 EUILION 2002	VAC 3131 EIVIS-TESting, Auj	usting and Balancing

### PART 2 - PRODUCTS

#### 2.1 PLUGS

Provide plastic plugs to seal holes drilled in ductwork for test purposes.

#### PART 3 - EXECUTION

## 3.1 GENERAL

- A. Refer to TAB Criteria in Article, Quality Assurance.
- B. Obtain applicable contract documents and copies of approved submittals for HVAC equipment and automatic control systems.

## 3.2 DESIGN REVIEW REPORT

The TAB Specialist shall review the Contract Plans and specifications and advise the Engineer of any design deficiencies that would prevent the HVAC systems from effectively operating in accordance with the sequence of operation specified or prevent the effective and accurate TAB of the system. The TAB Specialist shall provide a report individually listing each deficiency and the corresponding proposed corrective action necessary for proper system operation.

### 3.3 SYSTEMS INSPECTION REPORT

- A. Inspect equipment and installation for conformance with design.
- B. The inspection and report is to be done after air distribution equipment is on site and duct installation has begun, but well in advance of performance testing and balancing work. The purpose of the inspection is to identify and report deviations from design and ensure that systems will be ready for TAB at the appropriate time.
- C. Reports: Follow check list format developed by AABC, NEBB or SMACNA, supplemented by narrative comments, with emphasis on air handling units and fans. Check for conformance with submittals. Verify that diffuser and register sizes are correct. Check air terminal unit installation including their duct sizes and routing.

## 3.4 SYSTEM READINESS REPORT

A. Inspect each System to ensure that it is complete including installation and operation of controls.

B. Verify that all items such as ductwork piping, ports, terminals, connectors, etc., that is required for TAB are installed. Provide a report to the Engineer.

### 3.5 TAB REPORTS

- A. Submit an intermediate report for 25 percent of systems and equipment tested and balanced to establish satisfactory test results.
- B. The TAB contractor shall provide raw data immediately in writing to the Engineer if there is a problem in achieving intended results before submitting a formal report.
- C. If over 20 percent of readings in the intermediate report fall outside the acceptable range, the TAB report shall be considered invalid and all contract TAB work shall be repeated and re-submitted for approval.
- D. Do not proceed with the remaining systems until intermediate report is approved by the Engineer.

### 3.7 TAB PROCEDURES

- A. Tab shall be performed in accordance with the requirement of the Standard under which TAB agency is certified by either AABC or NEBB.
- B. General: During TAB all related system components shall be in full operation. Fan and pump rotation, motor loads and equipment vibration shall be checked and corrected as necessary before proceeding with TAB. Set controls and/or block off parts of distribution systems to simulate design operation of variable volume air or water systems for test and balance work.
- C. Coordinate TAB procedures with any phased construction completion requirements for the project. Provide TAB reports for each phase of the project prior to partial final inspections of each phase of the project.
- D. Allow sufficient time in construction schedule for TAB and submission of all reports for an organized and timely correction of deficiencies.
- E. Air Balance and Equipment Test: Include air handling units and fans.
  - 1. Artificially load air filters by partial blanking to produce air pressure drop of at least 90 percent of the design final pressure drop.
  - 2. Adjust fan speeds to provide design air flow. V-belt drives, including fixed pitch pulley requirements, are specified in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
  - 3. Test and balance systems in all specified modes of operation, including variable volume, economizer, and fire emergency modes. Verify that dampers and other controls function properly.
  - 4. Variable air volume (VAV) systems:
    - a. Coordinate TAB, including system volumetric controls, with Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.

b. Section 23 36 00, AIR TERMINAL UNITS, specifies that maximum and minimum flow rates for air terminal units (ATU) be factory set. Check and readjust ATU flow rates if necessary. Balance air distribution from ATU on full cooling maximum scheduled cubic meters per minute (cubic feet per minute). Reset room thermostats and check ATU operation from maximum to minimum cooling, to the heating mode, and back to cooling. Record and report the heating coil leaving air temperature when the ATU is in the maximum heating mode.

- 5. Record final measurements for air handling equipment performance data sheets.
- F. Water Balance and Equipment Test: Include circulating pumps, convertors and coils:
  - 1. Adjust flow rates for equipment. Set coils to values on equipment submittals, if different from values on contract drawings.
  - 2. Record final measurements for hydronic equipment on performance data sheets. Include entering and leaving water temperatures for heating and cooling coils, and for convertors. Include entering and leaving air temperatures (DB/WB for cooling coils) for air handling units and reheat coils. Make air and water temperature measurements at the same time.

#### 3.8 MARKING OF SETTINGS

Following approval of Tab final Report, the setting of all HVAC adjustment devices including valves, splitters and dampers shall be permanently marked by the TAB Specialist so that adjustment can be restored if disturbed at any time. Style and colors used for markings shall be coordinated with the COR.

### 3.9 IDENTIFICATION OF TEST PORTS

The TAB Specialist shall permanently and legibly identify the location points of duct test ports. If the ductwork has exterior insulation, the identification shall be made on the exterior side of the insulation. All penetrations through ductwork and ductwork insulation shall be sealed to prevent air leaks and maintain integrity of vapor barrier.

END OF SECTION 23 05 93

## **SECTION 23 07 11** HVAC, PLUMBING, AND BOILER PLANT INSULATION

### PART 1 - GENERAL

## 1.1 DESCRIPTION

- A. Field applied insulation for thermal efficiency and condensation control for
  - 1. HVAC piping, ductwork and equipment.

## B. Definitions

- 1. ASJ: All service jacket, white finish facing or jacket.
- 2. Air conditioned space: Space having air temperature and/or humidity controlled by mechanical equipment.
- 3. Cold: Equipment, ductwork or piping handling media at design temperature of 16 degrees C (60 degrees F) or below.
- 4. Concealed: Ductwork and piping above ceilings and in chases, and pipe spaces.
- 5. Exposed: Piping, ductwork, and equipment exposed to view in finished areas including mechanical, Boiler Plant and electrical equipment rooms or exposed to outdoor weather. Attics and crawl spaces where air handling units are located are considered to be mechanical rooms. Shafts, chases, unfinished attics, crawl spaces and pipe basements are not considered finished areas.
- 6. FSK: Foil-scrim-kraft facing.
- 7. Hot: HVAC Ductwork handling air at design temperature above 16 degrees C (60 degrees F); HVAC and plumbing equipment or piping handling media above 41 degrees C (105 degrees F); Boiler Plant breechings and stack temperature range 150-370 degrees C(300-700 degrees F) and piping media and equipment 32 to 230 degrees C(90 to 450 degrees F)
- 8. Density: kg/m³ kilograms per cubic meter (Pcf pounds per cubic foot).
- 9. Runouts: Branch pipe connections up to 25-mm (one-inch) nominal size to fan coil units or reheat coils for terminal units.
- 10. Thermal conductance: Heat flow rate through materials.
  - a. Flat surface: Watt per square meter (BTU per hour per square foot).
  - b. Pipe or Cylinder: Watt per square meter (BTU per hour per linear foot).
- 11. Thermal Conductivity (k): Watt per meter, per degree C (BTU per inch thickness, per hour, per square foot, per degree F temperature difference).
- 12. HPS: High pressure steam (415 kPa [60 psig] and above).
- 13. HPR: High pressure steam condensate return.
- 14. MPS: Medium pressure steam (110 kPa [16 psig] thru 414 kPa [59 psig].
- 15. MPR: Medium pressure steam condensate return.
- 16. LPS: Low pressure steam (103 kPa [15 psig] and below).
- 17. LPR: Low pressure steam condensate gravity return.
- 18. PC: Pumped condensate.
- 19. HWH: Hot water heating supply.
- 20. HWHR: Hot water heating return.
- 21. GH: Hot glycol-water heating supply.
- 22. GHR: Hot glycol-water heating return.
- 23. FWPD: Feedwater pump discharge.

- 24. FWPS: Feedwater pump suction.
- 25. CTPD: Condensate transfer pump discharge.
- 26. CTPS: Condensate transfer pump suction.
- 27. VR: Vacuum condensate return.
- 28. CPD: Condensate pump discharge.
- 29. R: Pump recirculation.
- 30. FOS: Fuel oil supply.
- 31. FOR: Fuel oil return.
- 32. CW: Cold water.
- 33. SW: Soft water.
- 34. HW: Hot water.
- 35. CH: Chilled water supply.
- 36. CHR: Chilled water return.
- 37. GC: Chilled glycol-water supply.
- 38. GCR: Chilled glycol-water return.
- 39. RS: Refrigerant suction.
- 40. PVDC: Polyvinylidene chloride vapor retarder jacketing, white.

## 1.2 RELATED WORK

- A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION: General mechanical requirements and items, which are common to more than one section of Division 23.
- B. Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM AND CONDENSATE HEATING PIPING: Piping and equipment.
- C. Section 23 31 00, HVAC DUCTS AND CASINGS: Ductwork, plenum and fittings.

## 1.3 QUALITY ASSURANCE

A. Refer to article QUALITY ASSURANCE, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

## B. Criteria:

- 1. Comply with NFPA 90A, particularly paragraphs 4.3.3.1 through 4.3.3.6, 4.3.10.2.6, and 5.4.6.4, parts of which are quoted as follows:
  - 4.3.3.1 Pipe insulation and coverings, duct coverings, duct linings, vapor retarder facings, adhesives, fasteners, tapes, and supplementary materials added to air ducts, plenums, panels, and duct silencers used in duct systems, unless otherwise provided for in 4.3.3.1.2 or 4.3.3.1.3, shall have, in the form in which they are used, a maximum flame spread index of 25 without evidence of continued progressive combustion and a maximum smoke developed index of 50 when tested in accordance with NFPA 255, Standard Method of Test of Surface Burning Characteristics of Building Materials.
  - 4.3.3.1.1 Where these products are to be applied with adhesives, they shall be tested with such adhesives applied, or the adhesives used shall have a maximum flame spread index of 25 and a maximum smoke developed index of 50 when in the final dry state. (See 4.2.4.2.)

> 4.3.3.1.2 The flame spread and smoke developed index requirements of 4.3.3.1.1 shall not apply to air duct weatherproof coverings where they are located entirely outside of a building, do not penetrate a wall or roof, and do not create an exposure hazard. 4.3.3.1.3 Smoke detectors required by 6.4.4 shall not be required to meet flame spread index or smoke developed index requirements.

- 4.3.3.2 Closure systems for use with rigid and flexible air ducts tested in accordance with UL 181, Standard for Safety Factory-Made Air Ducts and Air Connectors, shall have been tested, listed, and used in accordance with the conditions of their listings, in accordance with one of the following:
- UL 181A, Standard for Safety Closure Systems for Use with Rigid Air Ducts and Air Connectors
- UL 181B, Standard for Safety Closure Systems for Use with Flexible Air Ducts and Air Connectors
- 4.3.3.3 Air duct, panel, and plenum coverings and linings, and pipe insulation and coverings shall not flame, glow, smolder, or smoke when tested in accordance with a similar test for pipe covering, ASTM C 411, Standard Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation, at the temperature to which they are exposed in service.
- 4.3.3.3.1 In no case shall the test temperature be below 121°C (250°F).
- 4.3.3.4 Air duct coverings shall not extend through walls or floors that are required to be fire stopped or required to have a fire resistance rating, unless such coverings meet the requirements of 5.4.6.4.
- 4.3.3.5\* Air duct linings shall be interrupted at fire dampers to prevent interference with the operation of devices.
- 4.3.3.6 Air duct coverings shall not be installed so as to conceal or prevent the use of any service opening.
- 4.3.10.2.6 Materials exposed to the airflow shall be noncombustible or limited combustible and have a maximum smoke developed index of 50 or comply with the following.
- 4.3.10.2.6.1 Electrical wires and cables and optical fiber cables shall be listed as noncombustible or limited combustible and have a maximum smoke developed index of 50 or shall be listed as having a maximum peak optical density of 0.5 or less, an average optical density of 0.15 or less, and a maximum flame spread distance of 1.5 m (5 ft) or less when tested in accordance with NFPA 262, Standard Method of Test for Flame Travel and Smoke of Wires and Cables for Use in Air-Handling Spaces.
- 4.3.10.2.6.2 Pneumatic tubing for control systems shall be listed as having a maximum peak optical density of 0.5 or less, an average optical density of 0.15 or less, and a maximum flame spread distance of 1.5 m (5 ft) or less when tested in accordance with UL 1820, Standard for Safety Fire Test of Pneumatic Tubing for Flame and Smoke Characteristics.
- 4.3.10.2.6.3 Nonferrous fire sprinkler piping shall be listed as having a maximum peak optical density of 0.5 or less, an average optical density of 0.15 or less, and a maximum flame spread distance of 1.5 m (5 ft) or less when tested in accordance with UL 1887, Standard for Safety Fire Test of Plastic Sprinkler Pipe for Visible Flame and Smoke Characteristics.
- 4.3.10.2.6.4 Optical-fiber and communication raceways shall be listed as having a maximum peak optical density of 0.5 or less,

> an average optical density of 0.15 or less, and a maximum flame spread distance of 1.5 m  $(5\ {\rm ft})$  or less when tested in accordance with UL 2024, Standard for Safety Optical-Fiber Cable Raceway. 4.3.10.2.6.5 Loudspeakers and recessed lighting fixtures, including their assemblies and accessories, shall be permitted in the ceiling cavity plenum where listed as having a maximum peak optical density of 0.5 or less, an average optical density of 0.15 or less, and a peak heat release rate of 100 kW or less when tested in accordance with UL 2043, Standard for Safety Fire Test for Heat and Visible Smoke Release for Discrete Products and Their Accessories Installed in Air-Handling Spaces. 4.3.10.2.6.6 Supplementary materials for air distribution systems

- shall be permitted when complying with the provisions of 4.3.3. 4.3.10.2.6.7 Smoke detectors shall not be required to meet the provisions of this section.
- 5.4.6.4 Where air ducts pass through walls, floors, or partitions that are required to have a fire resistance rating and where fire dampers are not required, the opening in the construction around the air duct shall be as follows:
- (1)Not exceeding a 25.4 mm (1 in.) average clearance on all sides
- (2) Filled solid with an approved material capable of preventing the passage of flame and hot gases sufficient to ignite cotton waste when subjected to the time-temperature fire conditions required for fire barrier penetration as specified in NFPA 251, Standard Methods of Tests of Fire Endurance of Building Construction and Materials
- 2. Test methods: ASTM E84, UL 723, or NFPA 255.
- 3. Specified k factors are at 24 degrees C (75 degrees F) mean temperature unless stated otherwise. Where optional thermal insulation material is used, select thickness to provide thermal conductance no greater than that for the specified material. For pipe, use insulation manufacturer's published heat flow tables. For domestic hot water supply and return, run out insulation and condensation control insulation, no thickness adjustment need be made.
- 4. All materials shall be compatible and suitable for service temperature, and shall not contribute to corrosion or otherwise attack surface to which applied in either the wet or dry state.
- C. Every package or standard container of insulation or accessories delivered to the job site for use must have a manufacturer's stamp or label giving the name of the manufacturer and description of the material.

## 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Shop Drawings:
  - 1. All information, clearly presented, shall be included to determine compliance with drawings and specifications and ASTM, federal and military specifications.
    - a. Insulation materials: Specify each type used and state surface burning characteristics.
    - b. Insulation facings and jackets: Each type used. Make it clear that white finish will be furnished for exposed ductwork, casings and equipment.
    - c. Insulation accessory materials: Each type used.

> d. Manufacturer's installation and fitting fabrication instructions for flexible unicellular insulation.

e. Make reference to applicable specification paragraph numbers for coordination.

### 1.5 STORAGE AND HANDLING OF MATERIAL

Store materials in clean and dry environment, pipe covering jackets shall be clean and unmarred. Place adhesives in original containers. Maintain ambient temperatures and conditions as required by printed instructions of manufacturers of adhesives, mastics and finishing cements.

## 1.6 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by basic designation only.

В.	Federal Specifications (L-P-535E (2)-91	(Fed. Spec.): . Plastic Sheet (Sheeting): Plastic Strip; Poly (Vinyl Chloride) and Poly (Vinyl Chloride - Vinyl Acetate), Rigid.
C.	MIL-A-24179A (1)-87	
	MIL-C-19565C (1)-88	. Coating Compounds, Thermal Insulation, Fire-and Water- Resistant, Vapor-Barrier
	MIL-C-20079H-87	. Cloth, Glass; Tape, Textile Glass; and Thread, Glass and Wire- Reinforced Glass
D.	American Society for Tes	sting and Materials (ASTM):
	A167-99	. Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip
	B209-04	. Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate
		. Standard test method for Hot-Surface Performance of High-Temperature Thermal Insulation
	C449-00	. Standard Specification for Mineral Fiber Hydraulic-Setting Thermal Insulating and Finishing Cement
	C533-04	. Standard Specification for Calcium Silicate Block and Pipe Thermal Insulation
	C534-05	. Standard Specification for Preformed Flexible Elastomeric Cellular Thermal Insulation in Sheet and Tubular Form
	C547-06	. Standard Specification for Mineral Fiber pipe Insulation
	C552-03	. Standard Specification for Cellular Glass Thermal Insulation
	C553-02	. Standard Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications
	C585-90	Standard Practice for Inner and Outer Diameters of Rigid Thermal Insulation for Nominal Sizes of Pipe and Tubing (NPS System) R (1998)

	C612-04	. Standard Specification for Mineral Fiber Block and Board Thermal Insulation
	C1126-04	. Standard Specification for Faced or Unfaced Rigid Cellular Phenolic Thermal Insulation
	C1136-06	. Standard Specification for Flexible, Low Permeance Vapor Retarders for Thermal Insulation
	D1668-97a (2006)	. Standard Specification for Glass Fabrics (Woven and Treated) for Roofing and Waterproofing
	E84-06	. Standard Test Method for Surface Burning Characteristics of Building Materials
	E119-05a	. Standard Test Method for Fire Tests of Building Construction and Materials
	E136-04	Standard Test Methods for Behavior of Materials in a Vertical Tube Furnace at 750 degrees C (1380 F)
Ε.	National Fire Protection	n Association (NFPA):
		. Installation of Air Conditioning and Ventilating Systems
	96-04	. Standards for Ventilation Control and Fire Protection of Commercial Cooking Operations
	101-06	•
	251-06	. Standard methods of Tests of Fire Endurance of Building Construction Materials
	255-06	. Standard Method of tests of Surface Burning Characteristics of Building Materials
F.	Underwriters Laboratorie	es, Inc (UL):
	723	UL Standard for Safety Test for Surface Burning Characteristics of Building Materials with Revision of 08/03
G.	Manufacturer's Standard: Industry (MSS):	ization Society of the Valve and Fitting
		. Pipe Hangers and Supports Materials, Design, and Manufacture

## PART 2 - PRODUCTS

## 2.1 MINERAL FIBER

- A. ASTM C612 (Board, Block), Class 1 or 2, k = 0.037 Watt per meter, per degree C (0.26), external insulation for temperatures up to 204 degrees C (400 degrees F).
- C. ASTM C547 (Pipe Fitting Insulation and Preformed Pipe Insulation), Class 1, k = 0.037 (0.26) for use at temperatures 230 degrees C (450 degrees F).

## 2.2 MINERAL WOOL OR REFRACTORY FIBER

A. Comply with Standard ASTM C612, Class 3, 450 degrees C (850 degrees F).

03/14/2012 PHASE 2

### 2.3 RIGID CELLULAR PHENOLIC FOAM

A. Preformed (molded) pipe insulation, ASTM C1126, type III, grade 1, k =0.021(0.15), for temperatures up to 121 degrees C (250 degrees F) with vapor retarder and all service jacket with polyvinyl chloride premolded fitting covering.

B. Equipment and Duct Insulation, ASTM C 1126, type II, grade 1, k = 0.021 (0.15), for temperatures up to 121 degrees C (250 degrees F) with rigid cellular phenolic insulation and covering, vapor retarder and all service jacket.

### 2.4 CELLULAR GLASS CLOSED-CELL

- A. Comply with Standard ASTM C177, C518, density  $120 \text{ kg/m}^3$  (7.5 pcf) nominal, k = 0.033 (0.29) at 0 degrees C (75 degrees F).
- B. Pipe insulation for temperatures up to 200 degrees C (400 degrees F).

#### 2.5 POLYISOCYANURATE CLOSED-CELL RIGID

- A. Preformed (fabricated) pipe insulation, ASTM C591, type IV, K=0.027(0.19), for use at temperatures up to 149 degree C (300 degree F) with factory applied PVDC or all service jacket vapor retarder with polyvinyl chloride premolded fitting covers.
- B. Equipment and duct insulation, ASTM C 591, type IV, K=0.027(0.19), for use at temperatures up to 149 degrees C (300 degrees F) with PVDC or all service jacket vapor retarder jacket.

## 2.6 INSULATION FACINGS AND JACKETS

- A. Vapor Retarder, higher strength with low water permeance = 0.02 or less perm rating, Beach puncture 50 units for insulation facing on exposed ductwork, casings and equipment, and for pipe insulation jackets. Facings and jackets shall be all service type (ASJ) or PVDC Vapor Retarder jacketing.
- B. ASJ jacket shall be white kraft bonded to 0.025 mm (1 mil) thick aluminum foil, fiberglass reinforced, with pressure sensitive adhesive closure. Comply with ASTM C1136. Beach puncture 5 units, Suitable for painting without sizing. Jackets shall have minimum 40 mm (1-1/2 inch) lap on longitudinal joints and minimum 100 mm (4 inch) butt strip on end joints. Butt strip material shall be same as the jacket. Lap and butt strips shall be self-sealing type with factory-applied pressure sensitive adhesive.
- C. Vapor Retarder medium strength with low water vapor permeance of 0.02 or less perm rating), Beach puncture 25 units: Foil-Scrim-Kraft (FSK) or PVDC vapor retarder jacketing type for concealed ductwork and equipment.
- D. Glass Cloth Jackets: Presized, minimum 0.18 kg per square meter (7.8 ounces per square yard), 2000 kPa (300 psig) bursting strength with integral vapor retarder where required or specified. Weather proof if utilized for outside service.

E. Factory composite materials may be used provided that they have been tested and certified by the manufacturer.

- F. Pipe fitting insulation covering (jackets): Fitting covering shall be premolded to match shape of fitting and shall be polyvinyl chloride (PVC) conforming to Fed Spec L-P-335, composition A, Type II Grade GU, and Type III, minimum thickness 0.7 mm (0.03 inches). Provide color matching vapor retarder pressure sensitive tape.
- G. Aluminum Jacket-Piping systems and circular breeching and stacks: ASTM B209, 3003 alloy, H-14 temper, 0.6 mm (0.023 inch) minimum thickness with locking longitudinal joints. Jackets for elbows, tees and other fittings shall be factory-fabricated to match shape of fitting and of 0.6 mm (0.024) inch minimum thickness aluminum. Fittings shall be of same construction as straight run jackets but need not be of the same alloy. Factory-fabricated stainless steel bands shall be installed on all circumferential joints. Bands shall be 20 mm (0.75 inch) wide on 450 mm (18 inch) centers. System shall be weatherproof if utilized for outside service.
- H. Aluminum jacket-Rectangular breeching: ASTM B209, 3003 alloy, H-14 temper, 0.5 mm (0.020 inches) thick with 32 mm (1-1/4 inch) corrugations or 0.8 mm (0.032 inches) thick with no corrugations. System shall be weatherproof if used for outside service.

### 2.7 PIPE COVERING PROTECTION SADDLES

A. Cold pipe support: Premolded pipe insulation 180 degrees (half-shells) on bottom half of pipe at supports. Material shall be cellular glass or high density Polyisocyanurate insulation of the same thickness as adjacent insulation. Density of Polyisocyanurate insulation shall be a minimum of  $48 \text{ kg/m}^3$  (3.0 pcf).

Nominal Pipe Size and Accessor	ries Material (Insert Blocks)
Nominal Pipe Size mm (inches)	Insert Blocks mm (inches)
Up through 125 (5)	150 (6) long
150 (6)	150 (6) long
200 (8), 250 (10), 300 (12)	225 (9) long
350 (14), 400 (16)	300 (12) long
450 through 600 (18 through	350 (14) long
24)	

B. Warm or hot pipe supports: Premolded pipe insulation (180 degree halfshells) on bottom half of pipe at supports. Material shall be high density Polyisocyanurate (for temperatures up to 149 degrees C [300 degrees F]), cellular glass or calcium silicate. Insulation at supports shall have same thickness as adjacent insulation. Density of Polyisocyanurate insulation shall be a minimum of 48  $kg/m^3$  (3.0 pcf).

#### 2.8 ADHESIVE, MASTIC, CEMENT

A. Mil. Spec. MIL-A-3316, Class 1: Jacket and lap adhesive and protective finish coating for insulation.

03/14/2012 PHASE 2

B. Mil. Spec. MIL-A-3316, Class 2: Adhesive for laps and for adhering insulation to metal surfaces.

- C. Mil. Spec. MIL-A-24179, Type II Class 1: Adhesive for installing flexible unicellular insulation and for laps and general use.
- D. Mil. Spec. MIL-C-19565, Type I: Protective finish for outdoor use.
- E. Mil. Spec. MIL-C-19565, Type I or Type II: Vapor barrier compound for indoor use.
- F. ASTM C449: Mineral fiber hydraulic-setting thermal insulating and finishing cement.
- G. Other: Insulation manufacturers' published recommendations.

### 2.9 MECHANICAL FASTENERS

- A. Pins, anchors: Welded pins, or metal or nylon anchors with tin-coated or fiber washer, or clips. Pin diameter shall be as recommended by the insulation manufacturer.
- B. Staples: Outward clinching monel or stainless steel.
- C. Wire: 1.3 mm thick (18 gage) soft annealed galvanized or 1.9 mm (14 gage) copper clad steel or nickel copper alloy.
- D. Bands: 20 mm (3/4 inch) nominal width, brass, galvanized steel, aluminum or stainless steel.

### 2.10 REINFORCEMENT AND FINISHES

- A. Glass fabric, open weave: ASTM D1668, Type III (resin treated) and Type I (asphalt treated).
- B. Glass fiber fitting tape: Mil. Spec MIL-C-20079, Type II, Class 1.
- C. Tape for Flexible Elastomeric Cellular Insulation: As recommended by the insulation manufacturer.
- D. Hexagonal wire netting: 25 mm (one inch) mesh, 0.85 mm thick (22 gage) galvanized steel.
- E. Corner beads: 50 mm (2 inch) by 50 mm (2 inch), 0.55 mm thick (26 gage) galvanized steel; or, 25 mm (1 inch) by 25 mm (1 inch), 0.47 mm thick (28 gage) aluminum angle adhered to 50 mm (2 inch) by 50 mm (2 inch) Kraft paper.
- F. PVC fitting cover: Fed. Spec L-P-535, Composition A, 11-86 Type II, Grade GU, with Form B Mineral Fiber insert, for media temperature 4 degrees C (40 degrees F) to 121 degrees C (250 degrees F). Below 4 degrees C (40 degrees F) and above 121 degrees C (250 degrees F). Provide double layer insert. Provide color matching vapor barrier pressure sensitive tape.

### 2.11 FLAME AND SMOKE

Unless shown otherwise all assembled systems shall meet flame spread 25 and smoke developed 50 rating as developed under ASTM, NFPA and UL standards and specifications. See paragraph 1.3 "Quality Assurance".

### PART 3 - EXECUTION

### 3.1 GENERAL REQUIREMENTS

- A. Required pressure tests of duct and piping joints and connections shall be completed and the work approved by the COR for application of insulation. Surface shall be clean and dry with all foreign materials, such as dirt, oil, loose scale and rust removed.
- B. Except for specific exceptions, insulate entire specified equipment, piping (pipe, fittings, valves, accessories), and duct systems. Insulate each pipe and duct individually. Do not use scrap pieces of insulation where a full length section will fit.
- C. Insulation materials shall be installed in a first class manner with smooth and even surfaces, with jackets and facings drawn tight and smoothly cemented down at all laps. Insulation shall be continuous through all sleeves and openings, except at fire dampers and duct heaters (NFPA 90A). Vapor retarders shall be continuous and uninterrupted throughout systems with operating temperature 16 degrees C (60 degrees F) and below. Lap and seal vapor barrier over ends and exposed edges of insulation. Anchors, supports and other metal projections through insulation on cold surfaces shall be insulated and vapor sealed for a minimum length of 150 mm (6 inches).
- D. Install vapor stops at all insulation terminations on either side of valves, pumps and equipment and particularly in straight lengths of pipe insulation.
- E. Construct insulation on parts of equipment such as chilled water pumps and heads of chillers, convertors and heat exchangers that must be opened periodically for maintenance or repair, so insulation can be removed and replaced without damage. Install insulation with bolted 1 mm thick (20 gage) galvanized steel or aluminum covers as complete units, or in sections, with all necessary supports, and split to coincide with flange/split of the equipment.
- F. Insulation on hot piping and equipment shall be terminated square at items not to be insulated, access openings and nameplates. Cover all exposed raw insulation with white sealer or jacket material.
- G. Protect all insulations outside of buildings with aluminum jacket using lock joint or other approved system for a continuous weather tight system. Access doors and other items requiring maintenance or access shall be removable and sealable.
- H. HVAC work not to be insulated:
  - 1. Internally insulated ductwork and air handling units.
  - 2. Relief air ducts (Economizer cycle exhaust air).

- 3. Exhaust air ducts and plenums, and ventilation exhaust air shafts.
- 4. Equipment: Expansion tanks and hot water pumps.
- 5. In hot piping: Unions, flexible connectors, control valves, PRVs, safety valves and discharge vent piping, vacuum breakers, thermostatic vent valves, steam traps 20 mm (3/4 inch) and smaller, exposed piping through floor for convectors and radiators. Insulate piping to within approximately 75 mm (3 inches) of uninsulated items.
- I. Boiler plant work not to be insulated:
  - 1. Pipes, valves and fittings:
    - a. Flowmeter sensing piping and blowdown
    - b. Threaded valves
    - c. Check valves
    - d. Unions
    - e. Steam header drains
    - f. Pressure transmission to gages
    - g. Piping in control panels
  - 2. Equipment:
    - a. All nameplates
  - 3. Specialties:
    - a. Pressure reducing valves
    - b. Control valves-water and steam
    - c. Level sensors-piping, valves and blowdown
    - d. Strainers under 65 mm (2-1/2 inch) pipe size
    - e. Flexible connectors
- J. Apply insulation materials subject to the manufacturer's recommended temperature limits. Apply adhesives, mastic and coatings at the manufacturer's recommended minimum coverage.
- K. Elbows, flanges and other fittings shall be insulated with the same material as is used on the pipe straights. The elbow/ fitting insulation shall be field-fabricated, mitered or factory prefabricated to the necessary size and shape to fit on the elbow/ fitting. Use of polyurethane spray-foam to fill a PVC elbow jacket is prohibited on cold applications.
- L. Provide metal jackets over insulation as follows:
  - a. All piping and ducts exposed to outdoor weather.
  - b. A 50 mm (2 inch) overlap is required at longitudinal and circumferential joints.

## 3.2 INSULATION INSTALLATION

- A. Mineral Fiber Board:
  - 1. Faced board: Apply board on pins spaced not more than 300 mm (12 inches) on center each way, and not less than 75 mm (3 inches) from each edge of board. In addition to pins, apply insulation bonding adhesive to entire underside of horizontal metal surfaces. Butt insulation edges tightly and seal all joints with laps and butt strips. After applying speed clips cut pins off flush and apply vapor seal patches over clips.
  - 2. Plain board:

a. Insulation shall be scored, beveled or mitered to provide tight joints and be secured to equipment with bands spaced 225 mm (9 inches) on center for irregular surfaces or with pins and clips on flat surfaces. Use corner beads to protect edges of insulation.

- b. For hot equipment: Stretch 25 mm (1 inch) mesh wire, with edges wire laced together, over insulation and finish with insulating and finishing cement applied in one coat, 6 mm (1/4 inch) thick, trowel led to a smooth finish.
- c. For cold equipment: Apply meshed glass fabric in a tack coat 1.5 to 1.7 square meter per liter (60 to 70 square feet per gallon) of vapor mastic and finish with mastic at 0.3 to 0.4 square meter per liter (12 to 15 square feet per gallon) over the entire fabric surface.
- 3. Exposed, unlined ductwork and equipment in unfinished areas, mechanical and electrical equipment rooms and attics, and duct work exposed to outdoor weather:
  - a. 50 mm (2 inch) thick insulation faced with ASJ (white all service jacket): Supply air duct and afterfilter housing.
  - b. 40 mm (1-1/2 inch) thick insulation faced with ASJ: Return air duct, mixed air plenums and prefilter housing.
  - c. Outside air intake ducts: 25 mm (one inch) thick insulation faced with ASJ.
- 4. Hot equipment: 40 mm (1-1/2 inch) thick insulation faced with ASJ.
  - a. Convertors, air separators, steam condensate pump receivers.
  - b. Separation chambers on steam humidifiers located above ceilings.
- B. Molded Mineral Fiber Pipe and Tubing Covering:
  - Fit insulation to pipe or duct, aligning longitudinal joints. Seal longitudinal joint laps and
    circumferential butt strips by rubbing hard with a nylon sealing tool to assure a positive seal.
    Staples may be used to assist in securing insulation. Seal all vapor retarder penetrations on
    cold piping with a generous application of vapor barrier mastic. Provide inserts and install
    with metal insulation shields at outside pipe supports. Install freeze protection insulation
    over heating cable.
  - 2. Contractor's options for fitting, flange and valve insulation:
    - a. Insulating and finishing cement for sizes less than 100 mm (4 inches) operating at surface temperature of 16 degrees C (61 degrees F) or more.
    - b. Factory premolded, one piece PVC covers with mineral fiber, (Form B), inserts. Provide two insert layers for pipe temperatures below 4 degrees C (40 degrees F), or above 121 degrees C (250 degrees F). Secure first layer of insulation with twine. Seal seam edges with vapor barrier mastic and secure with fitting tape.
    - c. Factory molded, ASTM C547 or field mitered sections, joined with adhesive or wired in place. For hot piping finish with a smoothing coat of finishing cement. For cold fittings, 16 degrees C (60 degrees F) or less, vapor seal with a layer of glass fitting tape imbedded between two 2 mm (1/16 inch) coats of vapor barrier mastic.
    - d. Fitting tape shall extend over the adjacent pipe insulation and overlap on itself at least 50 mm (2 inches).
  - 3. Nominal thickness in millimeters and inches specified in table below, for piping above ground:

Nominal Thickness of	Molded Mi	neral Fib	er Insula	tion
Nominal Pipe Size, millimeters (inches):	25 (1) & below	32- 75 (1-1/4- 3)		200 (8) and above
a. 122-177 degrees C (251-350 F) (HPS, MPS,)	50 (2.0)	65 (2.5)	90 (3.5)	90 (3.5)
b. 100-121 degrees C HPR, MPR (212-250 degrees F) (Vent piping from PRV safety valves, condensate receivers, and flash tanks)	25 (1.0)	50 (2.0)	50 (2.0)	50 (2.0)
c. 38-99 degrees C (100- 211 degrees F) (LPR, PC, HWH, HWHR, GH, GHR)	25 (1.0)	40 (1.5)	50 (2.0)	50 (2.0)

# C. Rigid Cellular Phenolic Foam:

- 1. Rigid closed cell phenolic insulation may be provided for piping, ductwork and equipment for temperatures up to 121 degrees C (250 degrees F).
- 2. Note the NFPA 90A burning characteristics requirements of 25/50 in paragraph 1.3.B
- 3. Provide secure attachment facilities such as welding pins.
- 4. Apply insulation with joints tightly drawn together
- 5. Apply adhesives, coverings, neatly finished at fittings, and valves.
- 6. Final installation shall be smooth, tight, neatly finished at all edges.
- 7. Minimum thickness in millimeters (inches) specified in table below, for piping above ground:

Nominal Thickness of Rigid Closed-Cell Phenolic Foam Insulation					
Nominal Pipe Size millimeters (inches):	25 (1) & below	32-75 (1 1/4-3)	100-150 (4-6)	200-300 (8-12)	350 (14) & above
1. 100-121 degrees C (212- 250 degrees F), LPS, Vent piping from receivers and flash tanks.	15 (0.5)	25 (1)	25 (1)		
2. 38-99 degrees C (100-211 degrees F), LPR, PC, HWH, HWHR, GH and GHR.	15 (0.5)	20 (0.75)	25 (1)		-
3. 4-16 degrees C (40-60 degrees F), CH, CHR, GC, and GCR.	20 (0.75)	20 (0.75)	25 (1)	40 (1.5)	50 (2.0)

- 8. Condensation control insulation: Minimum 20 mm (0.75 inch) thick for all pipe sizes.
  - a. HVAC: Cooling coil condensation piping to waste piping fixture or drain inlet. Omit insulation on plastic piping in mechanical rooms.

- D. Cellular Glass Insulation:
  - 1. Pipe and tubing, covering nominal thickness in millimeters and inches as tabulated below for chilled water and refrigerant piping.

Nominal Thickness of	Cellular	Glass In	sulation	
Millimeters (inches)	Thru 38	50-	200-300	over
	(11/2)	150	(8-12)	350
		(2-6)		(14)
1. 4-16 degrees C (40-60	50	80	80	100
degrees F) (CH and CHR	(2.0)	(3.0)	(3.0)	(4.0)
within chiller room and				
pipe chase and underground)				
2. 4-16 degrees C (40-60	40	50	50	65
degrees F) (CH and CHR	(1.5)	(2.0)	(2.0)	(2.5)
outside chiller room)	,			


- 2. Cold equipment: 50 mm (2 inch) thick insulation faced with ASJ for chilled water pumps, water filters, chemical feeder pots or tanks, expansion tanks, air separators and air purgers.
- E. Polyisocyanurate Closed-Cell Rigid Insulation:
  - 1. Polyisocyanurate closed-cell rigid insulation (PIR) may be provided for piping, equipment and ductwork for temperature up to 149 degree C (300 degree F) provided insulation thickness requirement does not exceed 38 mm (1.5 inches).
  - 2. Install insulation, vapor retarder and jacketing per manufacturer's recommendations. Particular attention should be paid to recommendations for joint staggering, adhesive application, external hanger design, expansion/contraction joint design and spacing and vapor retarder integrity.
  - 3. Install insulation with all joints tightly butted (except expansion) joints in hot applications).
  - 4. If insulation thickness exceeds 63 mm (2.5 inches), install as a double layer system with longitudinal (lap) and butt joint staggering as recommended by manufacturer.
  - 5. For cold applications, vapor retarder shall be installed in a continuous manner. No staples, rivets, screws or any other attachment device capable of penetrating the vapor retarder shall be used to attach the vapor retarder or jacketing. No wire ties capable of penetrating the vapor retarder shall be used to hold the insulation in place. Banding shall be used to attach PVC or metal jacketing.
  - 6. Elbows, flanges and other fittings shall be insulated with the same material as is used on the pipe straights. The elbow/ fitting insulation shall be field-fabricated, mitered or factory prefabricated to the necessary size and shape to fit on the elbow/ fitting. Use of polyurethane spray-foam to fill PVC elbow jacket is prohibited on cold applications.
  - 7. For cold applications, the vapor retarder on elbows/fittings shall be either mastic-fabric-mastic or 2 mil thick PVDC vapor retarder adhesive tape.
  - 8. All PVC and metal jacketing shall be installed so as to naturally shed water. Joints shall point down and shall be sealed with either adhesive or caulking (except for periodic slip joints).
  - 9. Note the NFPA 90A burning characteristic requirements of 25/50 in paragraph 1.3B. Refer to paragraph 3.1 for items not to be insulated.
  - 10. Minimum thickness in millimeter (inches) specified in table below, for piping:

03/14/2012 PHASE 2

Nominal Thickness o	of Polyis	ocyanurate	Rigid In	sulation
Nominal Pipe Size millimeters(inches):	25(1) & below	32-75 (1 1/4- 3)	100-150 (4-6)	200-300 (8-12)
1. 122-149 degree C(251-300 degree F) (HPS, MPS)	40 (1.5)			
2. 100-121 degrees C (211-250 degrees F), HPR, MPR, LPS, Vent piping from receivers and flash tanks	20 (0.75)	40(1.5)	40(1.5)	40(1.50)
3. 38-99 degrees C (100-211 degrees F), LPR, PC, HWH, HWHR, GH and GHR	20 (0.75)	25(1.0)	40(1.5)	40(1.50)
4. 4-16 degrees C (40-60 degrees F), CH, CHR, GC and GCR for relative humidity up to 80 percent or underground location	25 (1.00	25 (1.0)	40 (1.50	40(1.5)
5. 4-16 degrees C(40-60 degrees F) CH, CHR, GC and GCR for relative humidity 80 to 90 percent or higher	40 (1.50	40 (1.5)	40 (1.5)	40 (1.5)

- 11. Condensation control insulation: Minimum 20 mm (0.75 inch) thick for all pipe sizes.
  - a. HVAC: Cooling coil condensation piping to waste piping fixture or drain inlet. Omit insulation on plastic piping in mechanical rooms.

END OF SECTION 23 07 11



# SECTION 23 09 23 DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Direct-digital controls shall be provided by Johnson Controls (Syracuse or Rochester office).
- B. Controls vendor to provide all necessary devices and materials if not provided elsewhere in this specification, including but not limited to, valves, sensors, actuators, switches, conduit, wiring, graphics and programming as required for a complete and operable system reporting to the facilities existing Johnson Controls head end.
- C. Some products are furnished but not installed by the contractor administered by this Section of the technical specifications. The contractor administered by this Section of the technical specifications shall formally coordinate in writing and receive from other contractors formal acknowledgements in writing prior to submission the installation of the products. These products may include the following:
  - Control valves.
  - 2. Flow switches.
  - 3. Flow meters.
  - 4. Sensor wells and sockets in piping.
  - 5. Terminal unit controllers.
- D. Some products are not provided by, but are nevertheless integrated with the work executed by, the contractor administered by this Section of the technical specifications. The contractor administered by this Section of the technical specifications shall formally coordinate in writing and receive from other contractors formal acknowledgements in writing prior to submission the particulars of the products. These products include the following:
  - 1. Fire alarm systems. If zoned fire alarm is required by the project-specific requirements, this interface shall require multiple relays, which are provided and installed by the fire alarm system contractor, to be monitored.
  - 2. Variable frequency drives. These controls, if not native BACnet, will require a BACnet Gateway.

#### E. Responsibility Table:

Work/Item/System	Furnish	Install	Low Voltage Wiring	Line Power
Control system low voltage and communication wiring	23 09 23	23 09 23	23 09 23	N/A
Terminal units	23	23	N/A	26
Controllers for terminal units	23	23	23 09 23	16
LAN conduits and raceway	23 09 23	23 09 23	N/A	N/A

Work/Item/System	Furnish	Install	Low Voltage Wiring	Line Power
Automatic dampers (not furnished with equipment)	23 09 23	23	N/A	N/A
Automatic damper actuators	23 09 23	23 09 23	23 09 23	23 09 23
Manual valves	23	23	N/A	N/A
Automatic valves	23 09 23	23	23 09 23	23 09 23
Pipe insertion devices and taps, flow and pressure stations.	23	23	N/A	N/A
Thermowells	23 09 23	23	N/A	N/A
Current Switches	23 09 23	23 09 23	23 09 23	N/A
Control Relays	23 09 23	23 09 23	23 09 23	N/A
Power distribution system monitoring interfaces	23 09 23	23 09 23	23 09 23	26
All control system nodes, equipment, housings, enclosures and panels.	23 09 23	23 09 23	23 09 23	26
Smoke detectors	28 31 00	28 31 00	28 31 00	28 31 00
Water treatment system	23	23	23	26
VFDs	23	26	23 09 23	26
Fire Alarm shutdown relay interlock wiring	28	28	28	26
Control system monitoring of fire alarm smoke control relay	28	28	23 09 23	28
Starters, HOA switches	23	23	N/A	26

F. This facility's existing direct-digital control system is manufactured by Johnson Controls (Syracuse). The contractor administered by this Section of the technical specifications shall observe the capabilities, communication network, services, spare capacity of the existing control system and its ECC prior to beginning work.

## 1.2 DEFINITION

- A. Algorithm: A logical procedure for solving a recurrent mathematical problem; A prescribed set of well-defined rules or processes for the solution of a problem in a finite number of steps.
- B. ARCNET: ANSI/ATA 878.1 Attached Resource Computer Network. ARCNET is a deterministic LAN technology; meaning it's possible to determine the maximum delay before a device is able to transmit a message.
- C. Analog: A continuously varying signal value (e.g., temperature, current, velocity etc.
- D. BACnet: A Data Communication Protocol for Building Automation and Control Networks, ANSI/ASHRAE Standard 135. This communications protocol allows diverse building automation devices to communicate data over and services over a network.

E. BACnet/IP: Annex J of Standard 135. It defines and allows for using a reserved UDP socket to transmit BACnet messages over IP networks. A BACnet/IP network is a collection of one or more IP sub-networks that share the same BACnet network number.

- F. BACnet Internetwork: Two or more BACnet networks connected with routers. The two networks may sue different LAN technologies.
- G. BACnet Network: One or more BACnet segments that have the same network address and are interconnected by bridges at the physical and data link layers.
- H. BACnet Segment: One or more physical segments of BACnet devices on a BACnet network, connected at the physical layer by repeaters.
- I. BACnet Broadcast Management Device (BBMD): A communications device which broadcasts BACnet messages to all BACnet/IP devices and other BBMDs connected to the same BACnet/IP network.
- J. BACnet Interoperability Building Blocks (BIBBs): BACnet Interoperability Building Blocks (BIBBs) are collections of one or more BACnet services. These are prescribed in terms of an "A" and a "B" device. Both of these devices are nodes on a BACnet internetwork.
- K. BACnet Testing Laboratories (BTL). The organization responsible for testing products for compliance with the BACnet standard, operated under the direction of BACnet International.
- L. Baud: It is a signal change in a communication link. One signal change can represent one or more bits of information depending on type of transmission scheme. Simple peripheral communication is normally one bit per Baud. (e.g., Baud rate = 78,000 Baud/sec is 78,000 bits/sec, if one signal change = 1 bit).
- M. Binary: A two-state system where a high signal level represents an "ON" condition and an "OFF" condition is represented by a low signal level.
- N. BMP or bmp: Suffix, computerized image file, used after the period in a DOS-based computer file to show that the file is an image stored as a series of pixels.
- O. Bus Topology: A network topology that physically interconnects workstations and network devices in parallel on a network segment.
- P. Control Unit (CU): Generic term for any controlling unit, stand-alone, microprocessor based, digital controller residing on secondary LAN or Primary LAN, used for local controls or global controls
- Q. Deadband: A temperature range over which no heating or cooling is supplied, i.e., 22-25 degrees C (72-78 degrees F), as opposed to a single point change over or overlap).
- R. Device: a control system component that contains a BACnet Device Object and uses BACnet to communicate with other devices.

S. Device Object: Every BACnet device requires one Device Object, whose properties represent the network visible properties of that device. Every Device Object requires a unique Object Identifier number on the BACnet internetwork. This number is often referred to as the device instance.

- T. Device Profile: A specific group of services describing BACnet capabilities of a device, as defined in ASHRAE Standard 135-2008, Annex L. Standard device profiles include BACnet Operator Workstations (B-OWS), BACnet Building Controllers (B-BC), BACnet Advanced Application Controllers (B-AAC), BACnet Application Specific Controllers (B-ASC), BACnet Smart Actuator (B-SA), and BACnet Smart Sensor (B-SS). Each device used in new construction is required to have a PICS statement listing which service and BIBBs are supported by the device.
- U. Diagnostic Program: A software test program, which is used to detect and report system or peripheral malfunctions and failures. Generally, this system is performed at the initial startup of the system.
- V. Direct Digital Control (DDC): Microprocessor based control including Analog/Digital conversion and program logic. A control loop or subsystem in which digital and analog information is received and processed by a microprocessor, and digital control signals are generated based on control algorithms and transmitted to field devices in order to achieve a set of predefined conditions.
- W. Distributed Control System: A system in which the processing of system data is decentralized and control decisions can and are made at the subsystem level. System operational programs and information are provided to the remote subsystems and status is reported back to the Engineering Control Center. Upon the loss of communication with the Engineering Control center, the subsystems shall be capable of operating in a stand-alone mode using the last best available data.
- X. Download: The electronic transfer of programs and data files from a central computer or operation workstation with secondary memory devices to remote computers in a network (distributed) system.
- Y. DXF: An AutoCAD 2-D graphics file format. Many CAD systems import and export the DXF format for graphics interchange.
- Z. Electrical Control: A control circuit that operates on line or low voltage and uses a mechanical means, such as a temperature sensitive bimetal or bellows, to perform control functions, such as actuating a switch or positioning a potentiometer.
- AA. Electronic Control: A control circuit that operates on low voltage and uses a solid-state components to amplify input signals and perform control functions, such as operating a relay or providing an output signal to position an actuator.
- BB. Engineering Control Center (ECC): The centralized control point for the intelligent control network. The ECC comprises of personal computer and connected devices to form a single workstation.
- CC. Ethernet: A trademark for a system for exchanging messages between computers on a local area network using coaxial, fiber optic, or twisted-pair cables.

DD. Firmware: Firmware is software programmed into read only memory (ROM) chips. Software may not be changed without physically altering the chip.

- EE. Gateway: Communication hardware connecting two or more different protocols. It translates one protocol into equivalent concepts for the other protocol. In BACnet applications, a gateway has BACnet on one side and non-BACnet (usually proprietary) protocols on the other side.
- FF. GIF: Abbreviation of Graphic interchange format.
- GG. Graphic Program (GP): Program used to produce images of air handler systems, fans, chillers, pumps, and building spaces. These images can be animated and/or color-coded to indicate operation of the equipment.
- HH. Graphic Sequence of Operation: It is a graphical representation of the sequence of operation, showing all inputs and output logical blocks.
- II. I/O Unit: The section of a digital control system through which information is received and transmitted. I/O refers to analog input (AI, digital input (DI), analog output (AO) and digital output (DO). Analog signals are continuous and represent temperature, pressure, flow rate etc, whereas digital signals convert electronic signals to digital pulses (values), represent motor status, filter status, on-off equipment etc.
- JJ. I/P: a method for conveying and routing packets of information over LAN paths. User Datagram Protocol (UDP) conveys information to "sockets" without confirmation of receipt. Transmission Control Protocol (TCP) establishes "sessions", which have end-to-end confirmation and guaranteed sequence of delivery.
- KK. JPEG: A standardized image compression mechanism stands for Joint Photographic Experts Group, the original name of the committee that wrote the standard.
- LL. Local Area Network (LAN): A communication bus that interconnects operator workstation and digital controllers for peer-to-peer communications, sharing resources and exchanging information.
- MM. Network Repeater: A device that receives data packet from one network and rebroadcasts to another network. No routing information is added to the protocol.
- NN. MS/TP: Master-slave/token-passing (ISO/IEC 8802, Part 3). It is not an acceptable LAN option for VA health-care facilities. It uses twistedpair wiring for relatively low speed and low cost communication.
- 00. Native BACnet Device: A device that uses BACnet as its primary method of communication with other BACnet devices without intermediary gateways. A system that uses native BACnet devices at all levels is a native BACnet system.
- PP. Network Number: A site-specific number assigned to each network segment to identify for routing. This network number must be unique throughout the BACnet internetwork.

QQ. Object: The concept of organizing BACnet information into standard components with various associated properties. Examples include analog input objects and binary output objects.

- RR. Object Identifier: An object property used to identify the object, including object type and instance. Object Identifiers must be unique within a device.
- SS. Object Properties: Attributes of an object. Examples include present value and high limit properties of an analog input object. Properties are defined in ASHRAE 135; some are optional and some are required. Objects are controlled by reading from and writing to object properties.
- TT. Operating system (OS): Software, which controls the execution of computer application programs.
- UU. PCX: File type for an image file. When photographs are scanned onto a personal computer they can be saved as PCX files and viewed or changed by a special application program as Photo Shop.
- VV. Peripheral: Different components that make the control system function as one unit. Peripherals include monitor, printer, and I/O unit.
- WW. Peer-to-Peer: A networking architecture that treats all network stations as equal partners- any device can initiate and respond to communication with other devices.
- XX. PICS: Protocol Implementation Conformance Statement, describing the BACnet capabilities of a device. All BACnet devices have published PICS.
- YY. PID: Proportional, integral, and derivative control, used to control modulating equipment to maintain a setpoint.
- ZZ. Repeater: A network component that connects two or more physical segments at the physical layer.
- AAA. Router: a component that joins together two or more networks using different LAN technologies. Examples include joining a BACnet Ethernet LAN to a BACnet MS/TP LAN.
- BBB. Sensors: devices measuring state points or flows, which are then transmitted back to the DDC system.
- CCC. Thermostats: devices measuring temperatures, which are used in control of standalone or unitary systems and equipment not attached to the DDC system.

# 1.3 QUALITY ASSURANCE

#### A. Criteria:

1. Single Source Responsibility of subcontractor: The Contractor shall obtain hardware and software supplied under this Section and delegate the responsibility to a single source controls installation subcontractor. The controls subcontractor shall be responsible for the

- complete design, installation, and commissioning of the system. The controls subcontractor shall be in the business of design, installation and service of such building automation control systems similar in size and complexity.
- Equipment and Materials: Equipment and materials shall be cataloged products of manufacturers regularly engaged in production and installation of HVAC control systems.
   Products shall be manufacturer's latest standard design and have been tested and proven in actual use.
- 3. The controls subcontractor shall provide a list of no less than five similar projects which have building control systems as specified in this Section. These projects must be on-line and functional such that the Department of Veterans Affairs (VA) representative would observe the control systems in full operation.
- 4. The controls subcontractor shall have in-place facility within 50 miles with technical staff, spare parts inventory for the next five (5) years, and necessary test and diagnostic equipment to support the control systems.
- 5. The controls subcontractor shall have minimum of three years experience in design and installation of building automation systems similar in performance to those specified in this Section. Provide evidence of experience by submitting resumes of the project manager, the local branch manager, project engineer, the application engineering staff, and the electronic technicians who would be involved with the supervision, the engineering, and the installation of the control systems. Training and experience of these personnel shall not be less than three years. Failure to disclose this information will be a ground for disqualification of the supplier.
- 6. Provide a competent and experienced Project Manager employed by the Controls Contractor. The Project Manager shall be supported as necessary by other Contractor employees in order to provide professional engineering, technical and management service for the work. The Project Manager shall attend scheduled Project Meetings as required and shall be empowered to make technical, scheduling and related decisions on behalf of the Controls Contractor.

## B. Codes and Standards:

- 1. All work shall conform to the applicable Codes and Standards.
- 2. Electronic equipment shall conform to the requirements of FCC Regulation, Part 15, Governing Radio Frequency Electromagnetic Interference, and be so labeled.

# 1.4 PERFORMANCE

- A. The system shall conform to the following:
  - 1. Graphic Display: The system shall display up to four (4) graphics on a single screen with a minimum of twenty (20) dynamic points per graphic. All current data shall be displayed within ten (10) seconds of the request.
  - 2. Graphic Refresh: The system shall update all dynamic points with current data within eight (8) seconds. Data refresh shall be automatic, without operator intervention.
  - 3. Object Command: The maximum time between the command of a binary object by the operator and the reaction by the device shall be two(2) seconds. Analog objects shall start to adjust within two (2) seconds.
  - 4. Object Scan: All changes of state and change of analog values shall be transmitted over the high-speed network such that any data used or displayed at a controller or work-station will be current, within the prior six (6) seconds.

5. Alarm Response Time: The maximum time from when an object goes into alarm to when it is annunciated at the workstation shall not exceed (10) seconds.

- 6. Program Execution Frequency: Custom and standard applications shall be capable of running as often as once every (5) seconds. The Contractor shall be responsible for selecting execution times consistent with the mechanical process under control.
- 7. Multiple Alarm Annunciations: All workstations on the network shall receive alarms within five (5) seconds of each other.
- 8. Performance: Programmable Controllers shall be able to execute DDC PID control loops at a selectable frequency from at least once every one (1) second. The controller shall scan and update the process value and output generated by this calculation at this same frequency.
- 9. Reporting Accuracy: Listed below are minimum acceptable reporting end-to-end accuracies for all values reported by the specified system:

Measured Variable	Reported Accuracy
Ducted air temperature	±0.5°C [±1°F]
Outdoor air temperature	±1.0°C [±2°F]
Dew Point	±1.5°C [±3°F]
Water temperature	±0.5°C [±1°F]
Relative humidity	±2% RH
Water flow	±1% of reading
Air pressure (ducts)	±25 Pa [±0.1"w.c.]
Electrical Power	±0.5% of reading

Note 1: for both absolute and differential pressure

10. Control stability and accuracy: Control sequences shall maintain measured variable at setpoint within the following tolerances:

Controlled Variable	Control Accuracy	Range of Medium		
Air Pressure	±3 Pa (±0.01 in. w.g.)	-25 to 25 Pa		
		(-0.1 to 0.1 in. w.g.)		
Airflow	±10% of full scale			
Space Temperature	±1.0°C (±2.0°F)			
Duct Temperature	±1.5°C (±3°F)			
Humidity	±5% RH			
Fluid Pressure	±250 Pa (±1.0 in. w.g.)	0-12.5 kPa		
		(0-50 in. w.g.)		
		differential		

11. Extent of direct digital control: control design shall allow for at least the points indicated on the points lists on the drawings.

# 1.5 WARRANTY

- A. Labor and materials for control systems shall be warranted for a period as specified under Warranty in FAR clause 52.246-21.
- B. Control system failures during the warranty period shall be adjusted, repaired, or replaced at no cost or reduction in service to the owner. The system includes all computer equipment, transmission equipment, and all sensors and control devices.
- C. The on-line support service shall allow the Controls supplier to dial out over telephone lines to or connect via (through password-limited

access) VPN through the internet monitor and control the facility's building automation system. This remote connection to the facility shall be within two (2) hours of the time that the problem is reported. This coverage shall be extended to include normal business hours, after business hours, weekend and holidays. If the problem cannot be resolved with on-line support services, the Controls supplier shall dispatch the qualified personnel to the job site to resolve the problem within 24 hours after the problem is reported.

D. Controls and Instrumentation subcontractor shall be responsible for temporary operations and maintenance of the control systems during the construction period until final commissioning, training of facility operators and acceptance of the project by VA.

# 1.6 SUBMITTALS

- A. Submit shop drawings in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's literature and data for all components including the following:
  - A wiring diagram for each type of input device and output device including DDC controllers, modems, repeaters, etc. Diagram shall show how the device is wired and powered, showing typical connections at the digital controllers and each power supply, as well as the device itself. Show for all field connected devices, including but not limited to, control relays, motor starters, electric or electronic actuators, and temperature pressure, flow and humidity sensors and transmitters.
  - 2. A diagram of each terminal strip, including digital controller terminal strips, terminal strip location, termination numbers and the associated point names.
  - 3. Control dampers and control valves schedule, including the size and pressure drop.
  - 4. Control air-supply components, and computations for sizing compressors, receivers and main air-piping, if pneumatic controls are furnished.
  - 5. Catalog cut sheets of all equipment used. This includes, but is not limited to software (by manufacturer and by third parties), DDC controllers, panels, peripherals, airflow measuring stations and associated components, and auxiliary control devices such as sensors, actuators, and control dampers. When manufacturer's cut sheets apply to a product series rather than a specific product, the data specifically applicable to the project shall be highlighted. Each submitted piece of literature and drawings should clearly reference the specification and/or drawings that it supposed to represent.
  - 6. Sequence of operations for each HVAC system and the associated control diagrams. Equipment and control labels shall correspond to those shown on the drawings.
  - 7. Color prints of proposed graphics with a list of points for display.
  - 8. Furnish a BACnet Protocol Implementation Conformance Statement (PICS) for each BACnet-compliant device.
  - Schematic wiring diagrams for all control, communication and power wiring. Provide a schematic drawing of the central system installation. Label all cables and ports with computer manufacturers' model numbers and functions. Show all interface wiring to the control system.
  - 10. An instrumentation list for each controlled system. Each element of the controlled system shall be listed in table format. The table shall show element name, type of device, manufacturer, model number, and product data sheet number.

- 11. Riser diagrams of wiring between central control unit and all control panels.
- 12. Scaled plan drawings showing routing of LAN and locations of control panels, controllers, routers, gateways, ECC, and larger controlled devices.
- 13. Construction details for all installed conduit, cabling, raceway, cabinets, and similar. Construction details of all penetrations and their protection.
- 14. Quantities of submitted items may be reviewed but are the responsibility of the contractor administered by this Section of the technical specifications.
- C. Product Certificates: Compliance with Article, QUALITY ASSURANCE.
- D. Licenses: Provide licenses for all software residing on and used by the Controls Systems and transfer these licenses to the Owner prior to completion.
- E. As Built Control Drawings:
  - 1. Furnish three (3) copies of as-built drawings for each control system. The documents shall be submitted for approval prior to final completion.
  - 2. Furnish one (1) stick set of applicable control system prints for each mechanical system for wall mounting. The documents shall be submitted for approval prior to final completion.
  - 3. Furnish one (1) CD-ROM in CAD DWG and/or .DXF format for the drawings noted in subparagraphs above.
- F. Operation and Maintenance (O/M) Manuals):
  - 1. Submit in accordance with Article, INSTRUCTIONS, in Specification Section 01 00 00, GENERAL REQUIREMENTS.
  - 2. Include the following documentation:
    - a. General description and specifications for all components, including logging on/off, alarm handling, producing trend reports, overriding computer control, and changing set points and other variables.
    - b. Detailed illustrations of all the control systems specified for ease of maintenance and repair/replacement procedures, and complete calibration procedures.
    - c. One copy of the final version of all software provided including operating systems, programming language, operator workstation software, and graphics software.
    - d. Complete troubleshooting procedures and guidelines for all systems.
    - e. Complete operating instructions for all systems.
    - f. Recommended preventive maintenance procedures for all system components including a schedule of tasks for inspection, cleaning and calibration. Provide a list of recommended spare parts needed to minimize downtime.
    - g. Training Manuals: Submit the course outline and training material to the Owner for approval three (3) weeks prior to the training to VA facility personnel. These persons will be responsible for maintaining and the operation of the control systems, including programming. The Owner reserves the right to modify any or all of the course outline and training material.
    - h. Licenses, guaranty, and other pertaining documents for all equipment and systems.
- G. Submit Performance Report to Engineer prior to final inspection.

03/14/2012 PHASE 2

#### 1.7 INSTRUCTIONS

A. Instructions to VA operations personnel: Perform in accordance with Article, INSTRUCTIONS, in Specification Section 01 00 00, GENERAL REQUIREMENTS, and as noted below.

- 1. First Phase: Formal instructions to the VA facilities personnel for a total of 16 hours, given in multiple training sessions (each no longer than four hours in length), conducted sometime between the completed installation and prior to the performance test period of the control system, at a time mutually agreeable to the Contractor and the VA.
- 2. The O/M Manuals shall contain approved submittals as outlined in Article 1.7, SUBMITTALS. The Controls subcontractor will review the manual contents with VA facilities personnel during second phase of training.
- 3. Training shall be given by direct employees of the controls system subcontractor.

#### 1.8 PROJECT CONDITIONS (ENVIRONMENTAL CONDITIONS OF OPERATION)

- A. The ECC and peripheral devices and system support equipment shall be designed to operate in ambient condition of 20 to  $35^{\circ}\text{C}$  (65 to  $90^{\circ}\text{F}$ ) at a relative humidity of 20 to 80% non-condensing.
- B. The CUs used outdoors shall be mounted in NEMA 4 waterproof enclosures, and shall be rated for operation at -40 to  $65^{\circ}\text{C}$  (-40 to  $150^{\circ}\text{F}$ ).
- C. All electronic equipment shall operate properly with power fluctuations of plus 10 percent to minus 15 percent of nominal supply voltage.
- D. Sensors and controlling devices shall be designed to operate in the environment, which they are sensing or controlling.

# 1.9 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. American Society of Heating, Refrigerating, and Air-Conditioning Engineers (ASHRAE):

Standard 135-08 ...... BACNET Building Automation and Control Networks

C.	American	Society	οf	Mechanical	Engineers	(ASME	):
$\sim$ .	TILLET TOUT	DOCICE	$\circ$	I I C CII C I I C C I	TITI TITLE CT D	( 1101.11	, -

B16.18-05	. Cast Copper Alloy Solder Joint Pressure Fittings.
B16.22-05	. Wrought Copper and Copper Alloy Solder Joint Pressure Fittings.

D	Amoriaan	Coaiota	٥f	Toating	Materials	/ A CTM ) •
D.	American	Society	OI	Testing	Materials	(ASTM):

American Society of Test	cing materials (ASIM):
B32-04	. Standard Specification for Solder Metal
B88-03	. Standard Specifications for Seamless Copper Water Tube
B88M-05	. Standard Specification for Seamless Copper Water Tube
	(Metric)
B280-03	. Standard Specification for Seamless Copper Tube for Air-
	Conditioning and Refrigeration Field Service
D2737-03	. Standard Specification for Polyethylene (PE) Plastic Tubing

E. Federal Communication Commission (FCC): Rules and Regulations Title 47 Chapter 1-2001 Part 15: Radio Frequency Devices.

F.	Institute	of	Electrical	and Electronic Engineers	(IEEE):
	802.3-05			. Information Technology-Telecom	munications and Information
				Exchange between Systems-Loca	l and Metropolitan Area
				Networks- Specific Requirements	-Part 3: Carrier Sense Multiple
				Access with Collision Detection (C	CSMA/CD) Access method and
				Physical Layer Specifications	

G.	National	Fire	Protection	Asso	ci	ati	on	(1	NFPA)	:

70-08	National Electric Code
90A-09	Standard for Installation of Air-Conditioning and Ventilation
	Systems

H. Underwriter Laboratories Inc (UL):

94-06	Tests for Flammability of Plastic Materials for Parts and Devices
	and Appliances
294-05	Access Control System Units
486A/486B-04	Wire Connectors
555S-06	Standard for Smoke Dampers
916-07	Energy Management Equipment
1076-05	Proprietary Burglar Alarm Units and Systems

# PART 2 - PRODUCTS

# 2.1 MATERIALS

A. Use new products that the manufacturer is currently manufacturing and that have been installed in a minimum of 25 installations. Spare parts shall be available for at least five years after completion of this contract.

# PART 3 - EXECUTION

#### 3.1 INSTALLATION

#### A. General:

- 1. Examine project plans for control devices and equipment locations; and report any discrepancies, conflicts, or omissions to COR for resolution before proceeding for installation.
- 2. Work Coordination: GENERAL CONDITIONS.
- 3. Install equipment, piping, wiring /conduit parallel to or at right angles to building lines.
- 4. Install all equipment and piping in readily accessible locations. Do not run tubing and conduit concealed under insulation or inside ducts.
- 5. Mount control devices, tubing and conduit located on ducts and apparatus with external insulation on standoff support to avoid interference with insulation.
- 6. Provide sufficient slack and flexible connections to allow for vibration of piping and equipment.

7. Run wire connecting devices on or in control cabinets parallel with the sides of the cabinet neatly racked to permit tracing.

8. Install equipment level and plumb.

#### B. Electrical Wiring Installation:

- All wiring cabling shall be installed in conduits. Install conduits and wiring in accordance
  with Specification Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS.
  Conduits carrying control wiring and cabling shall be dedicated to the control wiring and
  cabling: these conduits shall not carry power wiring. Provide plastic end sleeves at all
  conduit terminations to protect wiring from burrs.
- 2. Install analog signal and communication cables in conduit and in accordance with Specification Section 26 05 21. Install digital communication cables in conduit and in accordance with Specification Section 27 15 00, Communications Horizontal Cabling.
- 3. Install conduit and wiring between operator workstation(s), digital controllers, electrical panels, indicating devices, instrumentation, miscellaneous alarm points, thermostats, and relays as shown on the drawings or as required under this section.
- 1. Install all electrical work required for a fully functional system and not shown on electrical plans or required by electrical specifications. Where low voltage (less than 50 volt) power is required, provide suitable Class B transformers.
- 5. Install all system components in accordance with local Building Code and National Electric Code.
  - a. Splices: Splices in shielded and coaxial cables shall consist of terminations and the use of shielded cable couplers. Terminations shall be in accessible locations. Cables shall be harnessed with cable ties.
  - b. Equipment: Fit all equipment contained in cabinets or panels with service loops, each loop being at least 300 mm (12 inches) long. Equipment for fiber optics system shall be rack mounted, as applicable, in ventilated, self-supporting, code gauge steel enclosure. Cables shall be supported for minimum sag.
  - c. Cable Runs: Keep cable runs as short as possible. Allow extra length for connecting to the terminal board. Do not bend flexible coaxial cables in a radius less than ten times the cable outside diameter.
  - d. Use vinyl tape, sleeves, or grommets to protect cables from vibration at points where they pass around sharp corners, through walls, panel cabinets, etc.
- 6. Conceal cables, except in mechanical rooms and areas where other conduits and piping are exposed.
- 7. Permanently label or code each point of all field terminal strips to show the instrument or item served. Color-coded cable with cable diagrams may be used to accomplish cable identification.
- 8. Grounding: ground electrical systems per manufacturer's written requirements for proper and safe operation.

# C. Install Sensors and Controls:

- 1. Temperature Sensors:
  - a. Install all sensors and instrumentation according to manufacturer's written instructions. Temperature sensor locations shall be readily accessible, permitting quick replacement and servicing of them without special skills and tools.

- b. Calibrate sensors to accuracy specified, if not factory calibrated.
- c. Use of sensors shall be limited to its duty, e.g., duct sensor shall not be used in lieu of room sensor.
- d. Install room sensors permanently supported on wall frame. They shall be mounted at 1.5 meter (5.0 feet) above the finished floor.
- e. Mount sensors rigidly and adequately for the environment within which the sensor operates. Separate extended-bulb sensors from contact with metal casings and coils using insulated standoffs.
- f. Sensors used in mixing plenum, and hot and cold decks shall be of the averaging of type. Averaging sensors shall be installed in a serpentine manner horizontally across duct. Each bend shall be supported with a capillary clip.
- g. All pipe mounted temperature sensors shall be installed in wells.
- h. All wires attached to sensors shall be air sealed in their conduits or in the wall to stop air transmitted from other areas affecting sensor reading.
- i. Permanently mark terminal blocks for identification. Protect all circuits to avoid interruption of service due to short-circuiting or other conditions. Line-protect all wiring that comes from external sources to the site from lightning and static electricity.
- 2. Pressure Sensors:
- a. Install duct static pressure sensor tips facing directly downstream of airflow.
- b. Install high-pressure side of the differential switch between the pump discharge and the check valve.
- c. Install snubbers and isolation valves on steam pressure sensing devices.

#### 3. Actuators:

- a. Mount and link damper and valve actuators according to manufacturer's written instructions.
- b. Check operation of damper/actuator combination to confirm that actuator modulates damper smoothly throughout stroke to both open and closed position.
- c. Check operation of valve/actuator combination to confirm that actuator modulates valve smoothly in both open and closed position.

#### 4. Flow Switches:

- a. Install flow switch according to manufacturer's written instructions.
- b. Mount flow switch a minimum of 5 pipe diameters up stream and 5 pipe diameters downstream or 600 mm (2 feet) whichever is greater, from fittings and other obstructions.
- c. Assure correct flow direction and alignment.
- d. Mount in horizontal piping-flow switch on top of the pipe.

#### D. Installation of network:

# 1. Ethernet:

- a. The network shall employ Ethernet LAN architecture, as defined by IEEE 802.3. The Network Interface shall be fully Internet Protocol (IP) compliant allowing connection to currently installed IEEE 802.3, Compliant Ethernet Networks.
- b. The network shall directly support connectivity to a variety of cabling types. As a minimum provide the following connectivity: 100 Base TX (Category 5e cabling) for the communications between the ECC and the B-BC and the B-AAC controllers.
- 2. Third party interfaces: Contractor shall integrate real-time data from building systems by other trades and databases originating from other manufacturers as specified and required to make the system work as one system.

# E. Installation of digital controllers and programming:

- 1. Provide a separate digital control panel for each major piece of equipment, such as air handling unit, chiller, pumping unit etc. Points used for control loop reset such as outdoor air, outdoor humidity, or space temperature could be located on any of the remote control units.
- 2. Provide sufficient internal memory for the specified control sequences and trend logging. There shall be a minimum of 25 percent of available memory free for future use.
- 3. System point names shall be modular in design, permitting easy operator interface without the use of a written point index.
- 4. Provide software programming for the applications intended for the systems specified, and adhere to the strategy algorithms provided.
- 5. Provide graphics for each piece of equipment and floor plan in the building. This includes each chiller, cooling tower, air handling unit, fan, terminal unit, boiler, pumping unit etc. These graphics shall show all points dynamically as specified in the point list.

# 3.2 SYSTEM VALIDATION AND DEMONSTRATION

A. As part of final system acceptance, a system demonstration is required (see below). Prior to start of this demonstration, the contractor is to perform a complete validation of all aspects of the controls and instrumentation system.

#### B. Validation

- 1. Prepare and submit for approval a validation test plan including test procedures for the performance verification tests. Test Plan shall address all specified functions of the ECC and all specified sequences of operation. Explain in detail actions and expected results used to demonstrate compliance with the requirements of this specification. Explain the method for simulating the necessary conditions of operation used to demonstrate performance of the system. Test plan shall include a test check list to be used by the Installer's agent to check and initial that each test has been successfully completed. Deliver test plan documentation for the performance verification tests to the owner's representative 30 days prior to start of performance verification tests. Provide draft copy of operation and maintenance manual with performance verification test.
- 2. After approval of the validation test plan, installer shall carry out all tests and procedures therein. Installer shall completely check out, calibrate, and test all connected hardware and

software to insure that system performs in accordance with approved specifications and sequences of operation submitted. Installer shall complete and submit Test Check List.

#### C. Demonstration

- System operation and calibration to be demonstrated by the installer in the presence of the Architect or VA's representative on random samples of equipment as dictated by the Architect or VA's representative. Should random sampling indicate improper commissioning, the owner reserves the right to subsequently witness complete calibration of the system at no addition cost to the VA.
- 2. Demonstrate to authorities that all required safeties and life safety functions are fully functional and complete.
- 3. Make accessible, personnel to provide necessary adjustments and corrections to systems as directed by balancing agency.
- 4. The following witnessed demonstrations of field control equipment shall be included:
  - a. Observe HVAC systems in shut down condition. Check dampers and valves for normal position.
  - b. Test application software for its ability to communicate with digital controllers, operator workstation, and uploading and downloading of control programs.
  - c. Demonstrate the software ability to edit the control program off-line.
  - d. Demonstrate reporting of alarm conditions for each alarm and ensure that these alarms are received at the assigned location, including operator workstations.
  - e. Demonstrate ability of software program to function for the intended applications-trend reports, change in status etc.
  - f. Demonstrate via graphed trends to show the sequence of operation is executed in correct manner, and that the HVAC systems operate properly through the complete sequence of operation, e.g., seasonal change, occupied/unoccupied mode, and warmup condition.
  - g. Demonstrate hardware interlocks and safeties functions, and that the control systems perform the correct sequence of operation after power loss and resumption of power loss.
  - h. Prepare and deliver to the VA graphed trends of all control loops to demonstrate that each control loop is stable and the set points are maintained.
  - i. Demonstrate that each control loop responds to set point adjustment and stabilizes within one (1) minute. Control loop trend data shall be instantaneous and the time between data points shall not be greater than one (1) minute.
- 5. Witnessed demonstration of ECC functions shall consist of:
  - a. Running each specified report.
  - b. Display and demonstrate each data entry to show site specific customizing capability. Demonstrate parameter changes.
  - c. Step through penetration tree, display all graphics, demonstrate dynamic update, and direct access to graphics.
  - d. Execute digital and analog commands in graphic mode.
  - e. Demonstrate DDC loop precision and stability via trend logs of inputs and outputs (6 loops minimum).
  - f. Demonstrate EMS performance via trend logs and command trace.
  - g. Demonstrate scan, update, and alarm responsiveness.
  - h. Demonstrate spreadsheet/curve plot software, and its integration with database.
  - i. Demonstrate on-line user guide, and help function and mail facility.

j. Demonstrate digital system configuration graphics with interactive upline and downline load, and demonstrate specified diagnostics.

- k. Demonstrate multitasking by showing dynamic curve plot, and graphic construction operating simultaneously via split screen.
- I. Demonstrate class programming with point options of beep duration, beep rate, alarm archiving, and color banding.

# **END OF SECTION 23 09 23**



# SECTION 23 21 13 HYDRONIC PIPING

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Water piping to connect HVAC equipment, including the following:
  - 1. Chilled water (CHS, CHR)
  - 2. Heating hot water (HWS, HWR)
  - 3. Condensate drain piping
  - 4. Domestic water (CW, HW)

# 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- C. Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION: General mechanical requirements and items, which are common to more than one section of Division 23.
- D. Section 23 07 11, HVAC, PLUMBING, and BOILER PLANT INSULATION: Piping insulation.
- E. Section 23 25 00, HVAC WATER TREATMENT: Water treatment for open and closed systems.
- F. Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC: Temperature and pressure sensors and valve operators.

#### 1.3 QUALITY ASSURANCE

- A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION, which includes welding qualifications.
- B. Submit prior to welding of steel piping a certificate of Welder's certification. The certificate shall be current and not more than one year old.
- C. For mechanical pressed sealed fittings, only tools of fitting manufacturer shall be used.
- D. Mechanical pressed fittings shall be installed by factory trained workers.
- E. All grooved joint couplings, fittings, valves, and specialties shall be the products of a single manufacturer. Grooving tools shall be the same manufacturer as the grooved components.
  - 1. All castings used for coupling housings, fittings, valve bodies, etc., shall be date stamped for quality assurance and traceability.

#### 1.4 SUBMITTALS

A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.

- B. Manufacturer's Literature and Data:
  - 1. Pipe and equipment supports.
  - 2. Pipe and tubing, with specification, class or type, and schedule.
  - 3. Pipe fittings, including miscellaneous adapters and special fittings.
  - 4. Flanges, gaskets and bolting.
  - 5. Grooved joint couplings and fittings.
  - 6. Valves of all types.
  - 7. Strainers.
  - 8. Flexible connectors for water service.
  - 9. Expansion joints.
  - 10. Expansion compensators.
  - 11. All specified hydronic system components.
  - 12. Gages.
  - 13. Thermometers and test wells.
- C. Manufacturer's certified data report, Form No. U-1, for ASME pressure
   vessels:
  - 1. Heat Exchangers.
  - 2. Air separators.
  - 3. Expansion tanks.
- D. Coordination Drawings: Refer to Article, SUBMITTALS of Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.

# 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only. American National Standards Institute, Inc.
- B. American Society of Mechanical Engineers/American National Standards Institute, Inc. (ASME/ANSI):

B1.20.1-83(R2006) ......Pipe Threads, General Purpose (Inch)

Solder joint Pressure fittings

B16.23-02 ...... Cast Copper Alloy Solder joint Drainage fittings B40.100-05 ...... Pressure Gauges and Gauge Attachments

C. American National Standards Institute, Inc./Fluid Controls Institute
 (ANSI/FCI):

70-2-2006 ...... Control Valve Seat Leakage

D. American Society of Mechanical Engineers (ASME):

B16.1-98 ...... Cast Iron Pipe Flanges and Flanged Fittings

B16.3-2006 ...... Malleable Iron Threaded Fittings: Class 150 and 300

	B16.5-2003	. Pipe Flanges and Flanged Fittings: NPS ½ through NPS 24
		Metric/Inch Standard
	B16.9-07	. Factory Made Wrought Butt Welding Fittings
		Forged Fittings, Socket Welding and Threaded
		. Cast Copper Alloy Solder Joint Pressure Fittings
		. Wrought Copper and Bronze Solder Joint Pressure Fittings.
		. Cast Copper Alloy Pipe Flanges and Flanged Fittings
		. Malleable Iron Threaded Pipe Unions
		. Ductile Iron Pipe Flanges and Flanged Fittings
	B31.1-08	
		F U
Ε.	American Society for Te	sting and Materials (ASTM):
	A47/A47M-99 (2004)	. Ferritic Malleable Iron Castings
	A53/A53M-07	. Standard Specification for Pipe, Steel, Black and Hot-Dipped,
		Zinc-Coated, Welded and Seamless
	A106/A106M-08	. Standard Specification for Seamless Carbon Steel Pipe for
		High-Temperature Service
	A126-04	. Standard Specification for Gray Iron Castings for Valves, Flanges,
		and Pipe Fittings
	A183-03	Standard Specification for Carbon Steel Track Bolts and Nuts
		Standard Specification for Steel Castings, Carbon, Suitable for
	·	Fusion Welding, for High Temperature Service
	A234/A234M-07	Piping Fittings of Wrought Carbon Steel and Alloy Steel for
	•	Moderate and High Temperature Service
	A307-07	Standard Specification for Carbon Steel Bolts and Studs, 60,000
		PSI Tensile Strength
	A536-84 (2004)	Standard Specification for Ductile Iron Castings
		Deformed and Plain Carbon Steel Bars for Concrete
		Reinforcement
	A653/A 653M-08	Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy Coated
	, 1000,	(Galvannealed) By the Hot-Dip Process
	B32-08	Standard Specification for Solder Metal
		Standard Specification for Composition Bronze or Ounce Metal
	502 02	Castings
	B88-03	Standard Specification for Seamless Copper Water Tube
		Aluminum and Aluminum Alloy Sheet and Plate
		Standard Test Method for Steady State Heat Flux Measurements
	C177 04	and Thermal Transmission Properties by Means of the Guarded
		Hot Plate Apparatus
	C478.00	Precast Reinforced Concrete Manhole Sections
		Calcium Silicate Block and Pipe Thermal Insulation
		Cellular Glass Thermal Insulation
		Polyethylene Plastics Pipe and Fittings Materials
		· · ·
	CJ31-U0	Unfaced Preformed Rigid Cellular Polyisocyanurate Thermal Insulation
	D1794_09	Rigid Poly (Vinyl Chloride) (PVC) Compounds and Chlorinated Poly
	D1/04-00	(Vinyl Chloride) (CPVC) Compound (Vinyl Chloridae) (CPVC)
	D1785 06	Poly (Vinyl Chloride0 (PVC) Plastic Pipe, Schedules 40, 80 and 120
	υ1/02-00	Poly (viny) Chilorideo (PVC) Plastic Pipe, Schedules 40, 80 and 120

	D2241-05
F.	American Water Works Association (AWWA): C110-08
G.	American Welding Society (AWS):
н.	B2.1-02Standard Welding Procedure Specification  Copper Development Association, Inc. (CDA):  CDA A4015-06Copper Tube Handbook
I.	Expansion Joint Manufacturer's Association, Inc. (EJMA):  EMJA-2003Expansion Joint Manufacturer's Association Standards, Ninth  Edition
J.	Manufacturers Standardization Society (MSS) of the Valve and Fitting Industry, Inc.:  SP-67-02a
К.	National Sanitation Foundation/American National Standards Institute, Inc. (NSF/ANSI):  14-06

# 1.6 SPARE PARTS

A. For mechanical pressed sealed fittings provide tools required for each pipe size used at the facility.

L. Tubular Exchanger Manufacturers Association: TEMA 9th Edition, 2007

#### PART 2 - PRODUCTS

# 2.1 PIPE AND EQUIPMENT SUPPORTS, PIPE SLEEVES, AND WALL AND CEILING PLATES

A. Provide in accordance with Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.

#### 2.2 PIPE AND TUBING

- A. Chilled Water and Heating Hot Water and Vent Piping:
  - 1. Steel: ASTM A53 Grade B, seamless or ERW, Schedule 40.
  - 2. Copper water tube option: ASTM B88, Type K or L, hard drawn.
- B. Domestic Water Piping: ASTM B88, Type K or L, hard drawn copper tubing.
- C. Cooling Coil Condensate Drain Piping:
  - 1. From air handling units: Copper water tube, ASTM B88, Type M.
- D. Pipe supports, including insulation shields, for above ground piping: Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.

# 2.3 FITTINGS FOR STEEL PIPE

- A. 50 mm (2 inches) and Smaller: Screwed or welded joints.
  - 1. Butt welding: ASME B16.9 with same wall thickness as connecting piping.
  - 2. Forged steel, socket welding or threaded: ASME B16.11.
  - 3. Screwed: 150 pound malleable iron, ASME B16.3. 125 pound cast iron, ASME B16.4, may be used in lieu of malleable iron. Bushing reduction of a single pipe size, or use of close nipples, is not acceptable.
  - 4. Unions: ASME B16.39.
  - 5. Water hose connection adapter: Brass, pipe thread to 20 mm (3/4 inch) garden hose thread, with hose cap nut.
- B. 65 mm (2-1/2 inches) and Larger: Welded or flanged joints. Contractor's option: Grooved mechanical couplings and fittings are optional.
  - 1. Butt welding fittings: ASME B16.9 with same wall thickness as connecting piping. Elbows shall be long radius type, unless otherwise noted.
  - 2. Welding flanges and bolting: ASME B16.5:
    - a. Water service: Weld neck or slip-on, plain face, with 6 mm (1/8 inch) thick full face neoprene gasket suitable for 104 degrees C (220 degrees F).
      - 1) Contractor's option: Convoluted, cold formed 150 pound steel flanges, with teflon gaskets, may be used for water service.
    - b. Flange bolting: Carbon steel machine bolts or studs and nuts, ASTM A307, Grade B.
- C. Welded Branch and Tap Connections: Forged steel weldolets, or branchlets and threadolets may be used for branch connections up to one pipe size smaller than the main. Forged steel half-couplings, ASME B16.11 may be used for drain, vent and gage connections.
- D. Grooved Mechanical Pipe Couplings and Fittings (Contractor's Option): Grooved Mechanical Pipe Couplings and Fittings may be used, with cut or roll grooved pipe, in water service up to 110 degrees C (230 degrees F)

- in lieu of welded, screwed or flanged connections. All joints must be rigid type.
- 1. Grooved mechanical couplings: Malleable iron, ASTM A47 or ductile iron, ASTM A536, fabricated in two or more parts, securely held together by two or more track-head, square, or oval-neck bolts, ASTM A449 and A183.
- 2. Gaskets: Rubber product recommended by the coupling manufacturer for the intended service.
- 3. Grooved end fittings: Malleable iron, ASTM A47; ductile iron, ASTM A536; or steel, ASTM A53 or A106, designed to accept grooved mechanical couplings. Tap-in type branch connections are acceptable.

#### 2.4 FITTINGS FOR COPPER TUBING

#### A. Joints:

- 1. Solder Joints: Joints shall be made up in accordance with recommended practices of the materials applied. Apply 95/5 tin and antimony on all copper piping.
- 2. Mechanically formed tee connection in water and drain piping: Form mechanically extracted collars in a continuous operation by drilling pilot hole and drawing out tube surface to form collar, having a height of not less than three times the thickness of tube wall. Adjustable collaring device shall insure proper tolerance and complete uniformity of the joint. Notch and dimple joining branch tube in a single process to provide free flow where the branch tube penetrates the fitting.
- B. Bronze Flanges and Flanged Fittings: ASME B16.24.
- C. Fittings: ANSI/ASME B16.18 cast copper or ANSI/ASME B16.22 solder wrought copper.

# 2.5 DIELECTRIC FITTINGS

- A. Provide where copper tubing and ferrous metal pipe are joined.
- B. 50 mm (2 inches) and Smaller: Threaded dielectric union, ASME B16.39.
- C. 65 mm (2 1/2 inches) and Larger: Flange union with dielectric gasket and bolt sleeves, ASME B16.42.
- D. Temperature Rating, 99 degrees C (210 degrees F).
- E. Contractor's option: On pipe sizes 2" and smaller, screwed end brass ball valves may be used in lieu of dielectric unions.

# 2.6 SCREWED JOINTS

- A. Pipe Thread: ANSI B1.20.
- B. Lubricant or Sealant: Oil and graphite or other compound approved for the intended service.

## 2.7 VALVES

A. Asbestos packing is not acceptable.

B. All valves of the same type shall be products of a single manufacturer.

C. Provide chain operators for valves 150 mm (6 inches) and larger when the centerline is located 2400 mm (8 feet) or more above the floor or operating platform.

#### D. Shut-Off Valves

- 1. Ball Valves (Pipe sizes 2" and smaller): MSS-SP 110, screwed or solder connections, brass or bronze body with chrome-plated ball with full port and Teflon seat at 2760 kPa (400 psig) working pressure rating. Provide stem extension to allow operation without interfering with pipe insulation.
- 2. Butterfly Valves (Pipe Sizes 2-1/2" and larger): Provide stem extension to allow 50 mm (2 inches) of pipe insulation without interfering with valve operation. MSS-SP 67, flange lug type or grooved end rated 1205 kPa (175 psig) working pressure at 93 degrees C (200 degrees F). Valves shall be ANSI Leakage Class VI and rated for bubble tight shut-off to full valve pressure rating. Valve shall be rated for dead end service and bi-directional flow capability to full rated pressure. Not permitted for direct buried pipe applications.
  - a. Body: Cast iron, ASTM A126, Class B. Malleable iron, ASTM A47 electro-plated, or ductile iron, ASTM A536, Grade 65-45-12 electro-plated.
  - b. Trim: Bronze, aluminum bronze, or 300 series stainless steel disc, bronze bearings, 316 stainless steel shaft and manufacturer's recommended resilient seat. Resilient seat shall be field replaceable, and fully line the body to completely isolate the body from the product. A phosphate coated steel shaft or stem is acceptable, if the stem is completely isolated from the product.
  - c. Actuators: Field interchangeable. Valves for balancing service shall have adjustable memory stop to limit open position.
    - 1) Valves 150 mm (6 inches) and smaller: Lever actuator with minimum of seven locking positions, except where chain wheel is required.
    - 2) Valves 200 mm (8 inches) and larger: Enclosed worm gear with handwheel, and where required, chain-wheel operator.
    - 3) 3. Gate Valves (Contractor's Option in lieu of Ball or Butterfly Valves):
      - a) 50 mm (2 inches) and smaller: MSS-SP 80, Bronze, 1034 kPa (150 psig), wedge disc, rising stem, union bonnet.
      - b) 65 mm (2 1/2 inches) and larger: Flanged, outside screw and yoke. MSS-SP 70, iron body, bronze mounted, 861 kPa (125 psig) wedge disc.
- G. Water Flow Balancing Valves: For flow regulation and shut-off. Valves shall be line size rather than reduced to control valve size.
  - 1. Globe style valve.
  - 2. A dual purpose flow balancing valve and adjustable flow meter, with bronze or cast iron body, calibrated position pointer, valved pressure taps or quick disconnects with integral check valves and preformed polyurethane insulating enclosure.
  - 3. Provide a readout kit including flow meter, readout probes, hoses, flow charts or calculator, and carrying case.

# 2.8 STRAINERS

A. Y Type.

1. Screens: Bronze, monel metal or 18-8 stainless steel, free area not less than 2-1/2 times pipe area, with perforations as follows: 1.1 mm (0.045 inch) diameter perforations for 100 mm (4 inches) and larger: 3.2 mm (0.125 inch) diameter perforations.

B. Suction Diffusers: Specified in Section 23 21 23, HYDRONIC PUMPS.

#### 2.9 GAGES, PRESSURE AND COMPOUND

- A. ASME B40.100, Accuracy Grade 1A, (pressure, vacuum, or compound for air, oil or water), initial mid-scale accuracy 1 percent of scale (Qualify grade), metal or phenolic case, 115 mm (4-1/2 inches) in diameter, 6 mm (1/4 inch) NPT bottom connection, white dial with black graduations and pointer, clear glass or acrylic plastic window, suitable for board mounting. Provide red "set hand" to indicate normal working pressure.
- B. Provide brass lever handle union cock. Provide brass/bronze pressure snubber for gages in water service.
- C. Range of Gages: Provide range equal to at least 130 percent of normal operating range.
  - 1. For condenser water suction (compound): Minus 100 kPa (30 inches Hg) to plus 700 kPa (100 psig).

#### 2.10 PRESSURE/TEMPERATURE TEST PROVISIONS

- A. Pete's Plug: 6 mm (1/4 inch) MPT by 75 mm (3 inches) long, brass body and cap, with retained safety cap, nordel self-closing valve cores, permanently installed in piping where shown, or in lieu of pressure gage test connections shown on the drawings.
- B. Provide one each of the following test items to the COR:
  - 1. 6 mm (1/4 inch) FPT by 3 mm (1/8 inch) diameter stainless steel pressure gage adapter probe for extra long test plug. PETE'S 500 XL is an example.
  - 2. 90 mm (3-1/2 inch) diameter, one percent accuracy, compound gage, —100 kPa (30 inches) Hg to 700 kPa (100 psig) range.
  - 3. 0 104 degrees C (220 degrees F) pocket thermometer one-half degree accuracy, 25 mm (one inch) dial, 125 mm (5 inch) long stainless steel stem, plastic case.

#### 2.11 THERMOMETERS

- A. Mercury or organic liquid filled type, red or blue column, clear plastic window, with 150 mm (6 inch) brass stem, straight, fixed or adjustable angle as required for each in reading.
- B. Case: Chrome plated brass or aluminum with enamel finish.
- C. Scale: Not less than 225 mm (9 inches), range as described below, two degree graduations.
- D. Separable Socket (Well): Brass, extension neck type to clear pipe insulation.
- E. Scale ranges:
  - 1. Chilled Water and Glycol-Water: 0-38 degrees C (32-100 degrees F).

2. Hot Water and Glycol-Water: -1 – 116 degrees C (30-240 degrees F).

#### PART 3 - EXECUTION

#### 3.1 GENERAL

- A. The drawings show the general arrangement of pipe and equipment but do not show all required fittings and offsets that may be necessary to connect pipes to equipment, fan-coils, coils, radiators, etc., and to coordinate with other trades. Provide all necessary fittings, offsets and pipe runs based on field measurements and at no additional cost to the government. Coordinate with other trades for space available and relative location of HVAC equipment and accessories to be connected on ceiling grid. Pipe location on the drawings shall be altered by contractor where necessary to avoid interferences and clearance difficulties.
- B. Store materials to avoid excessive exposure to weather or foreign materials. Keep inside of piping relatively clean during installation and protect open ends when work is not in progress.
- C. Support piping securely. Refer to PART 3, Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION. Install heat exchangers at height sufficient to provide gravity flow of condensate to the flash tank and condensate pump.
- D. Install piping generally parallel to walls and column center lines, unless shown otherwise on the drawings. Space piping, including insulation, to provide 25 mm (one inch) minimum clearance between adjacent piping or other surface. Unless shown otherwise, slope drain piping down in the direction of flow not less than 25 mm (one inch) in 12 m (40 feet). Provide eccentric reducers to keep bottom of sloped piping flat.
- E. Locate and orient valves to permit proper operation and access for maintenance of packing, seat and disc. Generally locate valve stems in overhead piping in horizontal position. Provide a union adjacent to one end of all threaded end valves. Control valves usually require reducers to connect to pipe sizes shown on the drawing. Install butterfly valves with the valve open as recommended by the manufacturer to prevent binding of the disc in the seat.
- F. Offset equipment connections to allow valving off for maintenance and repair with minimal removal of piping. Provide flexibility in equipment connections and branch line take-offs with 3-elbow swing joints where noted on the drawings.
- G. Tee water piping runouts or branches into the side of mains or other branches. Avoid bull-head tees, which are two return lines entering opposite ends of a tee and exiting out the common side.
- H. Provide manual air vent at all piping system high points and drain valves at all low points.
- I. Connect piping to equipment as shown on the drawings. Install components furnished by others such as:

1. Flow elements (orifice unions), control valve bodies, flow switches, pressure taps with valve, and wells for sensors.

- J. Thermometer Wells: In pipes 65 mm (2-1/2 inches) and smaller increase the pipe size to provide free area equal to the upstream pipe area.
- K. Where copper piping is connected to steel piping, provide dielectric connections

#### 3.2 PIPE JOINTS

- A. Welded: Beveling, spacing and other details shall conform to ASME B31.1 and AWS B2.1. See Welder's qualification requirements under "Quality Assurance" in Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Screwed: Threads shall conform to ASME B1.20; joint compound shall be applied to male threads only and joints made up so no more than three threads show. Coat exposed threads on steel pipe with joint compound, or red lead paint for corrosion protection.
- C. Mechanical Joint: Pipe grooving shall be in accordance with joint manufacturer's specifications. Lubricate gasket exterior including lips, pipe ends and housing interiors to prevent pinching the gasket during installation. Lubricant shall be as recommended by coupling manufacturer.
- D. 125 Pound Cast Iron Flange (Plain Face): Mating flange shall have raised face, if any, removed to avoid overstressing the cast iron flange.

#### 3.3 LEAK TESTING ABOVEGROUND PIPING

- A. Inspect all joints and connections for leaks and workmanship and make corrections as necessary, to the satisfaction of the COR. Tests may be either of those below, or a combination, as approved by the COR.
- B. An operating test at design pressure, and for hot systems, design maximum temperature.
- C. A hydrostatic test at 1.5 times design pressure. For water systems the design maximum pressure would usually be the static head, or expansion tank maximum pressure, plus pump head. Factory tested equipment (convertors, exchangers, coils, etc.) need not be field tested. Isolate equipment where necessary to avoid excessive pressure on mechanical seals and safety devices.

## 3.4 FLUSHING AND CLEANING PIPING SYSTEMS

- A. Water Piping: Clean systems as recommended by the suppliers of chemicals specified in Section 23 25 00, HVAC WATER TREATMENT.
  - Initial flushing: Remove loose dirt, mill scale, metal chips, weld beads, rust, and like
    deleterious substances without damage to any system component. Provide temporary
    piping or hose to bypass coils, control valves, exchangers and other factory cleaned
    equipment unless acceptable means of protection are provided and subsequent inspection

of hide-out areas takes place. Isolate or protect clean system components, including pumps and pressure vessels, and remove any component which may be damaged. Open all valves, drains, vents and strainers at all system levels. Remove plugs, caps, spool pieces, and components to facilitate early debris discharge from system. Sectionalize system to obtain debris carrying velocity of 1.8 m/S (6 feet per second), if possible. Connect dead-end supply and return headers as necessary. Flush bottoms of risers. Install temporary strainers where necessary to protect down-stream equipment. Supply and remove flushing water and drainage by various type hose, temporary and permanent piping and Contractor's booster pumps. Flush until clean as approved by the COR.

- 2. Cleaning: Using products supplied in Section 23 25 00, HVAC WATER TREATMENT, circulate systems at normal temperature to remove adherent organic soil, hydrocarbons, flux, pipe mill varnish, pipe joint compounds, iron oxide, and like deleterious substances not removed by flushing, without chemical or mechanical damage to any system component. Removal of tightly adherent mill scale is not required. Keep isolated equipment which is "clean" and where dead-end debris accumulation cannot occur. Sectionalize system if possible, to circulate at velocities not less than 1.8 m/S (6 feet per second). Circulate each section for not less than four hours. Blow-down all strainers, or remove and clean as frequently as necessary. Drain and prepare for final flushing.
- 3. Final Flushing: Return systems to conditions required by initial flushing after all cleaning solution has been displaced by clean make-up. Flush all dead ends and isolated clean equipment. Gently operate all valves to dislodge any debris in valve body by throttling velocity. Flush for not less than one hour.

#### 3.5 WATER TREATMENT

- A. Close and fill system as soon as possible after final flushing to minimize corrosion.
- B. Charge systems with chemicals specified in Section 23 25 00, HVAC WATER TREATMENT.
- C. Utilize this activity, by arrangement with the COR, for instructing VA operating personnel.

## 3.6 OPERATING AND PERFORMANCE TEST AND INSTRUCTION

- A. Refer to PART 3, Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Adjust red set hand on pressure gages to normal working pressure.

#### END OF SECTION 23 21 13



# SECTION 23 21 23 HYDRONIC PUMPS

#### PART 1 - GENERAL

# 1.1 DESCRIPTION

A. Hydronic pumps for Heating, Ventilating and Air Conditioning.

#### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- C. Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- D. Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT.
- E. Section 23 21 13, HYDRONIC PIPING.
- F. Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC and STEAM GENERATION EQUIPMENT.
- G. Section 26 29 11, LOW-VOLTAGE MOTOR STARTERS.

## 1.3 QUALITY ASSURANCE

- A. Refer to Paragraph, QUALITY ASSURANCE, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Design Criteria:
  - 1. Pumps design and manufacturer shall conform to Hydraulic Institute Standards.
  - 2. Pump sizes, capacities, pressures, operating characteristics and efficiency shall be as scheduled.
  - 3. Head-capacity curves shall slope up to maximum head at shut-off. Curves shall be relatively flat for closed systems. Select pumps near the midrange of the curve, so the design capacity falls to the left of the best efficiency point, to allow a cushion for the usual drift to the right in operation, without approaching the pump curve end point and possible cavitation and unstable operation. Select pumps for open systems so that required net positive suction head (NPSHR) does not exceed the net positive head available (NPSHA).
  - 4. Pump Driver: Furnish with pump. Size shall be non-overloading at any point on the head-capacity curve, including in a parallel or series pumping installation with one pump in operation.
  - 5. Provide all pumps with motors, impellers, drive assemblies, bearings, coupling guard and other accessories specified. Statically and dynamically balance all rotating parts.
  - 6. Furnish each pump and motor with a nameplate giving the manufacturers name, serial number of pump, capacity in GPM and head in feet at design condition, horsepower, voltage, frequency, speed and full load current and motor efficiency.
  - 7. Test all pumps before shipment. The manufacturer shall certify all pump ratings.
  - 8. After completion of balancing, provide replacement of impellers or trim impellers to provide specified flow at actual pumping head, as installed.
- C. Allowable Vibration Tolerance for Pump Units: Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING and EQUIPMENT.

## 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Pumps and accessories.
  - 2. Motors and drives.
  - 3. Variable speed motor controllers.

C. Manufacturer's installation, maintenance and operating instructions, in accordance with Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.

D. Characteristic Curves: Head-capacity, efficiency-capacity, brake horsepower-capacity, and NPSHR-capacity for each pump and for combined pumps in parallel or series service. Identify pump and show fluid pumped, specific gravity, pump speed and curves plotted from zero flow to maximum for the impeller being furnished and at least the maximum diameter impeller that can be used with the casing.

#### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only:
- B. American Iron and Steel Institute (AISI):
- C. American National Standards Institute (ANSI):
  - ANSI B15.1-00(R2008)..... Safety Standard for Mechanical Power Transmission Apparatus
  - ANSI B16.1-05......Cast Iron Pipe Flanges and Flanged Fittings, Class 25, 125, 250 and 800
- D. American Society for Testing and Materials (ASTM):

  A48-03 (2008)......Standard Specification for Gray Iron Castings
  B62-2009.....Standard Specification for Composition Bronze
  or Ounce Metal Castings
- E. Maintenance and Operating Manuals in accordance with Section 01 00 00, General Requirements.

# 1.6 DEFINITIONS

- A. Capacity: Liters per second (L/s) (Gallons per minute (GPM) of the fluid pumped.
- B. Head: Total dynamic head in kPa (feet) of the fluid pumped.
- C. Flat head-capacity curve: Where the shutoff head is less than 1.16 times the head at the best efficiency point.

#### 1.7 SPARE MATERIALS

A. Furnish one spare seal and casing gasket for each pump to the COR.

#### PART 2 - PRODUCTS

# 2.1 CENTRIFUGAL PUMPS, BRONZE FITTED

- A. General:
  - 1. Provide pumps that will operate continuously without overheating bearings or motors at every condition of operation on the pump curve, or produce noise audible outside the room or space in which installed.
  - 2. Provide pumps of size, type and capacity as indicated, complete with electric motor and drive assembly, unless otherwise indicated. Design pump casings for the indicated working pressure and factory test at 1½ times the designed pressure.
  - 3. Provide pumps of the same type, the product of a single manufacturer, with pump parts of the same size and type interchangeable.
  - 4. General Construction Requirements
    - a. Balance: Rotating parts, statically and dynamically.
    - b. Construction: To permit servicing without breaking piping or motor connections.
    - c. Pump Motors: Provide high efficiency motors, inverter duty for variable speed service. Refer to Section 23 05 12, GENERAL MOTOR REQUIREMNTS FOR HVAC and STEAM GENERATION EQUIPMENT. Motors

VA-528A7-12-706 HYDRONIC PUMPS 23 21 23 - 2

- shall be Open Drip Proof and operate at 1750 rpm unless noted otherwise.
- d. Heating pumps shall be suitable for handling water to 225°F.
- e. Provide coupling guards that meet ANSI B15.1, Section 8 and OSHA requirements.
- f. Pump Connections: Flanged.
- g. Pump shall be factory tested.
- h. Performance: As scheduled on the Contract Drawings.

#### B. In-Line Type:

- 1. Casing and Bearing Housing: Close-grained cast iron, ASTM A48.
- 2. Casing Wear Rings: Bronze.
- 3. Suction and Discharge: Plain face flange, 850 kPa (125 psig), ANSI B16 1
- 4. Casing Vent: Manual brass cock at high point.
- 5. Casing Drain and Gage Taps: 15 mm (1/2-inch) plugged connections minimum size.
- 6. Impeller: Bronze, ASTM B62, enclosed type, keyed to shaft.
- 7. Shaft: Steel, AISI Type 1045 or stainless steel.
- 8. Shaft Seal: Manufacturer's standard mechanical type to suit pressure and temperature and fluid pumped.
- 9. Shaft Sleeve: Bronze or stainless steel.
- 10. Motor: Furnish with pump. Refer to Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT.
- 11. Provide line sized shut-off valve and suction strainer, maintain manufacturer recommended straight pipe length on pump suction (with blow down valve).

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Follow manufacturer's written instructions for pump mounting and start-up. Access/Service space around pumps shall not be less than minimum space recommended by pumps manufacturer.
- B. Coordinate location of thermometer and pressure gauges as per Section 23 21 13, HYDRONIC PIPING.

## 3.2 START-UP

- A. Verify that the piping system has been flushed, cleaned and filled.
- B. Lubricate pumps before start-up.
- C. Prime the pump, vent all air from the casing and verify that the rotation is correct. To avoid damage to mechanical seals, never start or run the pump in dry condition.
- D. Verify that correct size heaters-motor over-load devices are installed for each pump controller unit.
- E. Field modifications to the bearings and or impeller (including trimming) are not permitted. If the pump does not meet the specified vibration tolerance send the pump back to the manufacturer for a replacement pump. All modifications to the pump shall be performed at the factory.
- F. Ensure the disposable strainer is free of debris prior to testing and balancing of the hydronic system.
- G. After several days of operation, replace the disposable start-up strainer with a regular strainer in the suction diffuser.

# END OF SECTION 23 21 23

VA-528A7-12-706 HYDRONIC PUMPS 23 21 23 - 3



# SECTION 23 22 13 STEAM AND CONDENSATE HEATING PIPING

# PART 1 - GENERAL

### 1.1 DESCRIPTION

A. Steam, condensate and vent piping inside buildings.

# 1.2 RELATED WORK

- A. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Piping insulation: Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION.
- C. Water treatment for open and closed systems: Section 23 25 00, HVAC WATER TREATMENT.
- D. Heating Coils and Humidifiers: Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS and SECTION 23 31 00, HVAC DUCTS AND CASING.
- E. Temperature and pressure sensors and valve operators: Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.

# 1.3 QUALITY ASSURANCE

A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION, which includes welding qualifications.

### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Pipe and equipment supports
  - 2. Pipe and tubing, with specification, class or type, and schedule.
  - 3. Pipe fittings, including miscellaneous adapters and special fittings.
  - 4. Flanges, gaskets and bolting.
  - 5. Valves of all types.
  - 6. Strainers.
  - 7. Flexible ball joints: Catalog sheets, performance charts, schematic drawings, specifications and installation instructions.
  - 8. All specified steam system components.
  - 9. Gages.
  - 10. Thermometers and test wells.
- C. Manufacturer's certified data report, Form No. U-1, for ASME pressure
   vessels:
  - 1. Heat Exchangers (Steam-to-Hot Water).

D. Coordination Drawings: Refer to Article, SUBMITTALS of Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

# 1.5 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

В.	American	Society	of	Mechanical	Engineers	/American	National	Standards
	Institute	e (ASME/A	ANS:	Ι):				
				-· -·		/.		

B1.20.1-83(R2006)	Pipe Threads, General Purpose (Inch)
B16.4-2006	Gray Iron Threaded Fittings

			_			
С.	American	Society	$\circ$ t	Mechanical	Engineers	(ASME):
٠.		2001	~ -			(/

IMMELICAL DOCTECT OF THE	idificat diigificato (fibrid)
B16.1-2005	Gray Iron Pipe Flanges and Flanged Fittings
B16.3-2006	Malleable Iron Threaded Fittings
B16.9-2007	Factory-Made Wrought Buttwelding Fittings
B16.11-2005	Forged Fittings, Socket-Welding and Threaded
B16.14-91	Ferrous Pipe Plugs, Bushings, and Locknuts with Pipe Threads
B16.22-2001	Wrought Copper and Copper Alloy Solder-Joint Pressure Fittings
B16.23-2002	Cast Copper Alloy Solder Joint Drainage Fittings
B16.24-2006	Cast Copper Alloy Pipe Flanges and Flanged Fittings, Class 150,
	300, 400, 600, 900, 1500 and 2500
B16.39-98	Malleable Iron Threaded Pipe Unions, Classes 150, 250, and 300
B31.1-2007	Power Piping
B31.9-2008	Building Services Piping
B40.100-2005	Pressure Gauges and Gauge Attachments
Boiler and Pressure Ves	sel Code: SEC VIII D1-2001, Pressure Vessels,
Division 1	

D. American Society for Testing and Materials (ASTM):

A47-99	Ferritic Malleable Iron Castings
A53-2007	Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and
	Seamless
A106-2008	Seamless Carbon Steel Pipe for High-Temperature Service
A126-2004	Standard Specification for Gray Iron Castings for Valves, Flanges,
	and Pipe Fittings
A181-2006	Carbon Steel Forgings, for General-Purpose Piping
A183-2003	Carbon Steel Track Bolts and Nuts
A216-2008	Standard Specification for Steel Castings, Carbon, Suitable for
	Fusion Welding, for High Temperature Service
A285-01	Pressure Vessel Plates, Carbon Steel, Low-and-Intermediate-
	Tensile Strength
A307-2007	Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength
A516-2006	Pressure Vessel Plates, Carbon Steel, for Moderate-and- Lower
	Temperature Service
A536-84(2004)e1	Standard Specification for Ductile Iron Castings
B32-2008	Solder Metal
B61-2008	Steam or Valve Bronze Castings

	B88-2003	Composition Bronze or Ounce Metal CastingsSeamless Copper Water TubeSocket-Type Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe Fittings, Schedule 80
	F441-02(2008)	Chlorinated Poly (Vinyl Chloride) (CPVC) Plastic Pipe, Schedules 40 and 80
Ε.	American Welding Societ	y (AWS):
	A5.8-2004	. Filler Metals for Brazing and Braze Welding
	B2.1-00	Welding Procedure and Performance Qualifications
F.	<pre>Industry, Inc.:</pre>	zation Society (MSS) of the Valve and Fitting
	SP-67-95	·
		. Cast Iron Gate Valves, Flanged and Threaded Ends
		. Gray Iron Swing Check Valves, Flanged and Threaded Ends
	SP-72-99	Ball Valves with Flanged or Butt-Welding Ends for General Service
	SP-78-98	. Cast Iron Plug Valves, Flanged and Threaded Ends
	SP-80-97	Bronze Gate, Globe, Angle and Check Valves
	SP-85-94	. Cast Iron Globe and Angle Valves, Flanged and Threaded Ends
G.	Military Specifications MIL-S-901D-1989	(Mil. Spec.): Shock Tests, H.I. (High Impact) Shipboard Machinery, Equipment, and Systems

- H. National Board of Boiler and Pressure Vessel Inspectors (NB): Relieving Capacities of Safety Valves and Relief Valves
- I. Tubular Exchanger Manufacturers Association: TEMA 18th Edition, 2000

# PART 2 - PRODUCTS

# 2.1 PIPE AND EQUIPMENT SUPPORTS, PIPE SLEEVES, AND WALL AND CEILING PLATES

A. Provide in accordance with Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

# 2.2 PIPE AND TUBING

- A. Steam Piping: Steel, ASTM A53, Grade B, seamless or ERW; A106 Grade B, Seamless; Schedule 40.
- B. Steam Condensate and Pumped Condensate Piping:
  - 1. Concealed above ceiling, in wall or chase: Copper water tube ASTM B88, Type K, hard drawn
  - 2. All other locations: Copper water tube ASTM B88, Type K, hard drawn; or steel, ASTM A53, Grade B, Seamless or ERW, or A106 Grade B Seamless, Schedule 80.
- C. Vent Piping: Steel, ASTM A53, Grade B, seamless or ERW; A106 Grade B, Seamless; Schedule 40, galvanized.

### 2.3 FITTINGS FOR STEEL PIPE

- A. 50 mm (2 inches) and Smaller: Screwed or welded.
  - 1. Butt welding: ASME B16.9 with same wall thickness as connecting piping.
  - 2. Forged steel, socket welding or threaded: ASME B16.11.
  - 3. Screwed: 150 pound malleable iron, ASME B16.3. 125 pound cast iron, ASME B16.4, may be used in lieu of malleable iron, except for steam and steam condensate piping. Provide 300 pound malleable iron, ASME B16.3 for steam and steam condensate piping. Cast iron fittings or piping is not acceptable for steam and steam condensate piping. Bushing reduction of a single pipe size, or use of close nipples, is not acceptable.
  - 4. Unions: ASME B16.39.
  - 5. Steam line drip station and strainer quick-couple blowdown hose connection: Straight through, plug and socket, screw or cam locking type for 15 mm (1/2 inch) ID hose. No integral shut-off is required.
- B. 65 mm (2-1/2 inches) and Larger: Welded or flanged joints.
  - 1. Butt welding fittings: ASME B16.9 with same wall thickness as connecting piping. Elbows shall be long radius type, unless otherwise noted.
  - 2. Welding flanges and bolting: ASME B16.5:
    - a. Steam service: Weld neck or slip-on, raised face, with non-asbestos gasket. Non-asbestos gasket shall either be stainless steel spiral wound strip with flexible graphite filler or compressed inorganic fiber with nitrile binder rated for saturated and superheated steam service 750 degrees F and 1500 psi.
    - b. Flange bolting: Carbon steel machine bolts or studs and nuts, ASTM A307, Grade B.
- C. Welded Branch and Tap Connections: Forged steel weldolets, or branchlets and threadolets may be used for branch connections up to one pipe size smaller than the main. Forged steel half-couplings, ASME B16.11 may be used for drain, vent and gage connections.

# 2.4 FITTINGS FOR COPPER TUBING

- A. Solder Joint:
  - 1. Joints shall be made up in accordance with recommended practices of the materials applied. Apply 95/5 tin and antimony on all copper piping.
- B. Bronze Flanges and Flanged Fittings: ASME B16.24.
- C. Fittings: ANSI/ASME B16.18 cast copper or ANSI/ASME B16.22 solder wrought copper.

# 2.5 DIELECTRIC FITTINGS

- A. Provide where copper tubing and ferrous metal pipe are joined.
- B. 50 mm (2 inches) and Smaller: Threaded dielectric union, ASME B16.39.
- C. 65 mm (2 1/2 inches) and Larger: Flange union with dielectric gasket and bolt sleeves, ASME B16.42.
- D. Temperature Rating, 121 degrees C (250 degrees F) for steam condensate and as required for steam service.

E. Contractor's option: On pipe sizes 2" and smaller, screwed end brass gate valves may be used in lieu of dielectric unions.

#### 2.6 SCREWED JOINTS

- A. Pipe Thread: ANSI B1.20.
- B. Lubricant or Sealant: Oil and graphite or other compound approved for the intended service.

#### 2.7 VALVES

- A. Asbestos packing is not acceptable.
- B. All valves of the same type shall be products of a single manufacturer.
- C. Provide chain operators for valves 150 mm (6 inches) and larger when the centerline is located 2100 mm (7 feet) or more above the floor or operating platform.
- D. Shut-Off Valves
  - 1. Gate Valves:
    - a. 50 mm (2 inches) and smaller: MSS-SP80, Bronze, 1034 kPa (150 lb.), wedge disc, rising stem, union bonnet.
    - b. 65 mm (2 1/2 inches) and larger: Flanged, outside screw and yoke.
      - 1) High pressure steam 413 kPa (60 psig) and above nominal MPS system): Cast steel body, ASTM A216 grade WCB, 1034 kPa (150 psig) at 260 degrees C (500 degrees F), 11-1/2 to 13 percent chrome stainless steel solid disc and seats. Provide 25 mm (1 inch) factory installed bypass with globe valve on valves 100 mm (4 inches) and larger.
      - 2) All other services: MSS-SP 70, iron body, bronze mounted, 861 kPa (125 psig) wedge disc.
- E. Globe and Angle Valves:
  - 1. Globe Valves:
    - a. 50 mm (2 inches) and smaller: MSS-SP 80, bronze, 1034 kPa (150 lb.) Globe valves shall be union bonnet with metal plug type disc.
    - b. 65 mm (2 1/2 inches) and larger:
      - 1) Globe valves for high pressure steam 413 kPa (60 psig) and above nominal MPS system): Cast steel body, ASTM A216 grade WCB, flanged, OS&Y, 1034 kPa (150 psig) at 260 degrees C (500 degrees F), 11-1/2 to 13 percent chrome stainless steel disc and renewable seat rings.
      - 2) All other services: 861 kPa (125 psig), flanged, iron body, bronze trim, MSS-SP-85 for globe valves.
  - Angle Valves
    - a. 50 mm (2 inches) and smaller: MSS-SP 80, bronze, 1034 kPa (150 lb.) Angle valves shall be union bonnet with metal plug type disc.
    - b. 65 mm (2 1/2 inches) and larger:
      - 1) Angle valves for high pressure steam 413 kPa (60 psig) and above nominal MPS system): Cast steel body, ASTM A216 grade WCB, flanged, OS&Y, 1034 kPa (150 psig) at 260 degrees C (500

- degrees F), 11-1/2 to 13 percent chrome stainless steel disc and renewable seat rings.
- 2) All other services: 861 kPa (125 psig), flanged, iron body, bronze trim, MSS-SP-85 for angle valves.

# F. Swing Check Valves

- 1. 50 mm (2 inches) and smaller: MSS-SP 80, bronze, 1034 kPa (150 psig), 45 degree swing disc.
- 2. 65 mm (2-1/2 inches) and Larger:
  - a Check valves for high pressure steam 413 kPa (60 psig) and above nominal MPS system: Cast steel body, ASTM A216 grade WCB, flanged, OS&Y, 1034 kPa (150 psig) at 260 degrees C (500 degrees F), 11-1/2 to 13 percent chrome stainless steel disc and renewable seat rings.
  - b. All other services: 861 kPa (125 psig), flanged, iron body, bronze trim, MSS-SP-71 for check valves.

#### 2.8 STRAINERS

- A. Basket or Y Type. Tee type is acceptable for gravity flow and pumped steam condensate service.
- B. High Pressure Steam: Rated 1034 kPa (150 psig) saturated steam.
  - 1. 50 mm (2 inches) and smaller: Iron, ASTM A116 Grade B, or bronze, ASTM B-62 body with screwed connections (250 psig).
  - 2. 65 mm (2-1/2 inches) and larger: Flanged cast steel or 1723 kPa (250 psig) cast iron.
- C. All Other Services: Rated 861 kPa (125 psig) saturated steam.
  - 1. 50 mm (2 inches) and smaller: Cast iron or bronze.
  - 2. 65 mm (2-1/2 inches) and larger: Flanged, iron body.
- D. Screens: Bronze, monel metal or 18-8 stainless steel, free area not less than 2-1/2 times pipe area, with perforations as follows:
  - 1. 75 mm (3 inches) and smaller: 20 mesh for steam and 1.1 mm (0.045 inch) diameter perforations for liquids.
  - 2. 100 mm (4 inches) and larger: 1.1 mm (0.045) inch diameter perforations for steam and 3.2 mm (0.125 inch) diameter perforations for liquids.

# 2.9 STEAM SYSTEM COMPONENTS

- A. Heat Exchanger (Steam to Hot Water): Shell and tube type, U-bend removable tube bundle, steam in shell, water in tubes, equipped with support cradles.
  - 1. Maximum tube velocity: 2.3 m/s (7.5 feet per second).
  - 2. Tube fouling factor: TEMA Standards, but not less than 0.00018 m<sup>2</sup>K/W (0.001 ft<sup>2</sup>hrF/Btu).
  - 3. Materials:
    - a. Shell: Steel.
    - b. Tube sheet and tube supports: Steel or brass.
    - c. Tubes: 20 mm (3/4 inch) OD copper.
    - d. Head or bonnet: Cast iron or steel.
  - 4. Construction: In accordance with ASME Pressure Vessel Code for 861 kPa (125 psig) working pressure for shell and tubes. Provide manufacturer's certified data report, Form No. U-1.

B. Optional Heat Transfer Package: In lieu of field erected individual components, the Contractor may provide a factory or shop assembled package of heat exchangers, pumps, and other components supported on a welded steel frame.

- C. Safety Valves and Accessories: Comply with ASME Boiler and Pressure Vessel Code, Section VIII. Capacities shall be certified by National Board of Boiler and Pressure Vessel Inspectors, maximum accumulation 10 percent. Provide lifting lever. Provide drip pan elbow where shown.
- D. Steam PRV for Individual Equipment: Cast iron or bronze body, screwed or flanged ends, rated 861 kPa (125 psig) working pressure. Singleseated, diaphragm operated, spring loaded, adjustable range, all parts renewable.
- E. Flash Tanks: Horizontal or vertical vortex type, constructed of copper bearing steel, ASTM A516 or ASTM A285, for a steam working pressure of 861 kPa (125 psig) to comply with ASME Code for Unfired Pressure Vessels and stamped with "U" symbol. Perforated pipe inside tank shall be ASTM A53 Grade B, Seamless or ERW, or A106 Grade B Seamless, Schedule 80. Corrosion allowance of 1.6 mm (1/16 inch) may be provided in lieu of the copper bearing requirement. Provide data Form No. U-1.
- G. Steam Trap: Each type of trap shall be the product of a single manufacturer. Provide trap sets at all low points and at 61 m (200 feet) intervals on the horizontal main lines.
  - 1. Floats and linkages shall provide sufficient force to open trap valve over full operating pressure range available to the system. Unless otherwise indicated on the drawings, traps shall be sized for capacities indicated at minimum pressure drop as follows:
    - a. For equipment with modulating control valve: 1.7 kPa (1/4 psig), based on a condensate leg of 300 mm (12 inches) at the trap inlet and gravity flow to the receiver.
    - b. For main line drip trap sets and other trap sets at steam pressure: Up to 70 percent of design differential pressure. Condensate may be lifted to the return line.
  - 2. Trap bodies: Bronze, cast iron, or semi-steel, constructed to permit ease of removal and servicing working parts without disturbing connecting piping. For systems without relief valve traps shall be 5. Mechanism: Brass, stainless steel or corrosion resistant alloy. rated for the pressure upstream of the PRV supplying the system.
  - 3. Balanced pressure thermostatic elements: Phosphor bronze, stainless steel or monel metal.
  - 4. Valves and seats: Suitable hardened corrosion resistant alloy.
  - 6. Floats: Stainless steel.
  - 7. Inverted bucket traps: Provide bi-metallic thermostatic element for rapid release of non-condensables.
- H. Thermostatic Air Vent (Steam): Brass or iron body, balanced pressure bellows, stainless steel (renewable) valve and seat, rated 861 kPa (125 psig) working pressure, 20 mm (3/4 inch) screwed connections. Air vents shall be balanced pressure type that responds to steam pressure-temperature curve and vents air at any pressure.
- J. Unfired clean steam generator
  - 1. Provide a packaged factory assembled, pre-piped unfired steam generator consisting of stainless steel shell, stainless steel tube coil, stainless steel steam piping, valves and controls

- All stainless steel piping shall be type 316 factory-fabricated and provided as a part of the complete package.
- 2. Shell: Stainless steel ASME code construction with flanged piping connections. 345 kPa (50 psig) maximum WSP.
- 3. Tubes: Stainless steel suitable for 862 kPa (125 psig) working pressure.
- 4. Design: Heated fluid in shell and heating fluid (higher pressure steam) in tubes.
- 5. Each steam generator shall be furnished with the following accessories:
  - a. Resilient insulation.
  - b. Pilot operated modulating control valve with pressure controller.
  - c. Control pilot to maintain constant steam output.
  - d. Pressure relief valve.
  - e. Vessel and tube side pressure gages.
  - f. Liquid level controller with brass feed water solenoid valve, in check valve and strainer.
  - g. Over-pressure limit system with auto-reset.
  - h. Factory packaging.
  - i. Dual F&T condensate traps.
  - j. Manual blow down valve.
  - k. TDS based automatic blow down
  - I. Low water cut-off and high pressure cut-off.
  - m. Fully wired control box.
  - n. Automatic drain solenoid valve.
  - o. Drain cooler
- 6. Provide solid state control module with LED backlit LCD display and LED pilot lights to indicate on-off, high pressure, low pressure, low water and water feed. Control module shall allow the local adjustment of pressure limits on display screen. Control module shall have alarm light and alarm horn with built in alarm silence relay. Control module shall be supplied with dry contact closure outputs to indicate to building automation controls (BAC) the occurrence of power on, high pressure, low pressure, low water and water feed. The control module shall allow the BAC to turn the unfired steam generator on or off through a remote relay suitable for 24 VAC, 1 amp. The control module shall allow the BAC to remotely monitor the operating pressure. Control module shall be supplied with an on-off switch and shall be mounted in a NEMA 1 panel. All solenoids and limits shall be 24 VAC.

# 2.13 GAGES, PRESSURE AND COMPOUND

- A. ASME B40.1, Accuracy Grade 1A, (pressure, vacuum, or compound), initial mid-scale accuracy 1 percent of scale (Qualify grade), metal or phenolic case, 115 mm (4-1/2 inches) in diameter, 6 mm (1/4 inch) NPT bottom connection, white dial with black graduations and pointer, clear glass or acrylic plastic window, suitable for board mounting. Provide red "set hand" to indicate normal working pressure.
- B. Provide brass, lever handle union cock. Provide brass/bronze pressure snubber for gages in water service. Provide brass pigtail syphon for steam gages.
- C. Range of Gages: For services not listed provide range equal to at least 130 percent of normal operating range:

Low pressure steam and steam	0 to 207 kPa (30 psig).
condensate to 103 kPa(15 psig)	
Medium pressure steam and steam	0 to 689 kPa (100 psig).

condensate nominal 413 kPa (60 psig)	
High pressure steam and steam	0 to 1378 kPa (200 psig).
condensate nominal 620 kPa to 861 kPa	
(90 to 125 psig)	
Pumped condensate, steam condensate,	0 to 415 kPa (60 psig)
gravity or vacuum	
(30" HG to 30 psig)	

### 2.14 PRESSURE/TEMPERATURE TEST PROVISIONS

- A. Provide one each of the following test items to the COR:
  - 1. 6 mm (1/4 inch) FPT by 3 mm (1/8 inch) diameter stainless steel pressure gage adapter probe for extra long test plug. PETE'S 500 XL is an example.
  - 2. 90 mm (3-1/2 inch) diameter, one percent accuracy, compound gage, 762 mm (30 inches) Hg to 689 kPa (100 psig) range.
  - 3. 0 104 degrees C (32-220 degrees F) pocket thermometer one-half degree accuracy, 25 mm (one inch) dial, 125 mm (5 inch) long stainless steel stem, plastic case.

#### PART 3 - EXECUTION

### 3.1 GENERAL

- A. The drawings show the general arrangement of pipe and equipment but do not show all required fittings and offsets that may be necessary to connect pipes to equipment, fan-coils, coils, radiators, etc., and to coordinate with other trades. Provide all necessary fittings, offsets and pipe runs based on field measurements and at no additional cost to the government. Coordinate with other trades for space available and relative location of HVAC equipment and accessories to be connected on ceiling grid. Pipe location on the drawings shall be altered by contractor where necessary to avoid interferences and clearance difficulties.
- B. Store materials to avoid excessive exposure to weather or foreign materials. Keep inside of piping relatively clean during installation and protect open ends when work is not in progress.
- C. Support piping securely. Refer to PART 3, Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION. Install convertors and other heat exchangers at height sufficient to provide gravity flow of condensate to the flash tank and condensate pump.
- D. Install piping generally parallel to walls and column center lines, unless shown otherwise on the drawings. Space piping, including insulation, to provide 25 mm (one inch) minimum clearance between adjacent piping or other surface. Unless shown otherwise, slope steam, condensate and drain piping down in the direction of flow not less than 25 mm (one inch) in 12 m (40 feet). Provide eccentric reducers to keep bottom of sloped piping flat.
- E. Locate and orient valves to permit proper operation and access for maintenance of packing, seat and disc. Generally locate valve stems in overhead piping in horizontal position. Provide a union adjacent to one end of all threaded end valves. Control valves usually require reducers

to connect to pipe sizes shown on the drawing. Install butterfly valves with the valve open as recommended by the manufacturer to prevent binding of the disc in the seat.

- F. Offset equipment connections to allow valving off for maintenance and repair with minimal removal of piping. Provide flexibility in equipment connections and branch line take-offs with 3-elbow swing joints where noted on the drawings.
- G. Tee water piping runouts or branches into the side of mains or other branches. Avoid bull-head tees, which are two return lines entering opposite ends of a tee and exiting out the common side.
- H. Connect piping to equipment as shown on the drawings. Install components furnished by others such as:
  - 1. Flow elements (orifice unions), control valve bodies, flow switches, pressure taps with valve, and wells for sensors.
- Where copper piping is connected to steel piping, provide dielectric connections.

#### 3.2 PIPE JOINTS

- A. Welded: Beveling, spacing and other details shall conform to ASME B31.1 and AWS B2.1. See Welder's qualification requirements under "Quality Assurance" in Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Screwed: Threads shall conform to ASME B1.20; joint compound shall be applied to male threads only and joints made up so no more than three threads show. Coat exposed threads on steel pipe with joint compound, or red lead paint for corrosion protection.
- C. 125 Pound Cast Iron Flange (Plain Face): Mating flange shall have raised face, if any, removed to avoid overstressing the cast iron flange.

# 3.3 STEAM TRAP PIPING

A. Install to permit gravity flow to the trap. Provide gravity flow (avoid lifting condensate) from the trap where modulating control valves are used. Support traps weighing over 11 kg (25 pounds) independently of connecting piping.

### 3.4 LEAK TESTING

- A. Inspect all joints and connections for leaks and workmanship and make corrections as necessary, to the satisfaction of the COR in accordance with the specified requirements. Testing shall be performed in accordance with the specification requirements.
- B. An operating test at design pressure, and for hot systems, design maximum temperature.
- C. A hydrostatic test at 1.5 times design pressure. For water systems the design maximum pressure would usually be the static head, or expansion

tank maximum pressure, plus pump head. Factory tested equipment (convertors, exchangers, coils, etc.) need not be field tested. Avoid excessive pressure on mechanical seals and safety devices.

# 3.7 FLUSHING AND CLEANING PIPING SYSTEMS

A. Steam, Condensate and Vent Piping: No flushing or chemical cleaning required. Accomplish cleaning by pulling all strainer screens and cleaning all scale/dirt legs during start-up operation.

# 3.8 OPERATING AND PERFORMANCE TEST AND INSTRUCTION

- A. Refer to PART 3, Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Adjust red set hand on pressure gages to normal working pressure.

END OF SECTION 23 22 13



# SECTION 23 25 00 HVAC WATER TREATMENT

### PART 1 - GENERAL

### 1.1 DESCRIPTION

- A. This section specifies cleaning and treatment of circulating HVAC water systems, including the following.
  - 1. Cleaning compounds.
  - 2. Chemical treatment for closed loop heat transfer systems.
  - 3. Glycol-water heat transfer systems.

### 1.2 RELATED WORK

- A. Test requirements and instructions on use of equipment/system: Section 01 00 00, GENERAL REQUIREMENTS.
- B. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- C. Piping and valves: Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM and CONDENSATE HEATING PIPING.

# 1.3 QUALITY ASSURANCE

- A. Refer to paragraph, QUALITY ASSURANCE in Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Chemicals: Chemicals shall be non-toxic approved by local authorities and meeting applicable EPA requirements.

# 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data including:
  - 1. Cleaning compounds and recommended procedures for their use.
  - 2. Chemical treatment for closed systems, including installation and operating instructions.
  - 3. Glycol-water system materials, equipment, and installation.
- C. Water analysis verification.
- D. Materials Safety Data Sheet for all proposed chemical compounds, based on U.S. Department of Labor Form No. L5B-005-4.
- E. Maintenance and operating instructions in accordance with Section 01 00 00, GENERAL REQUIREMENTS.

#### 1.5 APPLICABLE PUBLICATIONS

A. The publication listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

- C. American Society for Testing and Materials (ASTM):
  F441/F441M-02 (2008).....Standard Specification for Chlorinated Poly (Vinyl Chloride)
  (CPVC) Plastic Pipe, Schedules 40 and 80

#### PART 2 - PRODUCTS

### 2.1 CLEANING COMPOUNDS

- A. Alkaline phosphate or non-phosphate detergent/surfactant/specific to remove organic soil, hydrocarbons, flux, pipe mill varnish, pipe compounds, iron oxide, and like deleterious substances, with or without inhibitor, suitable for system wetted metals without deleterious effects.
- B. All chemicals to be acceptable for discharge to sanitary sewer.
- C. Refer to Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM and CONDENSATE HEATING PIPING, PART 3, for flushing and cleaning procedures.

# 2.2 CHEMICAL TREATMENT FOR CLOSED LOOP SYSTEMS

- A. Inhibitor: Provide sodium nitrite/borate, molybdate-based inhibitor or other approved compound suitable for make-up quality and make-up rate and which will cause or enhance bacteria/corrosion problems or mechanical seal failure due to excessive total dissolved solids. Shot feed manually. Maintain inhibitor residual as determined by water treatment laboratory, taking into consideration residual and temperature effect on pump mechanical seals.
- B. pH Control: Inhibitor formulation shall include adequate buffer to maintain pH range of 8.0 to 10.5.
- C. Performance: Protect various wetted, coupled, materials of construction including ferrous, and red and yellow metals. Maintain system essentially free of scale, corrosion, and fouling. Corrosion rate of following metals shall not exceed specified mills per year penetration; ferrous, 0-2; brass, 0-1; copper, 0-1. Inhibitor shall be stable at equipment skin surface temperatures and bulk water temperatures of not less than 121 degrees C (250 degrees F) and 52 degrees C (125 degrees Fahrenheit) respectively. Heat exchanger fouling and capacity reduction shall not exceed that allowed by fouling factor 0.0005.

# 2.3 GLYCOL-WATER SYSTEM

A. Propylene glycol shall be inhibited with 1.75 percent dipotassium phosphate. Do not use automotive anti-freeze because the inhibitors used are not needed and can cause sludge precipitate that interferes with heat transfer.

- B. Provide required amount of glycol to obtain the percent by volume for glycol-water systems as follows and to provide one-half tank reserve supply: 25 percent for run-around coil systems and hydronic system.
- C. Pot Feeder Make-up Unit: By pass type for chemical treatment, schedule 3.5 mm (10 gauge) heads, 20 mm (3/4-inch) system connections and large neck opening for chemical addition. Feeders shall be 19 Liters (5 gallon) minimum size.

### 2.4 EQUIPMENT AND MATERIALS IDENTIFICATION

Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Delivery and Storage: Deliver all chemicals in manufacturer's sealed shipping containers. Store in designated space and protect from deleterious exposure and hazardous spills.
- B. Install equipment furnished by the chemical treatment supplier and charge systems according to the manufacturer's instructions and as directed by the Technical Representative.
- C. Before adding cleaning chemical to the closed system, all air handling coils and fan coil units should be isolated by closing the inlet and outlet valves and opening the bypass valves. This is done to prevent dirt and solids from lodging the coils.
- D. Do not valve in or operate system pumps until after system has been cleaned.
- E. After chemical cleaning is satisfactorily completed, open the inlet and outlet valves to each coil and close the by-pass valves. Also, clean all strainers.
- F. Perform tests and report results in accordance with Section 01 00 00, GENERAL REQUIREMENTS.
- G. After cleaning is complete, and water PH is acceptable to manufacturer of water treatment chemical, add manufacturer-recommended amount of chemicals to systems.
- ${\tt H.}$  Instruct VA personnel in system maintenance and operation in accordance with Section 01 00 00, GENERAL REQUIREMENTS.

# **END OF SECTION 23 25 00**



# SECTION 23 31 00 HVAC DUCTS AND CASINGS

### PART 1 - GENERAL

# 1.1 DESCRIPTION

- A. Ductwork and accessories for HVAC including the following:
  - 1. Supply air, return air, outside air, exhaust, make-up air, and relief

# B. Definitions:

- 1. SMACNA Standards as used in this specification means the HVAC Duct Construction Standards, Metal and Flexible.
- 2. Seal or Sealing: Use of liquid or mastic sealant, with or without compatible tape overlay, or gasketing of flanged joints, to keep air leakage at duct joints, seams and connections to an acceptable minimum.
- 3. Duct Pressure Classification: SMACNA HVAC Duct Construction Standards, Metal and Flexible.
- 4. Exposed Duct: Exposed to view in a finished room.

# 1.2 RELATED WORK

- A. General Mechanical Requirements: Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Duct Insulation: Section 23 07 11, HVAC, PLUMBING, and BOILER PLANT INSULATION
- C. Supply Air Fans: Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING
- D. Testing and Balancing of Air Flows: Section 23 05 93, TESTING, ADJUSTING, and BALANCING FOR HVAC.

# 1.3 QUALITY ASSURANCE

- A. Refer to article, QUALITY ASSURANCE, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- B. Fire Safety Code: Comply with NFPA 90A.
- C. Duct System Construction and Installation: Referenced SMACNA Standards are the minimum acceptable quality.
- D. Duct Sealing, Air Leakage Criteria, and Air Leakage Tests: Ducts shall be sealed as per duct sealing requirements of SMACNA HVAC Air Duct Leakage Test Manual for duct pressure classes shown on the drawings.
- E. Duct accessories exposed to the air stream, such as dampers of all types (except smoke dampers) and access openings, shall be of the same material as the duct or provide at least the same level of corrosion resistance.

### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. Rectangular ducts:
    - a. Schedules of duct systems, materials and selected SMACNA construction alternatives for joints, sealing, gage and reinforcement.
    - b. Sealants and gaskets.
    - c. Access doors.
  - 2. Round and flat oval duct construction details:
    - a. Manufacturer's details for duct fittings.
    - b. Sealants and gaskets.
    - c. Access sections.
    - d. Installation instructions.
  - 3. Volume dampers.
  - 4. Upper hanger attachments.
  - 5. Sound attenuators, including pressure drop and acoustic performance.
  - 6. Flexible connections.
  - 7. Instrument test fittings.
  - 8. Details and design analysis of alternate or optional duct systems.
  - 9 COMMON WORK RESULTS FOR HVAC and STEAM GENERATION.
- C. Coordination Drawings: Refer to article, SUBMITTALS, in Section 23 05

# 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- C. American Society for Testing and Materials (ASTM):

American Society for re	sting and materials (ASIM).
A167-99(2009)	Standard Specification for Stainless and Heat-Resisting
	Chromium-Nickel Steel Plate, Sheet, and Strip
A653-09	Standard Specification for Steel Sheet, Zinc-Coated (Galvanized)
	or Zinc-Iron Alloy coated (Galvannealed) by the Hot-Dip process
A1011-09a	Standard Specification for Steel, Sheet and Strip, Hot rolled,
	Carbon, structural, High-Strength Low-Alloy, High Strength Low-
	Alloy with Improved Formability, and Ultra-High Strength
B209-07	Standard Specification for Aluminum and Aluminum-Alloy Sheet
	and Plate
C1071-05e1	Standard Specification for Fibrous Glass Duct Lining Insulation
	(Thermal and Sound Absorbing Material)
E84-09a	Standard Test Method for Surface Burning Characteristics of
	Building Materials

D.	National Fire Protection Association (NFPA):  90A-09
Ε.	Sheet Metal and Air Conditioning Contractors National Association (SMACNA):  2nd Edition – 2005
F.	Underwriters Laboratories, Inc. (UL):  181-08

#### PART 2 - PRODUCTS

### 2.1 DUCT MATERIALS AND SEALANTS

- A. General: Except for systems specified otherwise, construct ducts, casings, and accessories of galvanized sheet steel, ASTM A653, coating G90; or, aluminum sheet, ASTM B209, alloy 1100, 3003 or 5052.
- B. Joint Sealing: Refer to SMACNA HVAC Duct Construction Standards, paragraph S1.9.
  - Sealant: Elastomeric compound, gun or brush grade, maximum 25 flame spread and 50 smoke developed (dry state) compounded specifically for sealing ductwork as recommended by the manufacturer. Generally provide liquid sealant, with or without compatible tape, for low clearance slip joints and heavy, permanently elastic, mastic type where clearances are larger. Oil base caulking and glazing compounds are not acceptable because they do not retain elasticity and bond.
  - 2. Tape: Use only tape specifically designated by the sealant manufacturer and apply only over wet sealant. Pressure sensitive tape shall not be used on bare metal or on dry sealant.
  - 3. Gaskets in Flanged Joints: Soft neoprene.
- C. Approved factory made joints may be used.

# 2.2 DUCT CONSTRUCTION AND INSTALLATION

- A. Regardless of the pressure classifications outlined in the SMACNA Standards, fabricate and seal the ductwork in accordance with the following pressure classifications:
- B. Duct Pressure Classification:
   0 to 50 mm (2 inch)
- C. Seal Class: All ductwork shall receive Class A Seal
- D. Round and Flat Oval Ducts: Furnish duct and fittings made by the same manufacturer to insure good fit of slip joints. When submitted and

approved in advance, round and flat oval duct, with size converted on the basis of equal pressure drop, may be furnished in lieu of rectangular duct design shown on the drawings, however rectangular duct may not be substituted for flat oval or round duct specified on drawings.

- 1. Elbows: Diameters 80 through 200 mm (3 through 8 inches) shall be two sections die stamped, all others shall be gored construction, maximum 18 degree angle, with all seams continuously welded or standing seam. Coat galvanized areas of fittings damaged by welding with corrosion resistant aluminum paint or galvanized repair compound.
- 2. Provide bell mouth, conical tees or taps, laterals, reducers, and other low loss fittings as shown in SMACNA HVAC Duct Construction Standards.
- 3. Ribbed Duct Option: Lighter gage round/oval duct and fittings may be furnished provided certified tests indicating that the rigidity and performance is equivalent to SMACNA standard gage ducts are submitted.
  - a. Ducts: Manufacturer's published standard gage, G90 coating, spiral lock seam construction with an intermediate standing rib.
  - b. Fittings: May be manufacturer's standard as shown in published catalogs, fabricated by spot welding and bonding with neoprene base cement or machine formed seam in lieu of continuous welded seams.
- 4. Provide flat side reinforcement of oval ducts as recommended by the manufacturer and SMACNA HVAC Duct Construction Standard S3.13. Because of high pressure loss, do not use internal tie-rod reinforcement unless approved by the COR.
- E. Casings and Plenums: Construct in accordance with SMACNA HVAC Duct Construction Standards Section 6, including curbs, access doors, pipe penetrations, eliminators and drain pans. Access doors shall be hollow metal, insulated, with latches and door pulls, 500 mm (20 inches) wide by 1200 1350 mm (48 54 inches) high. Provide view port in the doors where shown. Provide drain for outside air louver plenum. Outside air plenum shall have exterior insulation. Drain piping shall be routed to the nearest floor drain.
- F. Volume Dampers: Single blade or opposed blade, multi-louver type as detailed in SMACNA Standards. Refer to SMACNA Detail Figure 2-12 for Single Blade and Figure 2.13 for Multi-blade Volume Dampers.
- G. Duct Hangers and Supports: Refer to SMACNA Standards Section IV. Avoid use of trapeze hangers for round duct.

# 2.3 DUCT ACCESS DOORS, PANELS AND SECTIONS

- A. Provide access doors, sized and located for maintenance work, upstream, in the following locations:
  - 1. Each duct mounted coil and humidifier.
  - 2. Each fire damper (for link service), smoke damper and automatic control damper.
  - 3. Each duct mounted smoke detector.
- B. Openings shall be as large as feasible in small ducts, 300 mm by 300 mm (12 inch by 12 inch) minimum where possible. Access sections in insulated ducts shall be double-wall, insulated. Transparent shatterproof covers are preferred for uninsulated ducts.
  - 1. For rectangular ducts: Refer to SMACNA HVAC Duct Construction Standards (Figure 2-12).

2. For round and flat oval duct: Refer to SMACNA HVAC duct Construction Standards (Figure 2-11).

# 2.4 DUCT MOUNTED THERMOMETER (AIR)

- A. Provide one (1) at discharge of each new air handling unit.
- B. Stem Type Thermometers: ASTM E1, 7 inch scale, red appearing mercury, lens front tube, cast aluminum case with enamel finish and clear glass or polycarbonate window, brass stem, 2 percent of scale accuracy to ASTM E77 scale calibrated in degrees Fahrenheit.
- C. Thermometer Supports:
  - 1. Socket: Brass separable sockets for thermometer stems with or without extensions as required, and with cap and chain.
  - 2. Flange: 3 inch outside diameter reversible flange, designed to fasten to sheet metal air ducts, with brass perforated stem.

# PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Comply with provisions of Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION, particularly regarding coordination with other trades and work in existing buildings.
- B. Fabricate and install ductwork and accessories in accordance with referenced SMACNA Standards:
  - 1. Drawings show the general layout of ductwork and accessories but do not show all required fittings and offsets that may be necessary to connect ducts to equipment, boxes, diffusers, grilles, etc., and to coordinate with other trades. Fabricate ductwork based on field measurements. Provide all necessary fittings and offsets at no additional cost to the government. Coordinate with other trades for space available and relative location of HVAC equipment and accessories on ceiling grid. Duct sizes on the drawings are inside dimensions which shall be altered by Contractor to other dimensions with the same air handling characteristics where necessary to avoid interferences and clearance difficulties.
  - 2. Provide duct transitions, offsets and connections to coils and other equipment in accordance with SMACNA Standards, Section II. Provide streamliner, when an obstruction cannot be avoided and must be taken in by a duct. Repair galvanized areas with galvanizing repair compound.
  - 3. Provide bolted construction and tie-rod reinforcement in accordance with SMACNA Standards.
  - 4. Construct casings, eliminators, and pipe penetrations in accordance with SMACNA Standards, Chapter 6. Design casing access doors to swing against air pressure so that pressure helps to maintain a tight seal.
- C. Install duct hangers and supports in accordance with SMACNA Standards, Chapter 4.
- D. Seal openings around duct penetrations of floors and fire rated partitions with fire stop material as required by NFPA 90A.

- E. Control Damper Installation:
  - 1. Provide necessary blank-off plates required to install dampers that are smaller than duct size. Provide necessary transitions required to install dampers larger than duct size.
  - 2. Assemble multiple sections dampers with required interconnecting linkage and extend required number of shafts through duct for external mounting of damper motors.
  - 3. Provide necessary sheet metal baffle plates to eliminate stratification and provide air volumes specified. Locate baffles by experimentation, and affix and seal permanently in place, only after stratification problem has been eliminated.
  - 4. Install all damper control/adjustment devices on stand-offs to allow complete coverage of insulation.
- F. Protection and Cleaning: Adequately protect equipment and materials against physical damage. Place equipment in first class operating condition, or return to source of supply for repair or replacement, as determined by COR. Protect equipment and ducts during construction against entry of foreign matter to the inside and clean both inside and outside before operation and painting. When new ducts are connected to existing ductwork, clean both new and existing ductwork by mopping and vacuum cleaning inside and outside before operation.

# 3.2 TESTING, ADJUSTING AND BALANCING (TAB)

A. Refer to Section 23 05 93, TESTING, ADJUSTING, and BALANCING FOR HVAC.

# 3.3 OPERATING AND PERFORMANCE TESTS

A. Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC and STEAM GENERATION

END OF SECTION 23 31 00

# SECTION 23 34 00 HVAC FANS

### PART 1 - GENERAL

# 1.1 DESCRIPTION

- A. Fans for heating, ventilating and air conditioning.
- B. Product Definitions: AMCA Publication 99, Standard 1-66.

### 1.2 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- C. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- D. Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT.
- E. Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.
- F. Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.
- G. Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.
- H. Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS.
- I. Section 23 82 16, AIR COILS.
- J. Section 26 29 11, LOW-VOLTAGE MOTOR STARTERS.

### 1.3 QUALITY ASSURANCE

- A. Refer to paragraph, QUALITY ASSURANCE, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Fans and power ventilators shall be listed in the current edition of AMCA 261, and shall bear the AMCA performance seal.
- C. Operating Limits for Centrifugal Fans: AMCA 99 (Class I, II, and III).
- D. Fans and power ventilators shall comply with the following standards:
  - 1. Testing and Rating: AMCA 210.
  - 2. Sound Rating: AMCA 300.
- E. Vibration Tolerance for Fans and Power Ventilators: Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.

## F. Performance Criteria:

- 1. The fan schedule shall show the design air volume and static pressure. Select the fan motor HP by increasing the fan BHP by 10 percent to account for the drive losses and field conditions.
- 2. Select the fan operating point as follows:
  - a. Forward Curve and Axial Flow Fans: Right hand side of peak pressure point
  - b. Air Foil, Backward Inclined, or Tubular: At or near the peak static efficiency
- G. Safety Criteria: Provide manufacturer's standard screen on fan inlet and discharge where exposed to operating and maintenance personnel.

- H. Corrosion Protection:
  - 1. Except for fans in fume hood exhaust service, all steel shall be mill-galvanized, or phosphatized and coated with minimum two coats, corrosion resistant enamel paint. Manufacturers paint and paint system shall meet the minimum specifications of: ASTM D1735 water fog; ASTM B117 salt spray; ASTM D3359 adhesion; and ASTM G152 and G153 for carbon arc light apparatus for exposure of non-metallic material.
  - 2. Fans for general purpose fume hoods, or chemical hoods, and radioisotope hoods shall be constructed of materials compatible with the chemicals being transported in the air through the fan.
- I. Spark resistant construction: If flammable gas, vapor or combustible dust is present in concentrations above 20% of the Lower Explosive Limit (LEL), the fan construction shall be as recommended by AMCA's Classification for Spark Resistant Construction. Drive set shall be comprised of non-static belts for use in an explosive.

#### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, and SAMPLES.
- B. Manufacturers Literature and Data:
  - 1. Fan sections, motors and drives.
- C. Certified Sound power levels for each fan.
- D. Motor ratings types, electrical characteristics and accessories.
- E. Roof curbs.
- F. Belt guards.
- G. Maintenance and Operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS.
- H. Certified fan performance curves for each fan showing cubic feet per minute (CFM) versus static pressure, efficiency, and horsepower for design point of operation.

## 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

VA-528A7-12-706 HVAC FANS 23 34 00 - 2

C.	B117-07a	sting and Materials (ASTM): .Standard Practice for Operating Salt Spray (Fog) Apparatus .Standard Practice for Testing Water Resistance of Coatings
		Using Water Fog Apparatus
	D3359-08	. Standard Test Methods for Measuring Adhesion by Tape Test
	G152-06	. Standard Practice for Operating Open Flame Carbon Arc Light
		Apparatus for Exposure of Non-Metallic Materials
	G153-04	. Standard Practice for Operating Enclosed Carbon Arc Light
		Apparatus for Exposure of Non-Metallic Materials
D.	National Fire Protection	n Association (NFPA):

- - NFPA 96-08.....Standard for Ventilation Control and Fire Protection of **Commercial Cooking Operations**
- E. National Sanitation Foundation (NSF):
  - 37-07 ...... Air Curtains for Entrance Ways in Food and Food Service **Establishments**
- F. Underwriters Laboratories, Inc. (UL): 181-2005 ...... Factory Made Air Ducts and Air Connectors

### 1.6 EXTRA MATERIALS

A. Provide one additional set of belts for all belt-driven fans.

# PART 2 - PRODUCTS

# 2.1 FAN SECTION (CABINET FAN)

Refer to specification Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS.

# 2.2 CENTRIFUGAL FANS

- A. Standards and Performance Criteria: Refer to Paragraph, QUALITY ASSURANCE. Record factory vibration test results on the fan or furnish to the Contractor.
- B. Fan arrangement, unless noted or approved otherwise:
  - 1. DWDl fans: Arrangement 3.
  - 2. SWSl fans: Arrangement 1, 3, 9 or 10.
- C. Construction: Wheel diameters and outlet areas shall be in accordance with AMCA standards.
  - 1. Housing: Low carbon steel, arc welded throughout, braced and supported by structural channel or angle iron to prevent vibration or pulsation, flanged outlet, inlet fully streamlined. Provide lifting clips, and casing drain. Provide manufacturer's standard access door. Provide 12.5 mm (1/2 inches) wire mesh screens for fan inlets without duct connections.
  - 2. Wheel: Steel plate with die formed blades welded or riveted in place, factory balanced statically and dynamically.

3. Shaft: Designed to operate at no more than 70 percent of the first critical speed at the top of the speed range of the fans class.

- 4. Bearings: Heavy duty ball or roller type sized to produce a BlO life of not less than 50,000 hours, and an average fatigue life of 200,000 hours. Extend filled lubrication tubes for interior bearings or ducted units to outside of housing.
- 5. Belts: Oil resistant, non-sparking and non-static.
- 6. Belt Drives: Factory installed with final alignment belt adjustment made after installation.
- 7. Motors and Fan Wheel Pulleys: Adjustable pitch for use with motors through 5HP, fixed pitch for use with motors larger than 5HP. Select pulleys so that pitch adjustment is at the middle of the adjustment range at fan design conditions.
- 8. Motor, adjustable motor base, drive and guard: Furnish from factory with fan. Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION for specifications. Provide protective sheet metal enclosure for fans located outdoors.
- 9. Furnish variable speed fan motor controllers where shown on the drawings. Refer to Section, MOTOR STARTERS. Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION for controller/motor combination requirements.

### PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install fan, motor and drive in accordance with manufacturer's instructions.
- B. Align fan and motor sheaves to allow belts to run true and straight.
- C. Bolt equipment to curbs with galvanized lag bolts.
- D. Install vibration control devices as shown on drawings and specified in Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.

# 3.2 PRE-OPERATION MAINTENANCE

- A. Lubricate bearings, pulleys, belts and other moving parts with manufacturer recommended lubricants.
- B. Rotate impeller by hand and check for shifting during shipment and check all bolts, collars, and other parts for tightness.
- C. Clean fan interiors to remove foreign material and construction dirt and dust.

# 3.3 START-UP AND INSTRUCTIONS

- A. Verify operation of motor, drive system and fan wheel according to the drawings and specifications.
- B. Check vibration and correct as necessary for air balance work.

# END OF SECTION 23 34 00

# SECTION 23 40 00 HVAC AIR CLEANING DEVICES

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. Air filters for heating, ventilating and air conditioning.
- B. Definitions: Refer to ASHRAE Standard 52.1 for definitions of face velocity, net effective filtering area, media velocity, resistance pressure drop), atmospheric dust spot efficiency and dust-holding capacity. ASHRAE Standard 52.1 measures arrestance, dust spot efficiency and dust holding capacity of filters.
- C. Refer to ASHRAE Standard 52.2 for definitions of MERV (Minimum Efficiency Reporting Value), PSE (Particle Size Efficiency) and particle size ranges for each MERV number. ASHRAE Standard 52.2 measures particle size efficiency (PSE).

#### 1.2 RELATED WORK

- A. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Filter housing and racks: Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS.

# 1.3 QUALITY ASSURANCE

- A. Air Filter Performance Report for Extended Surface Filters:
  - Submit a test report for each Grade of filter being offered. The report shall not be more than
    three (3) years old and prepared by using test equipment, method and duct section as
    specified by ASHRAE Standards 52.1 and 52.2 for type filter under test and acceptable to
    COR, indicating that filters comply with the requirements of this specification. Test for 150
    m/min (500 fpm) will be accepted for lower velocity rated filters provided the test report of
    an independent testing laboratory complies with all the requirements of this specification.
  - 2. Guarantee Performance: The manufacturer shall supply ASHRAE 52.2 test reports on each filter type submitted. Any filter supplied will be required to maintain the minimum efficiency shown on the ASHRAE Standard 52.2 report throughout the time the filter is in service. Within the first 6-12 weeks of service a filter may be pulled out of service and sent to an independent laboratory for ASHRAE Standard 52.2 testing for initial efficiency only. If this filter fails to meet the minimum level of efficiency shown in the previously submitted reports, the filter manufacturer/distributor shall take back all filters and refund the owner all monies paid for the filters, cost of installation, cost of freight and cost of testing.
- B. Filter Warranty for Extended Surface Filters: Guarantee the filters against leakage, blow-outs, and other deficiencies during their normal useful life, up to the time that the filter reaches the final pressure drop. Defective filters shall be replaced at no cost to the Government.

- C. Comply with UL Standard 586 for flame test.
- D. Nameplates: Each filter shall bear a label or name plate indicating manufacturer's name, filter size, rated efficiency.

### 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
  - Extended surface filters.
- C. Air Filter performance reports.
- D. Suppliers warranty.

### 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by basic designation only.
- B. American Society of Heating, Refrigerating and Air-conditioning Engineers, Inc. (ASHRAE):
  - 52.1-92R ...... Gravimetric and Dust-Spot procedures for Testing Air Cleaning

    Devices Used in General Ventilation for Removing Particulate

    Matter
  - 52.2-2007.....Method of Testing General Ventilation Air-Cleaning Devices for Removal Efficiency by Particle Size
- C. American Society of Mechanical Engineers (ASME):

  NQA-1-2008.....Quality Assurance Requirements for Nuclear Facilities

  Applications
- D. Underwriters Laboratories, Inc. (UL): 586; Amendment 20 March 2000 High-Efficiency, Particulate, Air Filter Units 900; Revision 15 July 2009 ....... Test Performance of Air Filter Units

### PART 2 - PRODUCTS

# 2.1 REPLACEMENT FILTER ELEMENTS TO BE FURNISHED

- A. To allow temporary use of HVAC systems for testing and in accordance with Paragraph, TEMPORARY USE OF MECHANICAL AND ELECTRICAL SYSTEMS in Section 01 00 00, GENERAL REQUIREMENTS, provide one complete set of spare filters to the COR.
- B. The COR will direct whether these additional filters will either be installed as replacements for dirty units or turned over to VA for future use as replacements.

# 2.2 EXTENDED SURFACE AIR FILTERS

A. Use factory assembled air filters of the extended surface type with supported or non-supported cartridges for removal of particulate matter in air conditioning, heating and ventilating systems. Filter units shall be of the extended surface type fabricated for disposal when the dust-load limit is reached as indicated by maximum (final) pressure drop.

- B. Filter Classification: UL approved Class 1 or Class 2 conforming to UL Standard 900.
- C. Filter Grades, Percent, Average ASHRAE Efficiency and Controlled Containment:

Table 2.20							
	Filter Grades						
MERV Value ASHRAE 52.2	Application	Dust-Spot Efficiency ASHRAE 52.1	Particle Size	Thickness /Type			
8	Pre-Filter	30 to 35%	3 to 10 Microns	50 mm (2-inch) Throwaway			
14	After-Filter	90%	0.3 to 1 Micron	300 mm (12-inch) Cartridge			

Table 2.2C

# D. Filter Media:

- 1. MERV 14 Supported (Rigid Pleated) Type: Media shall be composed of high density glass fibers or other suitable fibers. Fastening methods used to maintain pleat shape, (metal backing or aluminum separators) shall be sealed in a proper enclosing frame to insure no air leakage for life of filter. Staples and stays are prohibited.
- 2. MERV 8 (Pleated) Type: Media shall be composed of synthetic/natural fibers. Media shall maintain uniform pleat shape and stability for proper air flow and maximum dust loading. The media frame shall be constructed of aluminized steel. Bond the pleated media pack on all four edges to insure no air leakage for the life of the filter. Staples and stays are prohibited.
- E. Filter Efficiency and Arrestance: Efficiency and arrestance of filters shall be determined in accordance with ASHRAE Standard 52.1, and MERV value in accordance with ASHRAE Standard 52.2.
- F. Maximum initial resistance, recommended change over pressure drop, and maximum recommended final resistance, PA (inches of water), for each filter cartridge when operated at 150 m/min (500 feet per minute) face velocity shall be as specified in Table 2.2.F:

Table 2.2.F

Filter Initial and Final Resistance				
	Initial	Maximum	Maximum Final	
	Resistance	Recommended	Resistance	
		Change Over Pressure		
		Drop		

MERV 8 (2-inch deep)	95 (0.38)	190 (0.76)	250 (1.00)
MERV 14 (12-inch deep)	170 (0.68)	340 (1.36)	375 (1.50)

- G. Side Servicing Housings:
  - 1. Minimum 1.6 mm (l6 Gauge) galvanized steel, or aluminum, completely factory assembled with upstream and downstream flanges for connection into the duct system. Furnish housing length sufficient to provide for fully extended operating filter elements.
  - 2. Access doors: Double wall insulated, located on one side of the housing; with continuous gasketing on the perimeter and positive locking devices. Design doors to withstand a minimum positive/negative 1.0 kPa (4 inch WG) static pressure. Furnish access doors that are the full size of the housing.
  - 3. Filter slide channels: Channels shall incorporate a positive-sealing gasket material to seal the top and bottom of the filter cartridge frames to prevent bypass. Provide factory installed gasketing to prevent leakage between cartridges, and between cartridges and doors.
- H. Equipment Identification: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

#### 2.5 INSTRUMENTATION

- A. Magnehelic Differential Pressure Filter Gages: Nominal 100 mm (four inch) diameter, zero to 500 Pa (zero to two inch water gage). Gauges shall be flush-mounted in aluminum panel board, complete with static tips, copper or aluminum tubing, and accessory items to provide zero adjustment.
- B. DDC static (differential) air pressure measuring station. Refer to Specification Section 23 09 23 DIRECT DIGITAL CONTROL SYSTEM FOR HVAC
- C. Provide one DDC sensor across each extended surface filter. Provide Petcocks for each gauge or sensor.
- D. Provide one common filter gauge for two-stage filter banks with isolation valves to allow differential pressure measurement.

# 2.6 HVAC EQUIPMENT FACTORY FILTERS

- A. Manufacturer standard filters within fabricated packaged equipment should be specified with the equipment and should adhere to industry standard.
- B. Cleanable filters are not permitted.
- C. Automatic Roll Type filters are not permitted.

# PART 3 - EXECUTION

### 3.1 INSTALLATION

A. Install supports, filters and gages in accordance with manufacturer's instructions.

# 3.2 START-UP AND TEMPORARY USE

A. Clean and vacuum air handling units and plenums prior to starting air handling systems.

B. Install or deliver replacement filter units as directed by the COR.

END OF SECTION 23 40 00



# SECTION 23 57 00 PACKAGED HEAT TRANSFER STATIONS

### PART 1 - GENERAL

# 1.1 SECTION INCLUDES

- A. Variable Speed Heat Transfer Packages
- B. Products furnished but not installed under this Section.
  - 1. Variable speed drives

### 1.2 RELATED SECTIONS

#### 1.3 REFERENCES

- A. Hydraulic Institute Standards
- B. ANSI American National Standards Institute
- C. NEMA National Electrical Manufacturers Association
- D. U.L. 508 Electric Industrial Control Equipment
- E. N.E.C. Handbook N.F.P.A. 70
- F. AISC Manual of Steel Construction

# 1.4 SYSTEM DESCRIPTION

Furnish and install factory assembled heat transfer packaged pumping systems. The systems shall be pre-assembled and pre-tested units and shall require only Heating Hot Water Supply (HWS), Heating Hot Water Return (HWR), Medium Pressure Steam (MPS), Condensate, Domestic Cold Water make-up pipe connections, electrical power connection(s) and necessary connections to the various field mounted transmitters for control by the building automation system. Systems shall be designed to be disassembled and reassemble in field to accommodate restricted space access posed by existing mechanical equipment and services that cannot be disturbed.

# 1.5 SUBMITTALS

- A. SUBMIT IN ACCORDANCE WITH SPECIFICATION SECTION 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data:
  - 1. System design information sheet.
  - 2. Description of system operation.
  - 3. Packaged system dimension and general arrangement drawing.
  - 4. System Flow Diagram and Piping Schematic showing the overall system piping arrangement including remote mounted sensors and transmitters.
  - 5. Pump materials of construction and engineering data.
  - 6. Pump curve showing design point.
  - 7. Motor materials of construction and engineering data.
  - 8. Catalog information on valves, strainers and control components.

Complete description of Flow Test Procedures including performance data on all NIST Traceable instrumentation used during the test.

10. Submit manufacturer's installation instructions.

#### 1.6 QUALITY ASSURANCE

- The packaged pumping system manufacturer shall provide published catalog data clearly indicating that HVAC Packaged Pumping Systems are one of their standard product lines.
- C. The packaged pumping system manufacturer shall have in place Quality Assurance Program to assure the quality of engineering design, components, materials and workmanship provided in the packaged pumping system. Upon request, this procedure shall be submitted to the engineer.
- The system manufacturer shall have a minimum of ten years manufacturing and D. application experience and shall be responsible for the proper pressure and flow in the system.
- The packaged pumping system manufacturer must have proof experience, including a list of similar installations, which shall be provided to the engineer upon request.

#### PART 2 PRODUCTS

#### 2.1 MANUFACTURED UNIT - HEAT TRANSFER PACKAGE

### General:

The packaged system shall consist of a system base, pumps, motors, valves, manifolds, intermediate piping, piping supports, heat exchangers and other components as listed in this specification for a complete system. Contractor shall have the option to field-fabricate the system where conditions necessitate. Down-time constraints shall not be modified to accommodate this option.

#### В. Components

- All components shall be mounted on a structural steel base. The base shall be large enough to support the packaged pumping system's pumps, piping, variable frequency drive's (VFD's). Steel supports shall be welded to the base to support the piping, control panel and VFD's. Both the base and supports shall consist of structural steel components, all welded per the AISC Manual of Steel Construction, Part 4, "Welded Joints".
- 2. Pumps shall be vertical, close coupled inline type with ANSI flanged connections, cast iron casing, bronze impeller and mechanical seal. Pumps shall be mounted on the system base via a cast iron mounting ring or a fabricated steel flange support.
- 3. Motors shall be of the premium-efficiency, inverter duty type, ODP with a minimum 1.15 service factor. Motor manufacturer's stated efficiencies shall be derived from tests conducted in accordance with NEMA Standard MG1-12.53a which is based upon IEEE Standard 112, Method B.
- 4. The pump design conditions and motor horsepower requirements shall be as described on the pump schedule. The pump shall not overload the motor at any point on the pump curve.
- The package piping shall consist of fabricated welded steel headers with steel and/or cast iron fittings in and out of pumps. All piping for the system shall be as indicated on the drawings. Branch piping to the pumps shall be sized for the design capacity of the pump. Supports shall be provided for the suction and discharge headers. Piping supports shall include insulation protection saddles. The branch suction and discharge piping on each pump shall be supported independently of pump connections.

Drain plugs shall be provided at all low points in the system piping where water can be trapped. Manual air vents shall be provided at all high points in the system piping where air can be trapped.

- 6. Butterfly valves shall be furnished on the suction of each constant-speed pump. Butterfly valves shall be furnished on the suction and discharge of each variable-speed pump. Valves shall be constructed with a ductile iron lug style body, EPDM seat, aluminum bronze disc and stainless steel shaft. Valves 6" and smaller shall be provided with lever operators and valves 8" and larger shall be provided with hand wheel and gear operator.
- 7. A suction strainer shall be installed on the suction of each pump. The strainer shall be of the diffuser type or inline "Y" type. The strainer shall be constructed with a cast iron body and perforated 304 stainless steel screen. Disposable fine mesh screens shall be included for initial startup. The strainer shall include a mounted blow-down valve. Blow-down valve shall be piped to drain by contractor.
- 8. A globe style, center guided, silent check valve shall be installed on the discharge of each variable-speed pump. The valve shall be cast iron body with a pressure rating exceeding the pump shut-off head plus maximum suction pressure. Valve shall have a bronze disc, stainless steel shaft and spring and a resilient seat.
- 9. Shell-and-Tube, U-Tube Heat Exchanger:
  - A steam to water removable U-Tube type heat exchanger of the sizes and capacities noted on the schedule and constructed in accordance with ASME Pressure Vessel Code for 861 kPa (125 psig) working pressure in both shell and tubes. The heat exchanger shall be cast iron head (of either two or four pass configuration) with steel shell and steel or brass tube supports.
  - Tubes shall be of 20 mm (3/4 inch) 20 gauge copper and 2. shall be secured to a steel tubesheet via rolled joints.
  - 3. Heat exchanger shall be constructed of a cast iron or fabricated steel head, steel shell, and steel baffles, tie rods, and spacers. Unit shall have a compressed fiber gasket to seal the shell at the tubesheet.
  - 4. Heat exchanger design shall allow for a maximum tubeside velocity no greater than 2.3 m/s (7.5 ft/s) and a shell side velocity no greater than 1.2 m/s (4.0 ft/s). Unit shall be constructed with a fouling factor not less than 0.00018~mK/W (0.001~ft~hrF/Btu). Unit diameter shall be no less than 12 inches and the bundle length shall be no greater than that scheduled.
  - 5. Heat exchanger shall provide the scheduled thermal performance.
- 10. Grade 2A pressure gauges, 4½" diameter, shall be furnished mounted on the control cubicle for indication of all individual pump suction/discharge pressures and all common suction and discharge pressures. All control sensing lines and gauge connections shall be piped with full port, balltype shut-off valves. Gauges shall be mounted such that they can be viewed from the front of the control enclosure.
- 11. A bladder type expansion tank shall be provided on the pump skid as indicated on the drawings. The expansion tank shall have a carbon steel shell and a replaceable heavy-duty butyl bladder. The tank must be constructed in accordance with Section VIII of the ASME Code for Boilers and Pressure Vessels and stamped for 125 PSI working pressure. The tank volume shall be as indicated on the drawings.
- 12. A vortex type air separator shall be provided on the pump skid as indicated on the drawings. The air separator shall have a carbon steel

shell and must be constructed in accordance with Section VIII of the ASME Code for Boilers and Pressure Vessels and stamped for 125 PSI working pressure. A blow-down connection shall be provided to facilitate routine cleaning of the air separator. An automatic air release valve shall be provided at the high-point of the air separator complete with isolation valve.

- 13. The pumping system shall include a ¾" make-up water connection complete with pressure reducing valve, isolation valves and bypass piping.
- 14. Provide a chemical pot-feeder constructed of carbon steel with a funnel and all valves, drains and accessories required and as indicated on the drawings. Unit shall be securely mounted on the skid.
- 15. Provide a side-stream type water filter as indicated on the plans.
- 16. The packaged pumping system shall include all controls necessary to operate the system. The microprocessor based Direct Digital Controller (DDC) shall be of the same manufacture as the Building Automation System (BAS) and shall have "stand alone" capability, including on-board software necessary to operate the pumping system should the signal from the BAS be temporarily lost. The controller must be fully wired, programmed and tested by the packaged pumping system manufacturer before shipment from the factory.
- 17. The control system shall be designed to start and stop the variable-speed pumps and modulate their speed as required by system demands. The pumping system controller shall provide for Direct Digital Control with discrete signal selection. The DDC algorithm will include a factory tuned proportional, integral and derivative (PID) control action. Use of any or all of these terms as well as changing their constants shall be user online programmable. The 4-20mA DC signal(s) from the remote mounted differential pressure transmitter(s) shall be transmitted over a No. 22 gauge or larger shielded cable or broadcast over the BAS communication trunk to the pumping system controller located in the logic section of control enclosure. The pumping system controller shall have fieldprogrammable independent set points, the value of which shall be the optimum differential pressure as designed for each remote location or zone. The zone that deviates farthest from its independent set point shall be the controlling input to insure that the pumps run at the minimum speed necessary to satisfy demand in all zones. The pumping system controller shall have loop alarms for all analog inputs. Failure of any remote transmitter shall remove that transmitter signal from the remaining control functions. Failure of all remote transmitters shall activate a pre-set speed control output that will run all variable speed pumps at an adjustable set speed. The controller shall be housed in a metal enclosure designed for EMI and RFI rejection. The pumping system controller shall enable and modulate variable speed pumps in accordance with a Best-Efficiency Control program to insure that the system operates at maximum efficiency throughout the range of operation. The Best-Efficiency Control program shall evaluate system flow, system TDH and input kW to operate only the most efficient combinations of pumps.
  - 18. The pumping system controls for the variable-speed pumps shall include semi-automatic and manual modes of operation. The operator shall be capable of starting each pump manually while allowing the automatic controls to adjust the pump speed to maintain system differential pressure. This shall be accomplished by utilizing the pump Hand-Off-Auto switch on the system control panel. The operator shall also have the option of starting each pump and controlling its speed manually. This shall be accomplished by utilizing the pump Hand-Off-Auto switch and the manual speed adjustment on each variable frequency drive control panel.

19. The control system shall include a failure alarm for each pump. Each alarm shall include a current switch, adjustable time delay, alarm light and manual reset. Upon a pump failure alarm, the pump shall be stopped and locked-out of service until the alarm is manually reset via a panel mounted reset push button. A pump failure alarm shall automatically replace the failed pump with the next pump in the sequence.

- 20. The power distribution panel shall be NEMA 1, single door design with single-point input power connection.
  - Power distribution panel shall include:
    - 1) Main input terminal block
    - 2) Control circuit transformer
    - 3) Power distribution equipment for each pump
    - 4) Disconnect switch with thru-the-door handle for each pump
    - Magnetic starter and overload for each constant-speed pump 5)
- 21. The control logic panel shall be NEMA 1, single door design with singlepoint input power connection.
  - Control logic panel shall include:
    - Door mounted Control Power On/Off switch and light 1)
    - 2) System Local-Off-Remote switch (remote provides for remote system start/stop from BAS)
    - System Initialized light 3)
    - 4) Hand-Off-Auto switch for each pump
    - Run Light for each pump
    - Pump Failure alarm light and reset
    - 7) Pump sequencing logic
    - 8) Elapsed Time Meter for each pump
    - All control panel indicating lights shall be a million hour average life, LED type.
    - 10) System BAS Controller for variable speed system
    - 11) Local Display or Human Machine Interface (HMI)
    - 12) Interface controls for variable frequency drives
    - 13) Provisions for single communication cable connection to BAS.

All communication between the pumping system controller and the BAS shall be via the native protocol of the BAS. Separate data gathering panels and protocol converters used for communication with the BAS shall not be acceptable.

Door handles shall be provided for each panel disconnect switch so that power circuits are turned off before the door can be opened. All electric wiring between the control panel, magnetic starters, variable frequency drives, electric motors and system mounted controls shall be completed per N.E.C. standards.

- 22. The DDC controller shall be of the same manufacture as the existing BAS.
- 23. The local user interface or Human Machine Interface (HMI) unit shall be mounted in the door of the system control enclosure. It shall be microcomputer based and hold its firmware in EPROM memory. The system interface shall be of the same manufacture as the BAS. On-line programmable data entries such as set points, calculated results and totalization shall be stored in non-volatile memory. All data entry shall be modifiable by system mounted keypad or HMI using engineering units such as GPM, PSI and feet of head. The unit shall be programmable and modifiable from the BAS central computer.
- 24. To insure safety of the equipment the VFD shall include these protective features and options:

Static instantaneous over current and over voltage trip.

- b. Power unit over temperature protection
- Motor inverse time overload protection c.
- d. Motor amperage/load display
- Speed display e.
- Automatic restart after power failure or drive fault. The drive f. shall attempt a minimum of two restarts before a complete drive shut-down.
- Power On indication a.
- h. Manual speed adjustment
- i. Hand-Off-Automatic switch or Manual-Automatic switch with Start-Stop push-button.
- j. VFD Fault indication.

The drive shall include built-in diagnostics. Diagnostics shall be in the form of built-in LED indicating lights, LED readout or a Fault Diagnostic test card. If a test card is utilized, it shall be interchangeable between drives. The drive shall be listed by UL, ETL and/or CSA.

The VFD shall include a UL Listed manual full-speed bypass starter. The VFD bypass shall include the following features:

- a. Door interlocked circuit breaker
- Motor overload relay b.
- 2-contactor bypass starter
- Drive-Off-Bypass switch
- Drive and Bypass indication
- 25. The packaged pumping system manufacturer shall provide complete, selfcontained, variable capacitance type, differential pressure transmitter(s). The transmitter(s) shall be installed by the contractor where indicated on the drawings. Wiring terminals and electronics shall be in separate compartments so that the electronics remain sealed during installation. Reverse polarity protection shall be included to keep wiring mishaps from damaging the transmitter. The 4-20mA DC signal(s) shall be transmitted over a No. 22 gauge or larger shielded cable (supplied by the contractor) directly to the control panel terminal strip or to the nearest BAS control enclosure for broadcast back to the pumping
  - Design range shall be as required for the system. Transmitter shall have external zero and span adjustments. Over-pressure limits of 0 to 2,000 PSI on either side without damage to the transmitter. Minimum accuracy shall be ± 0.15% of calibrated span, includes combined effects of linearity, hysteresis and repeatability. Stability shall be  $\pm$  0.25% of upper range limit for six months. No internal mechanical linkages shall be used in the transmitter.
- 26. The flow transducer shall include a vortex-shedding type sensor with no moving parts. A piezo resistive sensor shall be used to detect vortex signals. The flow transducer shall have an achievable accuracy of  $\pm$  1% of full scale with flow velocities of .5 to 15 fps. The sensor shall be constructed of  $\mbox{Ultem}\mbox{\ensuremath{\mathbb{B}}}$  with the shedder bar constructed of 316 stainless steel. The unit shall be both insertable and removable through a balltype valve when the pipe is under pressure. The electronics shall be hermetically sealed and shall transmit a 4 to 20mA signal to be used for pump sequencing, BTU calculation, and/or shall be transmitted to the BAS for performance tracking.

03/14/2012 PHASE 2

The flow meter shall be a dual turbine, insertion type flow meter. flow meter shall have two contra-rotating axial turbines, each with its own rotational sensing system and an averaging circuit to reduce measurement errors due to swirl. Rotational sensing of each turbine shall be accomplished electronically by sensing impedance change and not with magnetic or photoelectric means.

The sensor shall have a maximum operating pressure of 400 PSI and an ambient temperature range of -5 to 160° F. Pressure drop shall be less than 1 PSI at 20 ft/s in 2.5" pipe, decreasing in larger pipes and lower velocities. Accuracy shall be ± 0.5% of reading at calibrated velocity, ± 1% of reading from 3 to 30 ft/s (10:1 range) and  $\pm$  2% of reading from 0.4 to 20 ft/s (50:1 range). Sensor shall be wet-calibrated in a flow laboratory against primary volumetric standards directly traceable to NIST. Provide certificate of calibration with each flow meter.

The sensor shall have non-isolated 4-20mA and 0-10 V analog output signals that are linear with the flow rate.

The turbine elements shall be made of polypropylene with sapphire jewel bearings and tungsten carbide shafts. The flow sensor shall be constructed of electroless nickel plated brass with a watertight aluminum electronics enclosure.

The unit shall be both insertable and removable through a ball-type valve when the pipe is under pressure.

#### 2.2 FABRICATION

The packaged pumping system manufacturer shall provide a completely assembled and tested water circulating system that is fabricated using all new components.

#### 2.3 FINISHING

- All steel components shall be cleaned, degreased and painted with a rustpreventive, self-etching primer.
- The complete packaged pumping system shall be factory painted with lead-free, high-gloss enamel prior to shipment.
- Nameplates for each major component including pumps, motors, variable frequency drives, and electrical control panels shall be masked prior to painting and all shall be clean and legible prior to shipment.

### 2.4 SOURCE QUALITY CONTROL

#### FACTORY TESTS Α.

- After factory assembly, the packaged pumping system shall be hydrostatically tested at 50 PSIG over maximum system working pressure or to 150 PSIG (whichever is higher) for a minimum of one hour.
- Each pump shall be individually tested for performance while at full speed. Pump performance measurements shall include shut-off pressure and pump TDH and motor full load amps at 25%, 50%, 75% and 100% of pump design capacity.

During the variable speed wire-to-water efficiency test each pump and combination of pumps shall be operated according to multiple system curves in increments of 5% from 25% to 100% of design flow. The system is adjusted to operate the pump(s) at each design point where system/pump flow, system/pump head, pump speed, amperage, input kW and supply voltage are recorded. This test provides actual system wire-to-water efficiency based on the selected set points.

- 4. Each Control panel must be designed, built and tested per UL508A prior to integrating with the pumping system. The testing includes verification of wiring, component operation, programming and sequence testing.
- 5. The pumping system must be connected to a test tank with the actual components, valves and sensors specific for this project. Any calibrations or adjustments that are required for proper system operation will be performed. All sequencing controls, alarms and system operation must be tested and verified to be functional prior to removal from the test tank. These tests may be witnessed by the engineer, owner or a representative if required.
- 6. All testing must be performed with NIST Traceable instrumentation. The NIST Traceable instrumentation must be independently calibrated in accordance with NIST and Hydraulic Institute Standards.

#### INSPECTIONS С.

The manufacturer shall provide access to the owner or his representative to the fabrication facilities at any time during the construction of the packaged pumping system. All testing may be witnessed by a representative of the owner, contractor and/or consulting engineer.

#### VERIFICATION OF PERFORMANCE D.

A written report certified by an officer of manufacturing company shall be provided to the owner's representative on request.

#### PART 3 EXECUTION

#### 3.1 INSTALLATION

- The contractor shall off-load, store, locate, level, anchor, pipe and wire the Α. system and the remote components in accordance with manufacturer's instructions.
- Alignment: Base mounted pumps shall be aligned by the contractor after installation using a qualified millwright and the alignment shall be certified in writing.
- С. The contractor shall confirm that all components necessary for a complete and proper startup are installed, wired and operational prior to scheduling startup. A system startup request form shall be filled out and signed by the contractor and returned to the factory to certify readiness.

# 3.2

All piping in the building system shall be thoroughly cleaned and free of debris, dirt, sand and other impurities. After flushing the system, start-up of the pumping system can commence.

#### 3.3 ADJUSTING

During initial start up, the mechanical contractor shall, under the supervision and assistance of the manufacturer or his representative, adjust all mechanical and electrical components to actual job conditions. Balance all components of the system in accordance with section 23 05 93.

#### 3.4 IDENTIFICATION

Upon completed installation, provide self-adhering pipe labels on all new piping to clearly indicate service and direction of flow. Provide permanently affixed, dual layer, engraved plastic equipment tags to identify each scheduled component of the heat transfer package. Provide engraved brass valve tags secured to each valve handle with stainless steel chain; provide or update valve chart as applicable and coordinate numbering sequence with Owner. Submit all labeling material for approval prior to construction.

#### 3.5 DEMONSTRATION

- A. After all adjustments have been completed, the COR and designated maintenance personnel will receive a thorough demonstration of the system operation and will receive training in the operation and adjustment of all components.
- System manufacturer or his representative shall provide up to two (2) 8 hour days of adjustment and training for VA personnel on the operation and maintenance of the packaged pumping system.

END OF SECTION



# SECTION 23 73 00 INDOOR CENTRAL-STATION AIR-HANDLING UNITS

# PART 1 - GENERAL

### 1.1 DESCRIPTION

- A. Air handling units including integral components specified herein.
- B. Definitions: Air Handling Unit (AHU): A factory fabricated and tested assembly of modular sections consisting of fan, coils, filters, and other necessary equipment to perform one or more of the following functions of circulating, cleaning, heating, cooling, humidifying, dehumidifying, and mixing of air. Design capacities of units shall be as scheduled on the drawings.

# 1.2 RELATED WORK

- A. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Piping and duct insulation: Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION.
- C. Piping and valves: Section 23 21 13 / 23 22 13, HYDRONIC PIPING / STEAM AND CONDENSATE HEATING PIPING.
- D. Heating and cooling coils and pressure requirements: Section 23 82 16, AIR COILS.
- E. Return and exhaust fans: Section 23 34 00, HVAC FANS.
- F. Requirements for flexible duct connectors, sound attenuators and sound absorbing duct lining, and air leakage: Section 23 31 00, HVAC DUCTS and CASINGS.
- G. Air filters and filters' efficiency: Section 23 40 00, HVAC AIR CLEANING DEVICES.
- H. HVAC controls: Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.
- I. Testing, adjusting and balancing of air and water flows: Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.
- J. Types of motors: Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT.

# 1.3 QUALITY ASSURANCE

- A. Refer to Article, Quality Assurance, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Air Handling Units Certification: Certify air-handling units in accordance with ARI 430.
- C. Heating, Cooling, and Air Handling Capacity and Performance Standards: ARI 430, ARI 410, ASHRAE 51, and AMCA 210.
- D. Performance Criteria:
  - The fan schedule indicates design CFM Design Cubic Feet per Minute. The Fan motor BHP at the operating point on the fan curves shall be increased by 10% (safety factor) to cover the drive losses and field conditions. The fan motor shall be selected within the rated nameplate capacity, without relying upon NEMA Standard Service Factor.
  - 2. Select the fan operating point as follows:
    - a. Forward Curve and Axial Flow Fans: Right hand side of peak pressure point.
    - b. Air Foil, Backward Inclined, or Tubular: At or near the peak static efficiency.
  - 3. Operating Limits: AMCA 99.
- E. Units shall be constructed by a manufacturer who has been manufacturing air handling units for at least five (5) years.

# 1.4. SUBMITTALS:

A. The contractor shall, in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, furnish a complete submission for all air handling units covered in the project. The submission shall include all information listed below. Partial and incomplete submissions shall be rejected without reviews.

- B. Manufacturer's Literature and Data:
  - Submittals for AHUs shall include fans, drives, motors, coils, humidifiers, mixing box with outside/return air dampers, filter housings, blender sections, and all other related accessories. The contractor shall provide custom drawings showing total air handling unit assembly including dimensions, operating weight, access sections, flexible connections, door swings, control penetrations, electrical disconnect, lights, duplex receptacles, switches, wiring, utility connection points, unit support system, vibration isolators, drain pan, pressure drops through each component (filter, coil etc).
  - 2. Submittal drawings of section or component only will not be acceptable. Contractor shall also submit performance data including performance test results, charts, curves or certified computer selection data; data sheets; fabrication and insulation details. If the unit cannot be shipped in one piece, the contractor shall indicate the number of pieces that each unit will have to be broken into to meet shipping and job site rigging requirements. This data shall be submitted in hard copies and in electronic version compatible to AutoCAD version used by the VA at the time of submission.
  - 3. Submit sound power levels in each octave band for fan and at entrance and discharge of AHUs at scheduled conditions.
  - 4. Provide fan curves showing cubic feet per minute, static pressure, efficiency, and horsepower for design point of operation and at maximum design cubic feet per minute.
  - 5. Submit total fan static pressure, external static pressure, for AHU including total, inlet and discharge pressures, and itemized specified internal losses and unspecified internal losses. Refer to air handling unit schedule on drawings.
- C. Maintenance and operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS. Include instructions for lubrication, filter replacement, motor and drive replacement, spare part lists, and wiring diagrams.
- D. Submit shipping information that clearly indicates how the units will be shipped in compliance with the descriptions below.
  - 1. Units shall be shipped in one (1) piece where possible and in shrink wrapping to protect the unit from dirt, moisture and/or road salt.
  - 2. If not shipped in one (1) piece, provide manufacturer approved shipping splits where required for installation or to meet shipping and/or job site rigging requirements in modular sections. Indicate clearly that the shipping splits shown in the submittals have been verified to accommodate the construction constraints for rigging as required to complete installation and removal of any section for replacement through available access without adversely affecting other sections.
  - 3. If shipping splits are provided, each component shall be individually shrink wrapped to protect the unit and all necessary hardware (e.g. bolts, gaskets etc.) will be included to assemble unit on site (see section 2.1.A4).
  - 4. Lifting lugs will be provided to facilitate rigging on shipping splits and joining of segments. If the unit cannot be shipped in one piece, the contractor shall indicate the number of pieces that each unit will have to be broken into to meet shipping and job site rigging requirements.

## 1.5 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

B. Air-Conditioni	ng, Heating, and Refrigeration Institute (AHRI)/(ARI):
410-01	Standard for Forced-Circulation Air-Heating and Air-Cooling
	Coils
430-09	

- C. Air Movement and Control Association International, Inc. (AMCA): 210-07.....Laboratory Methods of Testing Fans for Rating
- D. American Society of Heating, Refrigerating and Air-conditioning Engineers, Inc. (ASHRAE):

170-2008 ...... Ventilation of Health Care Facilities

E. American Society for Testing and Materials (ASTM):

ASTM D1735-08.....Standard Practice for Testing Water Resistance of Coatings
Using Water Fog Apparatus

ASTM D3359-08 ...... Standard Test Methods for Measuring Adhesion by Tape Test

F. Military Specifications (Mil. Spec.):

MIL-P-21035B-2003 ......Paint, High Zinc Dust Content, Galvanizing Repair (Metric)

G. National Fire Protection Association (NFPA):

NFPA 90A.....Standard for Installation of Air Conditioning and Ventilating Systems, 2009

H. Energy Policy Act of 2005 (P.L.109-58)

# PART 2 - PRODUCTS

# 2.1 AIR HANDLING UNITS

- A. General:
  - 1. AHUs shall be entirely of double wall galvanized steel construction without any perforations except as specified in section 2.1.C.2. Casing is specified in paragraph 2.1.C. Foil face lining is not an acceptable substitute for double wall construction. Galvanizing shall be hot dipped conforming to ASTM A525 and shall provide a minimum of 0.275 kg of zinc per square meter (0.90 oz. of zinc per square foot) (G90). Aluminum constructed units may be provided subject to VA approval and documentation that structural rigidity is equal or greater than the galvanized steel specified.
  - 2. The contractor and the AHU manufacturer shall be responsible for insuring that the unit will not exceed the allocated space shown on the drawings, including required clearances for service and future overhaul or removal of unit components. All structural, piping, wiring, and ductwork alterations of units, which are dimensionally different than those specified, shall be the responsibility of the contractor at no additional cost to the government.
  - 3. AHUs shall be fully assembled by the manufacturer in the factory in accordance with the arrangement shown on the drawings. The unit shall be assembled into the largest sections possible subject to shipping and rigging restrictions. The correct fit of all components and casing sections shall be verified in the factory for all units prior to shipment. All units shall be fully assembled, tested and then split to accommodate shipment and job site rigging. On units not shipped fully assembled, the manufacturer shall tag each section and include air flow direction to facilitate assembly at the job site. Lifting lugs or shipping skids shall be provided for each section to allow for field rigging and final placement of unit.

4. The AHU manufacturer shall provide the necessary gasketing, caulking, and all screws, nuts, and bolts required for assembly. The manufacturer shall provide a local representative at the job site to supervise the assembly and to assure the units are assembled to meet manufacturer's recommendations and requirements noted on the drawings. Provide documentation that this representative has provided this service on similar jobs to the Contracting Officer. If a local representative cannot be provided, the manufacturer shall provide a factory representative.

- 5. Gaskets: All door and casing and panel gaskets and gaskets between air handling unit components, if joined in the field, shall be high quality which seal air tight and retain their structural integrity and sealing capability after repeated assembly and disassembly of bolted panels and opening and closing of hinged components. Bolted sections may use a more permanent gasketing method provided they are not disassembled.
- 6. Structural Rigidity: Provide structural reinforcement when required by span or loading so that the deflection of the assembled structure shall not exceed 1/200 of the span based on a differential static pressure of 1991 PA (8 inch WG) or higher.

# B. Base:

- Provide a heavy duty steel base for supporting all major AHU components. Bases shall be
  constructed of wide-flange steel I-beams, channels, or minimum 125 mm (5 inch) high 3.5
  mm (10 Gauge) steel base rails. Welded or bolted cross members shall be provided as
  required for lateral stability. Contractor shall provide supplemental steel supports as
  required to obtain proper operation heights for cooling coil condensate drain trap as shown
  on drawings.
- 2. AHUs shall be completely self supporting for installation on concrete housekeeping pad, steel support pedestals, or suspended as shown on drawings.
- 3. The AHU bases not constructed of galvanized steel shall be cleaned, primed with a rust inhibiting primer, and finished with rust inhibiting exterior enamel.
- C. Casing (including wall, floor and roof):
  - 1. General: AHU casing shall be constructed as solid double wall, galvanized steel insulated panels without any perforations, integral of or attached to a structural frame. The thickness of insulation, mode of application and thermal breaks shall be such that there is no visible condensation on the exterior panels of the AHU located in the non-conditioned spaces.
  - 2. Casing Construction:

Table 2.1.C.2

Outer Panel	0.8 mm (22 Gage) Minimum
Inner Panel	0.8 mm (22 Gage) Minimum
Insulation	Foam
Thickness	50 mm (2 inch) Minimum
Density	48 kg/m³ (3.0 lb/ft³) Minimum
Total R Value	2.3 m <sup>2</sup> .K/W (13.0 ft <sup>2.0</sup> F.hr/Btu)
	Minimum

3. Casing Construction (Contractor's Option):

Table 2.1.C.3

Outer Panel	1.3 mm (18 Gage) Minimum
Inner Panel	1.0 mm (20 Gage) Minimum
Insulation	Fiberglass
Thickness	50 mm (2 inch) Minimum
Density	24 kg/m³ (1.5 lb/ft³) Minimum

Total R Value	1.4 m <sup>2</sup> .K/W (8.0 ft <sup>2</sup> . OF.hr/Btu)					
	Minimum					

4. Blank-Off: Provide blank-offs as required to prevent air bypass between the AHU sections, around coils, and filters.

- 5. Casing panels shall be secured to the support structure with stainless steel or zinc-chromate plated screws and gaskets installed around the panel perimeter. Panels shall be completely removable to allow removal of fan, coils, and other internal components for future maintenance, repair, or modifications. Welded exterior panels are not acceptable.
- 6. Access Doors: Provide in each access section and where shown on drawings. Doors shall be a minimum of 50 mm (2 inch) thick with same double wall construction as the unit casing. Doors shall be a minimum of 600 mm (24 inches) wide, unless shown of different size on drawings, and shall be the full casing height up to a maximum of 1850 mm (6 feet). Doors shall be gasketed, hinged, and latched to provide an airtight seal. The access doors for fan section, mixing box, humidifier, coil section shall include a minimum 150 mm x 150 mm (6 inch x 6 inch) double thickness, with air space between the glass panes tightly sealed, reinforced glass or Plexiglas window in a gasketed frame.
  - a. Hinges: Manufacturers standard, designed for door size, weight and pressure classifications. Hinges shall hold door completely rigid with minimum 45 kg (100 lb) weight hung on latch side of door.
  - b. Latches: Non-corrosive alloy construction, with operating levers for positive cam action, operable from either inside or outside. Doors that do not open against unit operating pressure shall allow the door to ajar and then require approximately 0.785 radian (45 degrees) further movement of the handle for complete opening. Latch shall be capable of restraining explosive opening of door with a force not less than 1991 Pa (8 inch WG).
  - c. Gaskets: Neoprene, continuous around door, positioned for direct compression with no sliding action between the door and gasket. Secure with high quality mastic to eliminate possibility of gasket slipping or coming loose.
- 7. Provide sealed sleeves, metal or plastic escutcheons or grommets for penetrations through casing for power and temperature control wiring and pneumatic tubing. Coordinate with electrical and temperature control subcontractors for number and location of penetrations. Coordinate lights, switches, and duplex receptacles and disconnect switch location and mounting. All penetrations and equipment mounting may be provided in the factory or in the field. All field penetrations shall be performed neatly by drilling or saw cutting. No cutting by torches will be allowed. Neatly seal all openings airtight.

# D. Floor:

- Unit floor shall be level without offset space or gap and designed to support a minimum of 488 kg/square meter (100 lbs per square foot) distributed load without permanent deformation or crushing of internal insulation. Provide adequate structural base members beneath floor in service access sections to support typical service foot traffic and to prevent damage to unit floor or internal insulation. Unit floors in casing sections, which may contain water or condensate, shall be watertight with drain pan.
- 2. Where indicated, furnish and install floor drains, flush with the floor, with nonferrous grate cover and stub through floor for external connection.
- E. Condensate Drain Pan: Drain pan shall be designed to extend entire length of cooling coils including headers and return bends. Depth of drain pan shall be at least 43 mm (1.7 inches) and shall handle all condensate without overflowing. Drain pan shall be double-wall, double sloping type, and fabricated from stainless (304) with at least 50 mm

(2 inch) thick insulation sandwiched between the inner and outer surfaces. Drain pan shall be continuous metal or welded watertight. No mastic sealing of joints exposed to water will be permitted. Drain pan shall be placed on top of casing floor or integrated into casing floor assembly. Drain pan shall be pitched in all directions to drain line.

- 1. An intermediate, stainless-steel (304) condensate drip pan with copper downspouts shall be provided on stacked cooling coils.
  - Use of intermediate condensate drain channel on upper casing of lower coil is permissible provided it is readily cleanable. Design of intermediate condensate drain shall prevent upper coil condensate from flowing across face of lower coil.
- 2. Drain pan shall be piped to the exterior of the unit. Drain pan shall be readily cleanable.
- 3. Installation, including frame, shall be designed and sealed to prevent blow-by.

# F. Fans Sections:

- 1. Fans shall be minimum Class II construction, air foil or backward type as indicated on drawings, factory balanced and rated in accordance with AMCA 210 or ASHRAE 51. Provide self-aligning, pillow block, regreasable ball-type bearings selected for a B (10) life of not less than 50,000 hours and an L (50) average fatigue life of 200,000 hours per AFBMA Standard 9. Extend bearing grease lines to motor and drive side of fan section. Fan shall be located in airstream to assure proper air flow.
- 2. Allowable vibration tolerances for fan shall not exceed a self-excited vibration maximum velocity of 0.005 m/s (0.20 inch per second) RMS, filter in, when measured with a vibration meter on bearing caps of machine in vertical, horizontal and axial directions or measured at equipment mounting feet if bearings are concealed. After field installation, compliance to this requirement shall be demonstrated with field test in accordance with Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT and Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC. For plenum fan applications, the fan wheel shall meet or exceed guidelines in AMCA 801-92 for dynamic balancing requirements. Following fan assembly, the complete fan assembly balance shall be tested using an electronic balance analyzer with a tunable filter and stroboscope. Vibration measurements shall be taken on each motor bearing housing in the vertical, horizontal, and axial planes (5 total measurements, 2 each motor bearing and 1 axial).
- G. Fan Motor, Drive and Mounting Assembly:
  - Provide internally vibration isolated fan, motor and drive, mounted on a common integral
    bolted or welded structural steel base with adjustable motor slide rail with locking device.
    Provide vibration isolators and flexible duct connections at fan discharge to completely
    isolate fan assembly. Refer to Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC
    PIPING AND EQUIPMENT, for additional requirements.
  - 2. Fan Motor and Drive: Motors shall be premium energy efficient type, as mandated by the Energy Policy Act of 2005, with efficiencies as shown in the Specifications Section 23 05 12 (General Motor Requirements For HVAC and Steam Equipment), on drawings and suitable for use in variable frequency drive applications on AHUs where this type of drive is indicated. Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
  - 3. Fan drive and belts shall be factory mounted with final alignment and belt adjustment to be made by the Contractor after installation. Drive and belts shall be as specified in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION. Provide additional drive(s) if required during balancing, to achieve desired airflow.
- H. Filter Section: Refer to Section 23 40 00, HVAC AIR CLEANING DEVICES, for filter requirements.

Filters including one complete set for temporary use at site shall be provided independent
of the AHU. The AHU manufacturer shall install filter housings and racks in filter section
compatible with filters furnished. The AHU manufacturer shall be responsible for furnishing
temporary filters (pre-filters and after-filters, as shown on drawings) required for AHU
testing.

- Factory-fabricated filter section shall be of the same construction and finish as the AHU
  casing including filter racks and hinged double wall access doors. Filter housings shall be
  constructed in accordance with side service or holding frame housing requirements in
  Section 23 40 00. HVAC AIR CLEANING DEVICES.
- I. Coils: Coils shall be mounted on hot dipped galvanized steel supports to assure proper anchoring of coil and future maintenance. Coils shall be face or side removable for future replacement thru the access doors or removable panels. Each coil shall be removable without disturbing adjacent coil. Cooling coils and glycol-water exhaust heat recovery coils shall be designed and installed to insure no condensate carry over. Provide factory installed extended supply, return, drain, and vent piping connections. For air handling units serving surgical suites, provide copper fins for all coils. For all air handling units in high humidity areas, provide factory-coated coils for protection from corrosion by using multiple stage electro-deposition coating process. Refer to Drawings and Section 23 82 16, AIR COILS for additional coil requirements.
- J. UV Light Coil Disinfection Cleaners: Provide UV Light section with adequate length to allow effective disinfections of cooling coil. Provide High-Output UV lighting system specifically designed for HVAC application including:
  - 1. Fixture housings constructed of heavy gauge stainless steel. Reflectors are fabricated from bright annealed polished stainless steel, which has a reflectivity rate of 88% when exposed to short-wave UVC in the range of 254 nm. All components are in one integrated assembly to maximize serviceability. Water-tight lamp connections. Multiple fixtures to one power source. Hardwire all fixtures.

    2. Ballast: The solid-state electronic ballast, Class P rapid start with a power factor
  - minimum of 0.95. Photon production in air temperatures of 35° to 175° F. Minimum ballast start temperature is minus 20° F. Ballasts have an RFI EMI rating as defined by FCC part 18A for industrial / commercial applications in regards to suppression. Ballasts to be UL listed and suitable for use in air handling spaces.
  - 3. Lamps: UVC lamps to be high-output (800mA), T5 tube diameter, and constructed from hard glass tubing for maximum UV transmittance. Lamps to containing ≤8mg of mercury (Hg) and produce no ozone. Lamps to retain, minimum, 80% of initial output after 17,000 hours of use. Lamps sealed for moisture protection with a water-tight connections. Rated to produce 11.7µW/cm² per linear inch of lamp arc length at 1m in airstreams of 400FPM velocities at temperatures of 45° F.
- K. Electrical and Lighting: Wiring and equipment specifications shall conform to Division 26, ELECTRICAL.
  - 1. Vapor-proof lights using cast aluminum base style with glass globe and cast aluminum guard shall be installed in access sections for fan, mixing box, humidifier and any section over 300 mm (12 inch) wide. A switch shall control the lights in each compartment with pilot light mounted outside the respective compartment access door. Wiring between switches and lights shall be factory installed. All wiring shall run in neatly installed electrical conduits and terminate in a junction box for field connection to the building system. Provide single point 115 volt one phase connection at junction box.
  - 2. Install compatible 100 watt bulb in each light fixture.

- 3. Provide a convenience duplex receptacle next to the light switch.
- 4. Disconnect switch and power wiring: Provide factory or field mounted disconnect switch. Coordinate with Division 26, ELECTRICAL.

# PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install air handling unit in conformance with ARI 435.
- B. Assemble air handling unit components following manufacturer's instructions for handling, testing and operation. Repair damaged galvanized areas with paint in accordance with Military Spec. DOD-P-21035. Repair painted units by touch up of all scratches with finish paint material. Vacuum the interior of air handling units clean prior to operation.
- C. Leakage and test requirements for air handling units shall be the same as specified for ductwork in Specification Section 23 31 00, HVAC DUCTS AND CASINGS except leakage shall not exceed Leakage Class (C.) 12 listed in SMACNA HVAC Air Duct Leakage Test Manual when tested at 1.5 times the design static pressure. Repair casing air leaks that can be heard or felt during normal operation and to meet test requirements.
- D. Perform field mechanical (vibration) balancing in accordance with Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EOUIPMENT.
- E. Seal and/or fill all openings between the casing and AHU components and utility connections to prevent air leakage or bypass.

# 3.2 STARTUP SERVICES

- A. The air handling unit shall not be operated for any purpose, temporary or permanent, until ductwork is clean, filters are in place, bearings are lubricated and fan has been test run under observation.
- B. After the air handling unit is installed and tested, provide startup and operating instructions to VA personnel.
- C. An authorized factory representative should start up, test and certify the final installation and application specific calibration of control components. Items to be verified include fan performance over entire operating range, noise and vibration testing, verification of proper alignment, overall inspection of the installation, Owner/Operator training, etc.

- - - E N D - - -

# SECTION 23 74 13 PACKAGED, OUTDOOR, CENTRAL-STATION AIR-HANDLING UNITS

# PART 1 - GENERAL

# 1.1 DESCRIPTION

- A. Roof top air handling units including integral components specified herein
- B. Definitions: Roof Top Air Handling Unit(Roof Top Units, RTU): A factory fabricated assembly consisting of fan, coils, filters, and other necessary equipment to perform one or more of the following functions of circulating, cleaning, heating, cooling, humidifying, dehumidifying, and mixing of air. Design capacities of units shall be as scheduled on the drawings.

## 1.2 RELATED WORK

- A. General mechanical requirements and items, which are common to more than one section of Division 23: Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Sound and vibration requirements: Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.
- C. Piping and duct insulation: Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION.
- D. Piping and valves: Section 23 21 13, HYDRONIC PIPING and Section 23 22 13, STEAM AND CONDENSATE HEATING PIPING.
- E. Heating and cooling coils and pressure requirements: Section 23 82 16, AIR COILS.
- F. Return and exhaust fans: Section 23 34 00, HVAC FANS.
- G. Requirements for flexible duct connectors, sound attenuators and sound absorbing duct lining: Section 23 31 00, HVAC DUCTS AND CASINGS.
- H. Air filters and filters' efficiency: Section 23 40 00, HVAC AIR CLEANING DEVICES.
- I. HVAC controls: Section 23 09 23, DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC.
- J. Testing, adjusting and balancing of air and water flows: Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.
- K. Types of motors: Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC AND STEAM GENERATION EQUIPMENT.

# 1.3 QUALITY ASSURANCE

A. Refer to Article, Quality Assurance, in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.

- B. Certification: Certify roof top air-handling units in accordance with ARI 430.
- C. Heating, Cooling, and Air Handling Capacity and Performance Standards: ARI 430, ARI 410, ASHRAE 51, and AMCA 210.

# D. Performance Criteria:

- 1. The fan schedule indicates design cubic meter per minute (cubic feet per minute) and design static pressure. Scheduled fan motors, 375 watts (1/2 horsepower) and larger, are sized for the maximum of present or future design cubic meter per minute (cubic feet per minute) at 110 percent design static pressure, but not to exceed 187 Pa (3/4 inch water gage) additional pressure.
- 2. Fans and motors shall be capable of stable operation at design conditions cubic meters per minute (cubic feet per minute) and 110 percent pressure as stated above.
- 3. Lower than design pressure drop of approved individual components may allow use of a smaller fan motor and still provide the safety factor. When submitted as a deviation, a smaller motor may be approved in the interest of energy conservation. Such a deviation shall not qualify for any value engineering incentive claim or reward.
- 4. Select fan operating point to right hand side of peak static pressure point and near the peak of static efficiency.
- 5. Operating Limits: AMCA 99.
- E. Units shall be constructed by a manufacturer who has been manufacturing roof top units for at least five (5) years.
- F. Units shall be shipped in one (1) piece where possible and in shrink wrapping to protect the unit from dirt, moisture and /or road salt. Shipping splits can be provided as required for installation. Lifting lugs will be supplied on each side of the split to facilitate rigging and joining of segments.

# 1.4. SUBMITTALS:

- A. The contractor shall, in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, furnish a complete submission for all roof top units covered in the project. The submission shall include all information listed below. Partial and incomplete submissions shall be rejected without reviews.
- B. Manufacturer's Literature and Data:
  - Submittals for RTUs shall include fans, drives, motors, coils, humidifiers, filter housings, and all other related accessories. The contractor shall provide custom drawings showing total air handling unit assembly including dimensions, operating weight, access sections, flexible connections, door swings, controls penetrations, electrical disconnect, lights, duplex receptacles, switches, wiring, utility connection points, unit support system, vibration isolators, drain pan, pressure drops through each component (filter, coil etc) and rigging points. Submittal drawings of section or component only, will not be acceptable. Contractor

shall also submit performance data including performance test results, charts, curves or certified computer selection data; data sheets; fabrication and insulation details; and the number of pieces that each unit will have to be broken into to meet shipping and job site rigging requirements. This data shall be submitted in hard copies and in electronic version compatible to AutoCAD version used by the VA at the time of submission.

- Submit sound power levels in each octave band for fan and at entrance and discharge of RTUs at scheduled conditions. Include sound attenuator capacities and itemized internal component attenuation. Internal lining of supply air ductwork with sound absorbing material is not permitted. In absence of sound power ratings refer to Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.
- 3. Provide fan curves showing cubic meters per minute (cubic feet per minute), static pressure, efficiency, and horsepower for design point of operation and at maximum design cubic meters per minute (cubic feet per minute) and 110 percent of design static pressure.
- 4. Submit total fan static pressure, external static pressure, for RTU including total, inlet and discharge pressures, and itemized specified internal losses and unspecified internal losses. Refer to air handling unit schedule on drawings.
- C. Maintenance and operating manuals in accordance with Section 01 00 00, GENERAL REQUIREMENTS. Include instructions for lubrication, filter replacement, motor and drive replacement, spare part lists, and wiring diagrams.
- D. Submit written test procedures two weeks prior to factory testing. Submit written results of factory tests for approval prior to shipping.

# 1.5 APPLICABLE PUBLICATIONS

A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.

В.	430-89	Sound Rati Standard fo Coils Standard fo	on Institute (ARI ng of Ducted Air Movin or Forced-Circulation A or Central Station Air H f Certified Applied Air (	ng and Condition ir-Heating and A andling Units	ir-Cooling
C.	Air Moving and Co	_	ciation (AMCA): Methods of Testing Fa	ns for Rating	
D.	Anti-Friction Bea	_	er's Association, gs and Fatigue life for B	•	.):
Ε.	American Society Engineers (ASHRA) 51-01	Ε):	rigerating and Ai aboratory Methods of		
F.	American Society A653/653M-02	Steel Sheet	Materials (ASTM) , Zinc-Coated (Galvaniz lled) by the Hot-Dip Pro	zed) or Zinc-Iron	Alloy-Coated
1-528	A7-12-706	PACKAGED OUTDO	OR CENTRAL-STATION		23 74 13 - 3

	B117-97	Salt Spray (Fog) Testing
	C1071-00	Thermal and Acoustical Insulation (Mineral Fiber, Duct Lining
		Material)
	D1654-00	Standard Method for Evaluation of Painted or Coated
		Specimens Subjected to Corrosive Environments
	D1735-97	Water Resistance of Coatings Using Water Fog Apparatus
	D3359-95	Standard Test Methods for Measuring Adhesion by Tape Test
	E84-01	Surface Burning Characteristics of Building Materials
G.	Anti-Friction Bearing Ma	anufacturer's Association, Inc. (AFBMA):
	9-90	Load Ratings and Fatigue life for Ball Bearings
		(1117)
н.	Military Specifications	
	DOD-P-21035A-77	Paint, High Zinc Dust Content, Galvanizing Repair
I.	National Fire Protection	n Association (NFPA):
	90A-99	Installation of Air Conditioning and Ventilating Systems
I.	National Fire Protection	n Association (NFPA):

# PART 2 - PRODUCTS

## 2.1 ROOF TOP AIR HANDLING UNITS

## A. General:

- Roof top units (RTU) shall be entirely of double wall galvanized steel construction. Casing is specified in paragraph 2.1.C. Foil face lining is not an acceptable substitute for double wall construction. Galvanizing shall be hot dipped conforming to ASTM A525 and shall provide a minimum of 0.275 kg of zinc per square meter (0.90 oz. of zinc per square foot) (G90). Aluminum constructed units may be provided subject to VA approval and documentation that structural rigidity is equal or greater than the galvanized steel specified.
- 2. The contractor and the RTU manufacturer shall be responsible for insuring that the unit will not exceed the allocated space shown on the drawings, including required clearances for service and future overhaul or removal of unit components. All structural, piping, wiring, and ductwork alterations of units, which are dimensionally different than those specified, shall be the responsibility of the contractor at no additional cost to the government.
- 3. RTUs shall be fully assembled by the manufacturer in the factory in accordance with the arrangement shown on the drawings. The unit shall be assembled into the largest sections possible subject to shipping and rigging restrictions. The correct fit of all components and casing sections shall be verified in the factory for all units prior to shipment. All units shall be fully assembled, tested and then split to accommodate shipment and job site rigging. On units not shipped fully assembled, the manufacturer shall tag each section and include air flow direction to facilitate assembly at the job site. Lifting lugs or shipping skids shall be provided for each section to allow for field rigging and final placement of unit.
- 4. The RTU manufacturer shall provide the necessary gasketing, caulking, and all screws, nuts, and bolts required for assembly. The manufacturer shall provide a local representative at the job site to supervise the assembly and to assure the units are assembled to meet manufacturer's recommendations and requirements noted on the drawings. Provide documentation that this representative has provided this service on similar jobs to the Contracting Officer. If a local representative cannot be provided, the manufacturer shall provide a factory representative.

5. Gaskets: All door and casing and panel gaskets and gaskets between air handling unit components, if joined in the field, shall be high quality which seal air tight and retain their structural integrity and sealing capability after repeated assembly and disassembly of bolted panels and opening and closing of hinged components. Bolted sections may use a more permanent gasketing method provided they are not disassembled.

6. Structural Rigidity: Provide structural reinforcement when required by span or loading so that the deflection of the assembled structure shall not exceed 1/200 of the span based on a differential static pressure of 1991 Pa (8 inches water gage) or higher.

## B. Base:

- Provide a heavy duty steel base for supporting all RTU major components. Bases shall be constructed of wide-flange steel I-beams, channels, or minimum 125 mm (5 inch) high 3.5 mm (10 gauge) steel base rails. Welded or bolted cross members shall be provided as required for lateral stability. Contractor shall provide supplemental steel supports as shown on drawings.
- 2. RTUs shall be completely self supporting for installation on steel support pedestals.
- 3. The RTU bases not constructed of galvanized material shall be cleaned, primed with a rust inhibiting primer, and finished with rust inhibiting exterior enamel.

# C. Casing (including wall, floor and roof):

- 1. General: RTU casing shall be entirely double wall insulated panels, integral of or attached to a structural frame. Construction shall be such that removal of any panel shall not affect the structural integrity of the unit. Casing finished shall meet salt-spray test as specified in paragraph 2.1.C.10. All casing and panel sections shall be tightly butted and gasketed. No gaps of double wall construction will be allowed where panels bolt to air handling unit structural member. Structural members, not covered by the double wall panels, shall have equivalent insulated double wall construction.
- 2. Double wall galvanized steel panels, minimum 51 mm (2 inches) thick, constructed of minimum 1.3 mm (18 gauge) outer skin and 1.0 mm (20 gauge) solid or perforated inner skin. Perforated panels (inner skin) are not allowed in cooling coil sections, floors, door panels and where solid sheet is required to avoid air bypass.
- 3. Blank-Off: Provide where required to insure no air bypass between sections, through perforated panels or around coils or filters. Blank-Off shall be installed at each component of the air handling unit and also at the internal panels to prevent recirculation of the air through perforated panels. Seal any holes where bypass occurs.
- 4. Insulation: Insulation shall be encased in double-wall casing between exterior and interior panels such that no insulation can erode to the air stream. Insulation shall be 50 mm (2 inch) thick, 24 kg/m³ and (1.5 lb/ft³) density with a thermal conductivity R of approximately 13.8 W/m.K (8.0 BTU/hr-ft² °F). Units with less than 50 mm (2 inch) of insulation in any part of the walls, floor, roof or drain pan shall not be acceptable. The insulation shall comply with NFPA 90-A for the flame and smoke generation requirements. Also, refer to specification Section 23 07 11, HVAC, PLUMBING, AND BOILER PLANT INSULATION.
- 5. Condensation through metal connections between inner and outer panels shall be kept to an absolute minimum.
- 6. Casing panels shall be secured to the support structure with stainless steel or zinc-chromate plated screws and gaskets installed around the panel perimeter. Panels shall be completely removable to allow removal of fan, coils, and other internal components for future maintenance, repair, or modifications. Welded exterior panels are not acceptable.

7. Access Doors: Provide in each access section and where shown on drawings. Doors shall be a minimum of 50 mm (2 inches) thick with same double wall construction as the unit casing. Doors shall be a minimum of 600 mm (24 inches) wide, unless shown of different size on drawings, and shall be the full casing height up to a maximum of 1850 mm (6 feet). Doors shall be gasketed, hinged, and latched to provide an airtight seal. The access doors for fan section, mixing box, coil section shall include a minimum 150 mm x 150 mm (6 inch x 6 inch) double thickness, with air space between glass panes tightly sealed, reinforced glass or Plexiglas window in a gasketed frame.

- a. Hinges: Manufacturers standard, designed for door size, weight and pressure classifications. Hinges shall hold door completely rigid with minimum 45 kg (100 pound) weight hung on latch side of door.
- b. Latches: Non-corrosive alloy construction, with operating levers for positive cam action, operable from either inside or outside. Doors that do not open against unit operating pressure shall allow the door to ajar and then require approximately 0.785 radian (45 degrees) further movement of the handle for complete opening. Latch shall be capable of restraining explosive opening of door with a force not less than 1991 Pa (8 inches water gage).
- c. Gaskets: Neoprene, continuous around door, positioned for direct compression with no sliding action between the door and gasket. Secure with high quality mastic to eliminate possibility of gasket slipping or coming loose.
- 8. Provide sealed sleeves, metal or plastic escutcheons or grommets for penetrations through casing for power and temperature control wiring and pneumatic tubing. Coordinate with electrical and temperature control subcontractors for number and location of penetrations. Coordinate lights, switches, and duplex receptacles and disconnect switch location and mounting. All penetrations and equipment mounting may be provided in the factory or in the field. All field penetrations shall be performed neatly by drilling or saw cutting. No cutting by torches will be allowed. Neatly seal all openings airtight.
- 9. Roof of the unit shall be sloped to have a minimum pitch of 1/4 inch per foot. The roof shall overhang the side panels by a minimum of three inches to prevent precipitation drainage from streaming down the unit side panels.
- 10. Casing finished shall meet ASTM B117, 500-hour salt spray test, using 20 percent sodium chloride solution. Immediately after completion of the test, the coating shall show no sign of blistering, wrinkling, or cracking, no loss of adhesion, and the specimen shall show no sign of rust creepage beyond 1/8-inch on either side of scratch mark.
- D. Unit floor shall be level without offset space or gap and designed to support a minimum of 488 kg/square meter (100 pounds per square foot) distributed load without permanent deformation or crushing of internal insulation. Provide adequate structural base members beneath floor in service access sections to support typical service foot traffic and to prevent damage to unit floor or internal insulation. Unit floors in casing sections, which may contain water or condensate, shall be watertight with drain pan.
- E. Condensate Drain Pan: Drain pan shall be designed to extend entire length of cooling coils including headers and return bends. Depth of drain pan shall be at least 43 mm (1.7 inches) and shall handle all condensate without overflowing. Drain pan shall be double wall construction, 304 stainless steel and have a minimum of 50 mm (2 inch) insulation, and shall be sloped to drain. Drain pan shall be continuous

metal or welded watertight. No mastic sealing of joints exposed to water will be permitted. Drain pan shall be placed on top of casing floor or integrated into casing floor assembly. Drain pan shall be pitched in all directions to drain line.

- 1. An intermediate condensate drip pan shall be provided on stacked cooling coils and shall be constructed of 304 stainless steel with copper downspouts factory piped to main condensate pan. Use of intermediate condensate drain channel on upper casing of lower coil is permissible provided it is readily cleanable. Design of intermediate condensate drain shall prevent upper coil condensate from flowing across face of lower coil.
- 2. Drain pan shall be piped to the exterior of the unit. Drain pan shall be readily cleanable.
- 3. Installation, including frame, shall be designed and sealed to prevent blow-by.

# F. Fans Sections:

- Fans shall be minimum Class II construction, double width, double inlet centrifugal, air foil or backward inclined or forward curved type as indicated on drawings, factory balanced and rated in accordance with AMCA 210 or ASHRAE 51. Provide self-aligning, pillow block, regreasable ball-type bearings selected for a B(10) life of not less than 40,000 hours and an L(50) average fatigue life of 200,000 hours per AFBMA Standard 9. Extend bearing grease lines to motor and drive side of fan section. Fan shall be located in airstream to assure proper air flow.
- 2. Allowable vibration tolerances for fan shall not exceed a self-excited vibration maximum velocity of 0.005 m/s (0.20 inch per second) RMS, filter in, when measured with a vibration meter on bearing caps of machine in vertical, horizontal and axial directions or measured at equipment mounting feet if bearings are concealed. After field installation, compliance to this requirement shall be demonstrated with field test in accordance with Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT and Section 23 05 93, TESTING, ADJUSTING, AND BALANCING FOR HVAC.

# G. Fan Motor, Drive and Mounting Assembly:

- Provide internally vibration isolated fan, motor and drive, mounted on a common integral
  bolted or welded structural steel base with adjustable motor slide rail with locking device.
  Provide vibration isolators and flexible duct connections at fan discharge to completely
  isolate fan assembly. Refer to Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC
  PIPING AND EQUIPMENT, for additional requirements.
- 2. Fan Motor and Drive: Motors shall be energy efficient type with efficiencies as shown on drawings and suitable for use in variable frequency drive applications on RTUs where this type of drive is indicated. Refer to Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION, for additional motor and drive specifications. Where variable speed drives are required they shall be compatible with fan and motor. Refer to Specification Section 26 29 11, LOW-VOLTAGE MOTOR STARTERS.
- 3. Fan drive and belts shall be factory mounted with final alignment and belt adjustment to be made by the Contractor after installation. Drive and belts shall be as specified in Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION. Provide additional drive(s) if required during balancing, to achieve desired airflow.
- H. Filter Section: Refer to Section 23 40 00, HVAC AIR CLEANING DEVICES, for filter requirements.
  - 1. Filters including one complete set for temporary use at site shall be provided independent of the RTU. The RTU manufacturer shall install filter housings and racks in filter section

- compatible with filters furnished. The RTU manufacturer shall be responsible for furnishing temporary filters (pre-filters and after-filters, as shown on drawings) required for RTU testing.
- Factory-fabricated filter section shall be of the same construction and finish as the RTU
  casing including filter racks and hinged double wall access doors. Filter housings shall be
  constructed in accordance with side service or holding frame housing requirements in
  Section 23 40 00, HVAC AIR CLEANING DEVICES.
- I. Coils: Coils shall be mounted on hot dipped galvanized steel supports to assure proper anchoring of coil and future maintenance. Coils shall be face or side removable for future replacement thru the access doors or removable panels. Each coil shall be removable without disturbing adjacent coil. Cooling coils and glycol-water exhaust heat recovery coils shall be designed and installed to insure no condensate carry over. Provide factory installed extended supply, return, drain and vent piping connections. Refer to Drawings and Section 23 82 16, AIR COILS, for additional coil requirements.
  - 1. Water Coils, Including Glycol-Water.
- J. Discharge Section: Provide aerodynamically designed framed discharge openings or spun bellmouth fittings to minimize pressure loss.
- K. Electrical and Lighting: Wiring and equipment specifications shall conform to Division 26, ELECTRICAL.
  - 1. Vapor-proof lights using cast aluminum base style with glass globe and cast aluminum guard shall be installed in access sections for fan, mixing box and any section over 300mm (12 inch) wide. A switch shall control the lights in each compartment with pilot light mounted outside the respective compartment access door. Wiring between switches and lights shall be factory installed. All wiring shall run in neatly installed electrical conduits and terminate in a junction box for field connection to the building system. Provide single point 115 volt one phase connection at junction box.
  - 2. Install compatible 100 watt bulb in each light fixture.
  - 3. Provide a convenience duplex weatherproof receptacle next to the light switch.
  - 4. Disconnect switch and power wiring: Provide factory or field mounted disconnect switch. Coordinate with Division 26, ELECTRICAL.
- L. Condenser-Coil Fan: Propeller, mounted on shaft of permanently lubricated motor.
- M. Fan Motor: Comply with requirements in Section 23 05 12, GENERAL MOTOR REQUIREMENTS FOR HVAC and STEAM GENERATION EQUIPMENT.
- N. Supply-Air Refrigerant Coil: Aluminum-plate fins and seamless internally grooved copper tube in steel casing with equalizing-type vertical distributor. Polymer strip shall prevent all copper coil from contacting steel coil frame or condensate pan. Coil split shall be interlaced.
- O. Hot-Gas Reheat Refrigerant Coil: Aluminum-plate fins and seamless internally grooved copper tube in steel casing with equalizing-type vertical distributor. Polymer strip shall prevent copper coil from contacting steel coil frame or condensate pan.

- P. Refrigerant Circuit Components:
  - 1. Number of Independent Refrigerant Circuits: One.
  - 2. Compressor: Hermetic, scroll, mounted on vibration isolators; with internal overcurrent and high-temperature protection, internal pressure relief, and crankcase heater.
- Q. Refrigerant: R-410A unless otherwise indicated.
- R. Refrigeration Specialties:
  - 1. Expansion valve with replaceable thermostatic element.
  - 2. Refrigerant filter/dryer.
  - 3. Manual-reset high-pressure safety switch.
  - 4. Automatic-reset low-pressure safety switch.
  - 5. Minimum off-time relay.
  - 6. Automatic-reset compressor motor thermal overload.
  - 7. Brass service valves installed in compressor suction and liquid lines.
  - 8. Low-ambient kit high-pressure sensor.
  - 9. Hot-gas reheat solenoid valve with a replaceable magnetic coil.
  - 10. Hot-gas bypass solenoid valve with a replaceable magnetic coil.
  - 11. Four-way reversing valve with a replaceable magnetic coil, thermostatic expansion valves with bypass check valves, and a suction line accumulator.
- S. Air Filtration: Minimum arrestance according to ASHRAE 52.1, and MERV rating according to ASHRAE 52.2. as scheduled on drawings
- T. Outdoor- and Return-Air Mixing Dampers: Parallel- or opposed-blade galvanized-steel dampers mechanically fastened to cadmium plated for galvanized-steel operating rod in reinforced cabinet. Connect operating rods with common linkage and interconnect linkages so dampers operate simultaneously.
- U. Damper Motor: Modulating with adjustable minimum position.
- V. Relief-Air Damper: Gravity actuated or motorized, complying with ASHRAE/IESNA 90.1-2004, and having bird screen and hood.
- W. Electrical Power Connection: A single connection of power to unit with unit-mounted disconnect switch accessible from outside unit and control-circuit transformer with built-in overcurrent protection.
- X. Controls:
  - 1. Provide all components required to execute the sequence of operations indicated on drawings.
  - 2. Provide interface with BMS/DDC system via BACnet open protocol controller.
  - 3. Refrigerant Circuit Operation:
    - a. Occupied Periods: Cycle or stage compressors, and operate hot-gas bypass to match compressor output to cooling load to maintain discharge temperature. Cycle condenser fans to maintain maximum hot-gas pressure. Operate low-ambient control kit to maintain minimum hot-gas pressure.

4. Outdoor-Airflow Monitor: Accuracy maximum plus or minus 5 percent within 15 and 100 percent of total outdoor air. Monitor microprocessor shall adjust for temperature, and output shall range from 2- to 10-V dc or 4 to 20 mA.

- Y. UV Light Coil Disinfection Cleaners: Provide UV Light section with adequate length to allow effective disinfections of cooling coil. Provide High-Output UV lighting system specifically designed for HVAC application including:
  - Fixture housing constructed of heavy gauge stainless steel, which has reflectivity rate of 88% when exposed to short-wave UVC in the range of 254 nm. All components are in one integrated assembly to maximize serviceability. Water-tight lamp connections. Multiple fixtures to one power source. Hardwire all fixtures.
  - Ballast: The solid-state electronic ballast, Class P rapid start with a power factor minimum of 0.95. Photon production in air temperatures of 35 degrees to 175 degrees
     F. Minimum ballast start temperature is minus 20 degrees F. Ballasts have a RFI - EMI rating as defined by FCC part 18A for industrial commercial applications in regards to suppression. Ballast to be UL listed and suitable for use in air handling spaces
  - 3. Lamps: UVC lamps to be high-output (800mA). T5 tube diameter, and constructed from hard glass tubing for maximum UV transmittance. Lamps to contain ≤ 8mg of mercury (Hg) and produce no ozone. Lamps to retain a minimum of 80 % of initial output after 17,000 hours of use. Lamps sealed for moisture protect with a water-tight connection.

# Z. Accessories:

- 1. Duplex, 115-V, ground-fault-interrupter outlet with 15-A overcurrent protection. Include transformer if required. Outlet shall be energized even if the unit main disconnect is open.
- 2. Low-ambient kit using staged or variable-speed condenser fans for operation down to 1.7 deg C (35 deg F).
- 3. Filter differential pressure switch with sensor tubing on both sides of filter. Set for final filter pressure loss.
- 4. Hail guards of galvanized steel, painted to match casing.

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Install roof top unit in conformance with ARI 435.
- B. Assemble roof top unit components following manufacturer's instructions for handling, testing and operation. Repair damaged galvanized areas with paint in accordance with Military Spec. DOD-P-21035A. Repair painted units by touch up of all scratches with finish paint material. Vacuum clean interior of the units prior to operation.
- C. Leakage and test requirements for roof top units shall be the same as specified for ductwork in Specification Section 23 31 00, HVAC DUCTS AND CASINGS except leakage shall not exceed Leakage Class ( $C_{\rm L}$ ) 12 listed in SMACNA HVAC Air Duct Leakage Test Manual when tested at 1.5 times the design static pressure. Repair casing air leaks that can be heard or felt during normal operation and to meet test requirements.

D. Perform field mechanical (vibration) balancing in accordance with Section 23 05 41, NOISE AND VIBRATION CONTROL FOR HVAC PIPING AND EQUIPMENT.

 ${\tt E.}$  Seal and/or fill all openings between the casing and RTU components and utility connections to prevent air leakage or bypass.

# 3.2 STARTUP SERVICES

- A. A factory-trained service representative of the manufacturer shall supervise the unit startup and application specific calibration of control components.
- B. The air handling unit shall not be operated for any purpose, temporary or permanent, until ductwork is clean, filters are in place, bearings are lubricated and fan has been test run under observation.
- C. After the air handling unit is installed and tested, provide startup and operating instructions to VA personnel.

END OF SECTION 23 74 13



# SECTION 23 82 16 AIR COILS

# PART 1 - GENERAL

# 1.1 DESCRIPTION

Heating and cooling coils for air handling unit and duct applications.

## 1.2 RELATED WORK

- A. Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Section 23 73 13, OUTDOOR CENTRAL-STATION AIR-HANDLING UNITS.
- C. Reheat coils for VAV/CV terminals: Section 23 82 00, CONVECTION HEATING AND COOLING UNITS.

## 1.3 QUALITY ASSURANCE

- A. Refer to paragraph, QUALITY ASSURANCE, Section 23 05 11, COMMON WORK RESULTS FOR HVAC AND STEAM GENERATION.
- B. Unless specifically exempted by these specifications, heating and cooling coils shall be tested, rated, and certified in accordance with ARI Standard 410 and shall bear the ARI certification label.

# 1.4 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. Manufacturer's Literature and Data for Heating and Cooling Coils: Submit type, size, arrangements and performance details. Present application ratings in the form of tables, charts or curves.
- C. Provide installation, operating and maintenance instructions.
- D. Certification Compliance: Evidence of listing in current ARI Directory of Certified Applied Air Conditioning Products.
- E. Coils may be submitted with Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING UNITS or Section 23 74 13.

# 1.5 APPLICABLE PUBLICATIONS

- A. The publications listed below form a part of this specification to the extent referenced. The publications are referenced in the text by the basic designation only.
- B. Air Conditioning and Refrigeration Institute (ARI):
  Directory of Certified Applied Air Conditioning Products
  ARI 410-02 .......Forced-Circulation Air-Cooling Air-Heating Coils.
- C. American Society for Testing and Materials (ASTM): B75/75M-02 ......Seamless Copper Tube (Metric)

- D. National Fire Protection Association (NFPA): 70-05......National Electric Code
- E. National Electric Manufacturers Association (NEMA):

  250-03 ...... Enclosures for Electrical Equipment (1,000 Volts Maximum)
- F. Underwriters Laboratories, Inc. (UL): 1996-01..... Electric Duct Heaters

# PART 2 - PRODUCTS

# 2.1 HEATING AND COOLING COILS

- A. Conform to ASTM B75 and ARI 410.
- B. Tubes: Minimum 16 mm (0.625 inch) tube diameter; Seamless copper tubing.
- C. Fins: 0.1397 mm (0.0055 inch) aluminum or 0.1143 mm (0.0045 inch) copper mechanically bonded or soldered or helically wound around tubing. Provide copper fins for sprayed coil applications and reheat coils for Operating Rooms.
- D. Headers: Copper, welded steel or cast iron. Provide seamless copper tubing or resistance welded steel tube for volatile refrigerant coils.
- E. "U" Bends, Where Used: Machine die-formed, silver brazed to tube ends.
- F. Coil Casing: 1.6 mm (16 gage) galvanized steel with tube supports at 1200 mm (48 inch) maximum spacing. Construct casing to eliminate air bypass and moisture carry-over. Provide duct connection flanges.
- G. Pressures kPa (PSIG):

Pressure		Water Coil		Steam Coil		il	Refrigerant Coil		il	
Test	2	070	(300)	17	25	(250)		2070	(300)	
Working	1	380	(200)	5	20	(75)		1725	(250)	

- H. Protection: Unless protected by the coil casing, provide cardboard, plywood, or plastic material at the factory to protect tube and finned surfaces during shipping and construction activities.
- I. Vents and Drain: Coils that are not vented or drainable by the piping system shall have capped vent/drain connections extended through coil casing.
- J. Cooling Coil Condensate Drain Pan: Section 23 73 00, INDOOR CENTRAL-STATION AIR-HANDLING.

# 2.2 WATER COILS

A. Drainable Type (Self-Draining, Self-Venting); manufacturer standard:

I. Cooling, all types.

VA-528A7-12-706 AIR COILS 23 82 16 - 2

- 2. Heating or preheat.
- 3. Heat recovery

# PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Follow coil manufacturer's instructions for handling, cleaning, installation and piping connections.
- B. Comb fins, if damaged. Eliminate air bypass or leakage at coil sections.

# END OF SECTION 23 82 16

VA-528A7-12-706 AIR COILS 23 82 16 - 3



# SECTION 26 05 11 REQUIREMENTS FOR ELECTRICAL INSTALLATIONS

# PART 1 - GENERAL

# 1.1 DESCRIPTION

- A. This section applies to all sections of Divisions 26 and 28.
- B. Furnish and install electrical wiring, systems, equipment and accessories in accordance with the specifications and drawings. Capacities and ratings of motors, transformers, cable, switchboards, switchgear, panelboards, motor control centers and other items and arrangements for the specified items are shown on drawings.
- C. Electrical service entrance equipment and arrangements for temporary and permanent connections to the utility's system shall conform to the utility's requirements. Coordinate fuses, circuit breakers and relays with the utility's system, and obtain utility approval for sizes and settings of these devices.
- D. Wiring ampacities specified or shown on the drawings are based on copper conductors, with the conduit and raceways accordingly sized. Aluminum conductors are prohibited.

# 1.2 MINIMUM REQUIREMENTS

- A. References to the International Building Code (IBC), National Electrical Code (NEC), Underwriters Laboratories, Inc. (UL) and National Fire Protection Association (NFPA) are minimum installation requirement standards.
- B. Drawings and other specification sections shall govern in those instances where requirements are greater than those specified in the above standards.

# 1.3 TEST STANDARDS

A. All materials and equipment shall be listed, labeled or certified by a nationally recognized testing laboratory to meet Underwriters Laboratories, Inc., standards where test standards have been established. Equipment and materials which are not covered by UL Standards will be accepted provided equipment and material is listed, labeled, certified or otherwise determined to meet safety requirements of a nationally recognized testing laboratory. Equipment of a class which no nationally recognized testing laboratory accepts, certifies, lists, labels, or determines to be safe, will be considered if inspected or tested in accordance with national industrial standards, such as NEMA, or ANSI. Evidence of compliance shall include certified test reports and definitive shop drawings.

# B. Definitions:

1. Listed; Equipment, materials, or services included in a list published by an organization that is acceptable to the authority having jurisdiction and concerned with evaluation of products

- or services, that maintains periodic inspection of production or listed equipment or materials or periodic evaluation of services, and whose listing states that the equipment, material, or services either meets appropriate designated standards or has been tested and found suitable for a specified purpose.
- 2. Labeled; Equipment or materials to which has been attached a label, symbol, or other identifying mark of an organization that is acceptable to the authority having jurisdiction and concerned with product evaluation, that maintains periodic inspection of production of labeled equipment or materials, and by whose labeling the manufacturer indicates compliance with appropriate standards or performance in a specified manner.
- 3. Certified; equipment or product which:
  - a. Has been tested and found by a nationally recognized testing laboratory to meet nationally recognized standards or to be safe for use in a specified manner.
  - b. Production of equipment or product is periodically inspected by a nationally recognized testing laboratory.
  - c. Bears a label, tag, or other record of certification.
- 4. Nationally recognized testing laboratory; laboratory which is approved, in accordance with OSHA regulations, by the Secretary of Labor.

# 1.4 QUALIFICATIONS (PRODUCTS AND SERVICES)

- A. Manufacturers Qualifications: The manufacturer shall regularly and presently produce, as one of the manufacturer's principal products, the equipment and material specified for this project, and shall have manufactured the item for at least three years.
- B. Product Qualification:
  - 1. Manufacturer's product shall have been in satisfactory operation, on three installations of similar size and type as this project, for approximately three years.
  - 2. The Government reserves the right to require the Contractor to submit a list of installations where the products have been in operation before approval.
- C. Service Qualifications: There shall be a permanent service organization maintained or trained by the manufacturer which will render satisfactory service to this installation within eight hours of receipt of notification that service is needed. Submit name and address of service organizations.

# 1.5 APPLICABLE PUBLICATIONS

Applicable publications listed in all Sections of Division are the latest issue, unless otherwise noted.

# 1.6 MANUFACTURED PRODUCTS

- A. Materials and equipment furnished shall be of current production by manufacturers regularly engaged in the manufacture of such items, for which replacement parts shall be available.
- B. When more than one unit of the same class or type of equipment is required, such units shall be the product of a single manufacturer.
- C. Equipment Assemblies and Components:

- 1. Components of an assembled unit need not be products of the same manufacturer.
- 2. Manufacturers of equipment assemblies, which include components made by others, shall assume complete responsibility for the final assembled unit.
- 3. Components shall be compatible with each other and with the total assembly for the intended service.
- 4. Constituent parts which are similar shall be the product of a single manufacturer.
- D. Factory wiring shall be identified on the equipment being furnished and on all wiring diagrams.
- E. When Factory Testing Is Specified:
  - 1. The Government shall have the option of witnessing factory tests. The contractor shall notify the VA through the COR a minimum of 15 working days prior to the manufacturers making the factory tests.
  - 2. Four copies of certified test reports containing all test data shall be furnished to the COR prior to final inspection and not more than 90 days after completion of the tests.
  - 3. When equipment fails to meet factory test and re-inspection is required, the contractor shall be liable for all additional expenses, including expenses of the Government.

## 1.7 EQUIPMENT REQUIREMENTS

Where variations from the contract requirements are requested in accordance with Section 00 72 00, GENERAL CONDITIONS and Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, the connecting work and related components shall include, but not be limited to additions or changes to branch circuits, circuit protective devices, conduits, wire, feeders, controls, panels and installation methods.

# 1.8 EQUIPMENT PROTECTION

- A. Equipment and materials shall be protected during shipment and storage against physical damage, vermin, dirt, corrosive substances, fumes, moisture, cold and rain.
  - Store equipment indoors in clean dry space with uniform temperature to prevent condensation. Equipment shall include but not be limited to switchgear, switchboards, panelboards, transformers, motor control centers, motor controllers, uninterruptible power systems, enclosures, controllers, circuit protective devices, cables, wire, light fixtures, electronic equipment, and accessories.
  - During installation, equipment shall be protected against entry of foreign matter; and be vacuum-cleaned both inside and outside before testing and operating. Compressed air shall not be used to clean equipment. Remove loose packing and flammable materials from inside equipment.
  - 3. Damaged equipment shall be, as determined by the COR, placed in first class operating condition or be returned to the source of supply for repair or replacement.
  - 4. Painted surfaces shall be protected with factory installed removable heavy kraft paper, sheet vinyl or equal.
  - 5. Damaged paint on equipment and materials shall be refinished with the same quality of paint and workmanship as used by the manufacturer so repaired areas are not obvious.

## 1.9 WORK PERFORMANCE

A. All electrical work must comply with the requirements of NFPA 70 (NEC), NFPA 70B, NFPA 70E, OSHA Part 1910 subpart J, OSHA Part 1910 subpart S and OSHA Part 1910 subpart K in addition to other references required by contract.

- B. Job site safety and worker safety is the responsibility of the contractor.
- C. Electrical work shall be accomplished with all affected circuits or equipment de-energized. When an electrical outage cannot be accomplished in this manner for the required work, the following requirements are mandatory:
  - 1. Electricians must use full protective equipment (i.e., certified and tested insulating material to cover exposed energized electrical components, certified and tested insulated tools, etc.) while working on energized systems in accordance with NFPA 70E.
  - 2. Electricians must wear personal protective equipment while working on energized systems in accordance with NFPA 70E.
  - 3. Before initiating any work, a job specific work plan must be developed by the contractor with a peer review conducted and documented by the COR and Medical Center staff. The work plan must include procedures to be used on and near the live electrical equipment, barriers to be installed, safety equipment to be used and exit pathways.
  - 4. Work on energized circuits or equipment cannot begin until prior written approval is obtained from the COR.
- D. For work on existing stations, arrange, phase and perform work to assure electrical service for other buildings at all times. Refer to Article OPERATIONS AND STORAGE AREAS under Section 01 00 00, GENERAL REQUIREMENTS.
- E. New work shall be installed and connected to existing work neatly, safely and professionally. Disturbed or damaged work shall be replaced or repaired to its prior conditions, as required by Section 01 00 00, GENERAL REQUIREMENTS.
- F. Coordinate location of equipment and conduit with other trades to minimize interferences.

# 1.10 EQUIPMENT INSTALLATION AND REQUIREMENTS

- A. Equipment location shall be as close as practical to locations shown on the drawings.
- B. Working spaces shall not be less than specified in the NEC for all voltages specified.
- C. Inaccessible Equipment:
  - 1. Where the Government determines that the Contractor has installed equipment not conveniently accessible for operation and maintenance, the equipment shall be removed and reinstalled as directed at no additional cost to the Government.
  - 2. "Conveniently accessible" is defined as being capable of being reached quickly for operation, maintenance, or inspections without the use of ladders, or without climbing or crawling

> under or over obstacles such as, but not limited to, motors, pumps, belt guards, transformers, piping, ductwork, conduit and raceways.

## 1.11 EQUIPMENT IDENTIFICATION

- A. In addition to the requirements of the NEC, install an identification sign which clearly indicates information required for use and maintenance of items such as switchboards and switchgear, panelboards, cabinets, motor controllers (starters), fused and unfused safety switches, automatic transfer switches, separately enclosed circuit breakers, individual breakers and controllers in switchboards, switchgear and motor control assemblies, control devices and other significant equipment.
- B. Nameplates for Normal Power System equipment shall be laminated black phenolic resin with a white core with engraved lettering. Nameplates for Essential Electrical System (EES) equipment, as defined in the NEC, shall be laminated red phenolic resin with a white core with engraved lettering. Lettering shall be a minimum of 1/2 inch [12mm] high. Nameplates shall indicate equipment designation, rated bus amperage, voltage, number of phases, number of wires, and type of EES power branch as applicable. Secure nameplates with screws.
- C. Install adhesive arc flash warning labels on all equipment as required by NFPA 70E. Label shall indicate the arc hazard boundary (inches), working distance (inches), arc flash incident energy at the working distance (calories/ $cm^2$ ), required PPE category and description including the glove rating, voltage rating of the equipment, limited approach distance (inches), restricted approach distance (inches), prohibited approach distance (inches), equipment/bus name, date prepared, and manufacturer name and address.

### 1.12 SUBMITTALS

- A. Submit in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES.
- B. The Government's approval shall be obtained for all equipment and material before delivery to the job site. Delivery, storage or installation of equipment or material which has not had prior approval will not be permitted at the job site.
- C. All submittals shall include adequate descriptive literature, catalog cuts, shop drawings and other data necessary for the Government to ascertain that the proposed equipment and materials comply with specification requirements. Catalog cuts submitted for approval shall be legible and clearly identify equipment being submitted.
- D. Submittals for individual systems and equipment assemblies which consist of more than one item or component shall be made for the system or assembly as a whole. Partial submittals will not be considered for approval.
  - 1. Mark the submittals, "SUBMITTED UNDER SECTION\_
  - 2. Submittals shall be marked to show specification reference including the section and paragraph numbers.

- 3. Submit each section separately.
- E. The submittals shall include the following:
  - 1. Information that confirms compliance with contract requirements. Include the manufacturer's name, model or catalog numbers, catalog information, technical data sheets, shop drawings, pictures, nameplate data and test reports as required.
  - 2. Elementary and interconnection wiring diagrams for communication and signal systems, control systems and equipment assemblies. All terminal points and wiring shall be identified on wiring diagrams.
  - 3. Parts list which shall include those replacement parts recommended by the equipment manufacturer.
- F. Manuals: Submit in accordance with Section 01 00 00, GENERAL REQUIREMENTS.
  - 1. Maintenance and Operation Manuals: Submit as required for systems and equipment specified in the technical sections. Furnish four copies, bound in hardback binders, (manufacturer's standard binders) or an approved equivalent. Furnish one complete manual as specified in the technical section but in no case later than prior to performance of systems or equipment test, and furnish the remaining manuals prior to contract completion.
  - 2. Inscribe the following identification on the cover: the words "MAINTENANCE AND OPERATION MANUAL," the name and location of the system, equipment, building, name of Contractor, and contract number. Include in the manual the names, addresses, and telephone numbers of each subcontractor installing the system or equipment and the local representatives for the system or equipment.
  - 3. Provide a "Table of Contents" and assemble the manual to conform to the table of contents, with tab sheets placed before instructions covering the subject. The instructions shall be legible and easily read, with large sheets of drawings folded in.
  - 4. The manuals shall include:
    - a. Internal and interconnecting wiring and control diagrams with data to explain detailed operation and control of the equipment.
    - b. A control sequence describing start-up, operation, and shutdown.
    - c. Description of the function of each principal item of equipment.
    - d. Installation instructions.
    - e. Safety precautions for operation and maintenance.
    - f. Diagrams and illustrations.
    - g. Periodic maintenance and testing procedures and frequencies, including replacement parts numbers and replacement frequencies.
    - h. Performance data.
    - Pictorial "exploded" parts list with part numbers. Emphasis shall be placed on the use of special tools and instruments. The list shall indicate sources of supply, recommended spare parts, and name of servicing organization.
    - List of factory approved or qualified permanent servicing organizations for equipment repair and periodic testing and maintenance, including addresses and factory certification qualifications.
- G. Approvals will be based on complete submission of manuals together with shop drawings.

H. After approval and prior to installation, furnish the COR with one sample of each of the following:

- 1. A 300 mm (12 inch) length of each type and size of wire and cable along with the tag from the coils of reels from which the samples were taken.
- 2. Each type of conduit coupling, bushing and termination fitting.
- 3. Conduit hangers, clamps and supports.
- 4. Duct sealing compound.
- 5. Each type of receptacle, outlet box, manual motor starter, device wall plate, engraved nameplate, wire and cable splicing and terminating material, and branch circuit single pole molded case circuit breaker.

#### 1.13 SINGULAR NUMBER

Where any device or part of equipment is referred to in these specifications in the singular number (e.g., "the switch"), this reference shall be deemed to apply to as many such devices as are required to complete the installation as shown on the drawings.

### 1.14 ACCEPTANCE CHECKS AND TESTS

The contractor shall furnish the instruments, materials and labor for field tests.

#### 1.15 TRAINING

- A. Training shall be provided in accordance with Article 1.25, INSTRUCTIONS, of Section 01 00 00, GENERAL REQUIREMENTS.
- B. Training shall be provided for the particular equipment or system as required in each associated specification.
- C. A training schedule shall be developed and submitted by the contractor and approved by the COR at least 30 days prior to the planned training.

END OF SECTION 26 05 11



# SECTION 26 05 21 LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW)

#### PART 1 - GENERAL

#### 1.1 DESCRIPTION

This section specifies the furnishing, installation, and connection of the low voltage power and lighting wiring.

#### 1.2 RELATED WORK

- A. Section 07 84 00, FIRESTOPPING: Sealing around penetrations to maintain the integrity of fire-rated construction.
- B. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements that are common to more than one section.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground fault currents.
- D. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits for cables and wiring.

### 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

## 1.4 FACTORY TESTS

Low voltage cables shall be thoroughly tested at the factory per NEMA WC-70 to ensure that there are no electrical defects. Factory tests shall be certified.

## 1.5 SUBMITTALS

In accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, submit the following:

- 1. Manufacturer's Literature and Data: Showing each cable type and rating.
- 2. Certifications: Two weeks prior to the final inspection, submit four copies of the following certifications to the COR:
  - a. Certification by the manufacturer that the materials conform to the requirements of the drawings and specifications.
  - b. Certification by the contractor that the materials have been properly installed, connected, and tested.

## 1.6 APPLICABLE PUBLICATIONS

A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are reference in the text by designation only.

В.	American Society of Test	ting Material (ASTM): .Standard Specification for Vinyl Chloride Plastic Pressure- Sensitive Electrical Insulating Tape
C.	National Fire Protection 70-08	,
D.		ufacturers Association (NEMA): . Power Cables Rated 2000 Volts or Less for the Distribution of Electrical Energy
E.	83-08	. Thermoset-Insulated Wires and Cables . Thermoplastic-Insulated Wires and Cables . Electrical Grounding and Bonding Equipment . Wire Connectors . Splicing Wire Connectors . Sealed Wire Connector Systems . Equipment Wiring Terminals for Use with Aluminum and/or Copper Conductors . Thermoplastic-Insulated Underground Feeder and Branch Circuit Cable . Conduit, Tubing, and Cable Fittings
	1479-03	. Fire Tests of Through-Penetration Fire Stops

## PART 2 - PRODUCTS

## 2.1 CONDUCTORS AND CABLES

- A. Conductors and cables shall be in accordance with NEMA WC-70 and as specified herein.
- B. Single Conductor:
  - 1. Shall be annealed copper.
  - 2. Shall be stranded for sizes No. 8 AWG and larger, solid for sizes No. 10 AWG and smaller.
  - 3. Shall be minimum size No. 12 AWG, except where smaller sizes are allowed herein.
- C. Insulation:
  - 1. XHHW-2 or THHN-THWN shall be in accordance with NEMA WC-70, UL 44, and UL 83.
- D. Color Code:
  - 1. Secondary service feeder and branch circuit conductors shall be color-coded as follows

208/120 volt	Phase	480/277 volt
Black	A	Brown
Red	В	Orange
Blue	C	Yellow
White	Neutral	Gray *
* or white with	colored (other	than green) tracer.

a. Lighting circuit "switch legs" and 3-way switch "traveling wires" shall have color coding that is unique and distinct (e.g., pink and purple) from the color coding indicated above. The unique color codes shall be solid and in accordance with the NEC. Coordinate color coding in the field with the COR.

- 2. Use solid color insulation or solid color coating for No. 12 AWG and No. 10 AWG branch circuit phase, neutral, and ground conductors.
- 3. Conductors No. 8 AWG and larger shall be color-coded using one of the following methods:
  - a. Solid color insulation or solid color coating.
  - b. Stripes, bands, or hash marks of color specified above.
  - c. Color as specified using 0.75 in [19 mm] wide tape. Apply tape in half-overlapping turns for a minimum of 3 in [75 mm] for terminal points, and in junction boxes and pull-boxes. Apply the last two laps of tape with no tension to prevent possible unwinding. Where cable markings are covered by tape, apply tags to cable, stating size and insulation type.
- 4. For modifications and additions to existing wiring systems, color coding shall conform to the existing wiring system.

### 2.2 SPLICES AND JOINTS

- A. In accordance with UL 486A, C, D, E, and NEC.
- B. Aboveground Circuits (No. 10 AWG and smaller):
  - 1. Connectors: Solderless, screw-on, reusable pressure cable type, rated 600 V, 220° F [105° C], with integral insulation, approved for copper conductors.
  - 2. The integral insulator shall have a skirt to completely cover the stripped wires.
  - 3. The number, size, and combination of conductors, as listed on the manufacturer's packaging, shall be strictly followed.
- C. Aboveground Circuits (No. 8 AWG and larger):
  - 1. Connectors shall be indent, hex screw, or bolt clamp-type of high conductivity and corrosion-resistant material, listed for use with copper conductors.
  - 2. Field-installed compression connectors for cable sizes 250 kcmil and larger shall have not fewer than two clamping elements or compression indents per wire.
  - 3. Insulate splices and joints with materials approved for the particular use, location, voltage, and temperature. Splice and joint insulation level shall be not less than the insulation level of the conductors being joined.
  - 4. Plastic electrical insulating tape: Per ASTM D2304, flame-retardant, cold and weather

# 2.3 CONTROL WIRING

- A. Unless otherwise specified elsewhere in these specifications, control wiring shall be as specified for power and lighting wiring, except that the minimum size shall be not less than No. 14 AWG.
- B. Control wiring shall be large enough such that the voltage drop under in-rush conditions does not adversely affect operation of the controls.

## 2.4 WIRE LUBRICATING COMPOUND

A. Lubricating compound shall be suitable for the wire insulation and conduit, and shall not harden or become adhesive.

### PART 3 - EXECUTION

#### 3.1 GENERAL

- A. Install in accordance with the NEC, and as specified.
- B. Install all wiring in raceway systems.
- C. Splice cables and wires only in outlet boxes, junction boxes or pull-boxes.
- D. Wires of different systems (e.g., 120 V, 277 V) shall not be installed in the same conduit or junction box system.
- E. Install cable supports for all vertical feeders in accordance with the NEC. Provide split wedge type which firmly clamps each individual cable and tightens due to cable weight.
- F. For panel boards, cabinets, wireways, switches, and equipment assemblies, neatly form, train, and tie the cables in individual circuits.
- G. Wire Pulling:
  - 1. Provide installation equipment that will prevent the cutting or abrasion of insulation during pulling of cables. Use lubricants approved for the cable.
  - 2. Use nonmetallic ropes for pulling feeders.
  - 3. Attach pulling lines for feeders by means of either woven basket grips or pulling eyes attached directly to the conductors, as approved by the COR.
  - 4. All cables in a single conduit shall be pulled simultaneously.
  - 5. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- H. No more than three single-phase branch circuits shall be installed in any one conduit.

## 3.2 SPLICE INSTALLATION

- A. Splices and terminations shall be mechanically and electrically secure.
- B. Tighten electrical connectors and terminals according to manufacturer's published torque values.
- C. Where the Government determines that unsatisfactory splices or terminations have been installed, remove the devices and install approved devices at no additional cost to the Government.

## 3.3 FEEDER IDENTIFICATION

A. In each interior pull-box and junction box, install metal tags on all circuit cables and wires to clearly designate their circuit identification and voltage. The tags shall be the embossed brass type, 1.5 in [40 mm] in diameter and 40 mils thick. Attach tags with plastic ties.

# 3.4 EXISTING WIRING

Unless specifically indicated on the plans, existing wiring shall not be reused for a new installation.

### 3.5 CONTROL AND SIGNAL WIRING INSTALLATION

- A. Unless otherwise specified in other sections, install wiring and connect to equipment/devices to perform the required functions as shown and specified.
- B. Except where otherwise required, install a separate power supply circuit for each system so that malfunctions in any system will not affect other systems.
- C. Where separate power supply circuits are not shown, connect the systems to the nearest panel boards of suitable voltages, which are intended to supply such systems and have suitable spare circuit breakers or space for installation.

### 3.6 CONTROL AND SIGNAL SYSTEM WIRING IDENTIFICATION

- A. Install a permanent wire marker on each wire at each termination.
- B. Identifying numbers and letters on the wire markers shall correspond to those on the wiring diagrams used for installing the systems.
- C. Wire markers shall retain their markings after cleaning.

## 3.7 ACCEPTANCE CHECKS AND TESTS

- A. Feeders and branch circuits shall have their insulation tested after installation and before connection to utilization devices, such as fixtures, motors, or appliances. Test each conductor with respect to adjacent conductors and to ground. Existing conductors to be reused shall also be tested.
- B. Applied voltage shall be 500VDC for 300-volt rated cable, and 1000VDC for 600-volt rated cable. Apply test for one minute or until reading is constant for 15 seconds, whichever is longer. Minimum insulation resistance values shall not be less than 25 megohms for 300-volt rated cable and 100 megohms for 600-volt rated cable.
- C. Perform phase rotation test on all three-phase circuits.
- D. The contractor shall furnish the instruments, materials, and labor for all tests.

## END OF SECTION 26 05 21



# SECTION 26 05 26 GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

### PART 1 - GENERAL

#### 1.1 DESCRIPTION

- A. This section specifies the general grounding and bonding requirements for electrical equipment and operations to provide a low impedance path for possible ground fault currents.
- B. "Grounding electrode system" refers to all electrodes required by NEC, as well as made, supplementary, and lightning protection system grounding electrodes.
- C. The terms "connect" and "bond" are used interchangeably in this specification and have the same meaning.

### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- B. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW): Low Voltage power and lighting wiring.

# 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

## 1.4 SUBMITTALS

- A. Submit in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- B. Shop Drawings:
  - 1. Clearly present enough information to determine compliance with drawings and specifications.
  - 2. Include the location of system grounding electrode connections and the routing of aboveground and underground grounding electrode conductors.
- C. Test Reports: Provide certified test reports of ground resistance.
- D. Certifications: Two weeks prior to final inspection, submit four copies of the following to the COR:
  - 1. Certification that the materials and installation are in accordance with the drawings and specifications.
  - 2. Certification by the contractor that the complete installation has been properly installed and tested.

03/14/2012 PHASE 2

### 1.5 APPLICABLE PUBLICATIONS

Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.

A.	American	Society	for	Testing	and	Materials	(ASTM):	
	<b>₽1</b> _07			Stand	ard Cr	accification fo	r Hard-Drawn (	`or

B1-07	Standard Specification for Hard-Drawn Copper Wire
B3-07	Standard Specification for Soft or Annealed Copper Wire
B8-04	Standard Specification for Concentric-Lay-Stranded Copper
	Conductors, Hard, Medium-Hard, or Soft

- B. Institute of Electrical and Electronics Engineers, Inc. (IEEE): 81-1983 ...... IEEE Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System C2-07 ...... National Electrical Safety Code
- C. National Fire Protection Association (NFPA): 70-08 ...... National Electrical Code (NEC) 99-2005 ...... Health Care Facilities
- D. Underwriters Laboratories, Inc. (UL):

44-05	Thermoset-Insulated Wires and Cables
83-08	Thermoplastic-Insulated Wires and Cables
467-07	Grounding and Bonding Equipment
486A-486B-03	Wire Connectors

## PART 2 - PRODUCTS

# 2.1 GROUNDING AND BONDING CONDUCTORS

- A. Equipment grounding conductors shall be UL 44 or UL 83 insulated stranded copper, except that sizes No. 10 AWG [6 mm²] and smaller shall be solid copper. Insulation color shall be continuous green for all equipment grounding conductors, except that wire sizes No. 4 AWG [25 mm<sup>2</sup>] and larger shall be identified per NEC.
- B. Bonding conductors shall be ASTM B8 bare stranded copper, except that sizes No. 10 AWG [6 mm²] and smaller shall be ASTM B1 solid bare copper wire.
- C. Conductor sizes shall not be less than shown on the drawings, or not less than required by the NEC, whichever is greater.

## 2.2 GROUND CONNECTIONS

- A. Above Grade:
  - 1. Bonding Jumpers: Compression-type connectors, using zinc-plated fasteners and external tooth lockwashers.
  - 2. Connection to Building Steel: Exothermic-welded type connectors.
  - 3. Ground Busbars: Two-hole compression type lugs, using tin-plated copper or copper alloy bolts and nuts.

#### 2.3 GROUND TERMINAL BLOCKS

At any equipment mounting location (e.g., backboards and hinged cover enclosures) where rack-type ground bars cannot be mounted, provide screw lug-type terminal blocks.

## PART 3 - EXECUTION

### 3.1 GENERAL

- ${\tt A.}$  Ground in accordance with the NEC, as shown on drawings, and as specified herein.
- B. Equipment Grounding: Metallic structures, including ductwork and building steel, enclosures, raceways, junction boxes, outlet boxes, cabinets, machine frames, and other conductive items in close proximity with electrical circuits, shall be bonded and grounded.

## 3.2 RACEWAY

- A. Conduit Systems:
  - 1. Ground all metallic conduit systems. All metallic conduit systems shall contain an equipment grounding conductor.
  - 2. Conduit that only contains a grounding conductor, and is provided for its mechanical protection, shall be bonded to that conductor at the entrance and exit from the conduit.
  - 3. Metallic conduits which terminate without mechanical connection to an electrical equipment housing by means of locknut and bushings or adapters, shall be provided with grounding bushings. Connect bushings with a bare grounding conductor to the equipment ground bus.
- B. Feeders and Branch Circuits: Install equipment grounding conductors with all feeders and power and lighting branch circuits.
- C. Boxes, Cabinets, Enclosures, and Panelboards:
  - 1. Bond the equipment grounding conductor to each pullbox, junction box, outlet box, device box, cabinets, and other enclosures through which the conductor passes.
  - 2. Provide lugs in each box and enclosure for equipment grounding conductor termination.
- D. Receptacles shall not be grounded through their mounting screws. Ground receptacles with a jumper from the receptacle green ground terminal to the device box ground screw and a jumper to the branch circuit equipment grounding conductor.
- E. Ground lighting fixtures to the equipment grounding conductor of the wiring system when the green ground is provided; otherwise, ground the fixtures through the conduit systems. Fixtures connected with flexible conduit shall have a green ground wire included with the power wires from the fixture through the flexible conduit to the first outlet box.
- F. Fixed electrical appliances and equipment shall be provided with a ground lug for termination of the equipment grounding conductor.

## 3.3 CORROSION INHIBITORS

When making ground and ground bonding connections, apply a corrosion inhibitor to all contact surfaces. Use corrosion inhibitor appropriate for protecting a connection between the metals used.

#### 3.4 CONDUCTIVE PIPING

A. Bond all conductive interior piping systems to the grounding electrode system. Bonding connections shall be made as close as practical to the equipment ground bus.

### 3.5 GROUND RESISTANCE

- A. Grounding system resistance to ground shall not exceed 5 ohms. Make any modifications or additions to the grounding electrode system necessary for compliance without additional cost to the Government. Final tests shall ensure that this requirement is met.
- B. Resistance of the grounding electrode system shall be measured using a four-terminal fall-of-potential method as defined in IEEE 81. Ground resistance measurements shall be made before the electrical distribution system is energized and shall be made in normally dry conditions not fewer than 48 hours after the last rainfall. Resistance measurements of separate grounding electrode systems shall be made before the systems are bonded together below grade. The combined resistance of separate systems may be used to meet the required resistance, but the specified number of electrodes must still be provided.

**END OF SECTION 26 05 26** 

# SECTION 26 05 33 RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS

### PART 1 - GENERAL

### 1.1 DESCRIPTION

- A. This section specifies the furnishing, installation, and connection of conduit, fittings, and boxes, to form complete, coordinated, grounded raceway systems. Raceways are required for all wiring unless shown or specified otherwise.
- B. Definitions: The term conduit, as used in this specification, shall mean any or all of the raceway types specified.

#### 1.2 RELATED WORK

- A. Section 07 84 00, FIRESTOPPING: Sealing around penetrations to maintain the integrity of fire rated construction.
- B. Section 07 92 00, JOINT SEALANTS: Sealing around conduit penetrations through the building envelope to prevent moisture migration into the building.
- C. Section 09 91 00, PAINTING: Identification and painting of conduit and other devices.
- D. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- E. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS:
  Requirements for personnel safety and to provide a low impedance path
  for possible ground fault currents.

# 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

# 1.4 SUBMITTALS

In accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, submit the following:

- A. Manufacturer's Literature and Data: Showing each cable type and rating. The specific item proposed and its area of application shall be identified on the catalog cuts.
- B. Certifications:
  - 1. Two weeks prior to the final inspection, submit four copies of the following certifications to the COR:
    - a. Certification by the manufacturer that the material conforms to the requirements of the drawings and specifications.
    - b. Certification by the contractor that the material has been properly installed.

#### 1.5 APPLICABLE PUBLICATIONS

A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.

В.	American	National	Standards	Institute	(ANSI):
	C80.1-05		Elect	rical Rigid Ste	el Conduit
	C80.3-05		Stee	l Electrical Me	etal Tubing

- C. National Fire Protection Association (NFPA): 70-08.....National Electrical Code (NEC)
- D. Underwriters Laboratories, Inc. (UL):

1-05	. Flexible Metal Conduit
6-07	. Electrical Rigid Metal Conduit - Steel
50-95	. Enclosures for Electrical Equipment
360-093	Liquid-Tight Flexible Steel Conduit
467-07	. Grounding and Bonding Equipment
514A-04	. Metallic Outlet Boxes
514B-04	. Conduit, Tubing, and Cable Fittings
797-07	. Electrical Metallic Tubing

E. National Electrical Manufacturers Association (NEMA):
FB1-07 ......Fittings, Cast Metal Boxes and Conduit Bodies for Conduit,
Electrical Metallic Tubing and Cable

## PART 2 - PRODUCTS

## 2.1 MATERIAL

A. Conduit Size: In accordance with the NEC, but not less than 0.5 in [13 mm] unless otherwise shown. Where permitted by the NEC, 0.5 in [13 mm] flexible conduit may be used for tap connections to lighting fixtures.

### B. Conduit:

- 1. Rigid steel: Shall conform to UL 6 and ANSI C80.1.
- 2. Electrical metallic tubing (EMT): Shall conform to UL 797 and ANSI C80.3. Maximum size not to exceed 4 in [105 mm] and shall be permitted only with cable rated 600 V or less.
- 3. Flexible galvanized steel conduit: Shall conform to UL 1.
- 4. Liquid-tight flexible metal conduit: Shall conform to UL 360.

# C. Conduit Fittings:

- 1. Rigid steel conduit fittings:
  - a. Fittings shall meet the requirements of UL 514B and NEMA FB1.
  - b. Standard threaded couplings, locknuts, bushings, conduit bodies, and elbows: Only steel or malleable iron materials are acceptable. Integral retractable type IMC couplings are also acceptable.
  - c. Locknuts: Bonding type with sharp edges for digging into the metal wall of an enclosure.

d. Bushings: Metallic insulating type, consisting of an insulating insert, molded or locked into the metallic body of the fitting. Bushings made entirely of metal or nonmetallic material are not permitted.

- e. Erickson (union-type) and set screw type couplings: Approved for use in concrete are permitted for use to complete a conduit run where conduit is installed in concrete. Use set screws of case-hardened steel with hex head and cup point to firmly seat in conduit wall for positive ground. Tightening of set screws with pliers is prohibited.
- f. Sealing fittings: Threaded cast iron type. Use continuous drain-type sealing fittings to prevent passage of water vapor. In concealed work, install fittings in flush steel boxes with blank cover plates having the same finishes as that of other electrical plates in the room.
- 2. Electrical metallic tubing fittings:
  - a. Fittings and conduit bodies shall meet the requirements of UL 514B, ANSI C80.3, and NEMA FB1.
  - b. Only steel or malleable iron materials are acceptable.
  - c. Compression couplings and connectors: Concrete-tight and rain-tight, with connectors having insulated throats.
  - d. Indent-type connectors or couplings are prohibited.
  - e. Die-cast or pressure-cast zinc-alloy fittings or fittings made of "pot metal" are prohibited.
- 3. Flexible steel conduit fittings:
  - a. Conform to UL 514B. Only steel or malleable iron materials are acceptable.
  - b. Clamp-type, with insulated throat.
- 4. Liquid-tight flexible metal conduit fittings:
  - a. Fittings shall meet the requirements of UL 514B and NEMA FB1.
  - b. Only steel or malleable iron materials are acceptable.
  - c. Fittings must incorporate a threaded grounding cone, a steel or plastic compression ring, and a gland for tightening. Connectors shall have insulated throats.
- 5. Expansion and deflection couplings:
  - a. Conform to UL 467 and UL 514B.
  - b. Accommodate a 0.75 in [19 mm] deflection, expansion, or contraction in any direction, and allow 30 degree angular deflections.
  - c. Include internal flexible metal braid, sized to guarantee conduit ground continuity and a low-impedance path for fault currents, in accordance with UL 467 and the NEC tables for equipment grounding conductors.
  - d. Jacket: Flexible, corrosion-resistant, watertight, moisture and heat-resistant molded rubber material with stainless steel jacket clamps.

## D. Conduit Supports:

- 1. Parts and hardware: Zinc-coat or provide equivalent corrosion protection.
- 2. Individual Conduit Hangers: Designed for the purpose, having a pre-assembled closure bolt and nut, and provisions for receiving a hanger rod.
- 3. Multiple conduit (trapeze) hangers: Not less than 1.5 x 1.5 in [38 mm x 38 mm], 12-gauge steel, cold-formed, lipped channels; with not less than 0.375 in [9 mm] diameter steel hanger rods.
- 4. Solid Masonry and Concrete Anchors: Self-drilling expansion shields, or machine bolt expansion.

- E. Outlet, Junction, and Pull Boxes:
  - 1. UL-50 and UL-514A.
  - 2. Cast metal where required by the NEC or shown, and equipped with rustproof boxes.
  - 3. Sheet metal boxes: Galvanized steel, except where otherwise shown.
  - 4. Surface-mounted wall or ceiling boxes shall be installed with surface-style flat or raised covers.

### PART 3 - EXECUTION

## 3.1 PENETRATIONS

- A. Cutting or Holes:
  - 1. Cut holes in advance where they should be placed in the structural elements, such as ribs or beams. Obtain the approval of the COR prior to drilling through structural elements.
  - Cut holes through concrete and masonry in new and existing structures with a diamond core
    drill or concrete saw. Pneumatic hammers, impact electric, hand, or manual hammer-type
    drills are not allowed, except where permitted by the COR as required by limited working
    space.
- B. Firestop: Where conduits, wireways, and other electrical raceways pass through fire partitions, fire walls, smoke partitions, or floors, install a fire stop that provides an effective barrier against the spread of fire, smoke and gases as specified in Section 07 84 00, FIRESTOPPING.
- C. Waterproofing: At floor and exterior wall conduit penetrations, completely seal clearances around the conduit and make watertight, as specified in Section 07 92 00, JOINT SEALANTS.

## 3.2 INSTALLATION, GENERAL

- A. In accordance with UL, NEC, as shown, and as specified herein.
- B. Install conduit as follows:
  - 1. In complete mechanically and electrically continuous runs before pulling in cables or wires.
  - 2. Flattened, dented, or deformed conduit is not permitted. Remove and replace the damaged conduits with new undamaged material.
  - 3. Assure conduit installation does not encroach into the ceiling height head room, walkways, or doorways.
  - 4. Cut square, ream, remove burrs, and draw up tight.
  - 5. Independently support conduit at 8 ft [2.4 M] on centers. Do not use other supports, i.e., suspended ceilings, suspended ceiling supporting members, lighting fixtures, conduits, mechanical piping, or mechanical ducts.
  - 6. Support within 12 in [300 mm] of changes of direction, and within 12 in [300 mm] of each enclosure to which connected.
  - 7. Close ends of empty conduit with plugs or caps at the rough-in stage until wires are pulled in, to prevent entry of debris.
  - 8. Secure conduits to cabinets, junction boxes, pull-boxes, and outlet boxes with bonding type locknuts. For rigid and IMC conduit installations, provide a locknut on the inside of the enclosure, made up wrench tight. Do not make conduit connections to junction box covers.
  - 9. Conduit bodies shall only be used for changes in direction, and shall not contain splices.

#### C. Conduit Bends:

- 1. Make bends with standard conduit bending machines.
- 2. Conduit hickey may be used for slight offsets and for straightening stubbed out conduits.
- 3. Bending of conduits with a pipe tee or vise is prohibited.

### D. Layout and Homeruns:

- 1. Install conduit with wiring, including homeruns, as shown on drawings.
- 2. Deviations: Make only where necessary to avoid interferences and only after drawings showing the proposed deviations have been submitted approved by the COR.

### 3.3 EXPOSED WORK INSTALLATION

- A. Unless otherwise indicated on the drawings, exposed conduit is only permitted in mechanical and electrical rooms.
- B. Conduit for Conductors 600 V and Below: Rigid steel or EMT. Mixing different types of conduits indiscriminately in the system is prohibited.
- C. Align and run conduit parallel or perpendicular to the building lines.
- D. Install horizontal runs close to the ceiling or beams and secure with conduit straps.
- E. Support horizontal or vertical runs at not over 8 ft [2.4 M] intervals.

## F. Painting:

- 1. Paint exposed conduit as specified in Section 09 91 00, PAINTING.
- 2. Paint all conduits containing cables rated over 600 V safety orange. Refer to Section 09 91 00, PAINTING for preparation, paint type, and exact color. In addition, paint legends, using 2 in [50 mm] high black numerals and letters, showing the cable voltage rating. Provide legends where conduits pass through walls and floors and at maximum 20 ft [6 M] intervals in between.

## 3.4 HAZARDOUS LOCATIONS

- A. Use rigid steel conduit only, notwithstanding requirements otherwise specified in this or other sections of these specifications.
- B. Install UL approved sealing fittings that prevent passage of explosive vapors in hazardous areas equipped with explosion-proof lighting fixtures, switches, and receptacles, as required by the NEC.

## 3.5 WET OR DAMP LOCATIONS

- A. Unless otherwise shown, use rigid steel conduit.
- B. Provide sealing fittings to prevent passage of water vapor where conduits pass from warm to cold locations, i.e., refrigerated spaces, constant-temperature rooms, air-conditioned spaces, building exterior walls, roofs, or similar spaces.

C. Unless otherwise shown, use rigid steel or IMC conduit within 5 ft [1.5 M] of the exterior and below concrete building slabs in contact with soil, gravel, or vapor barriers. Conduit shall be half-lapped with 10 mil PVC tape before installation. After installation, completely recoat or retape any damaged areas of coating.

### 3.6 MOTORS AND VIBRATING EQUIPMENT

- A. Use flexible metal conduit for connections to motors and other electrical equipment subject to movement, vibration, misalignment, cramped quarters, or noise transmission.
- B. Use liquid-tight flexible metal conduit for installation in exterior locations, moisture or humidity laden atmosphere, corrosive atmosphere, water or spray wash-down operations, inside airstream of HVAC units, and locations subject to seepage or dripping of oil, grease, or water. Provide a green equipment grounding conductor with flexible metal conduit.

### 3.7 EXPANSION JOINTS

- A. Conduits 3 in [75 mm] and larger that are secured to the building structure on opposite sides of a building expansion joint require expansion and deflection couplings. Install the couplings in accordance with the manufacturer's recommendations.
- B. Provide conduits smaller than 3 in [75 mm] with junction boxes on both sides of the expansion joint. Connect conduits to junction boxes with sufficient slack of flexible conduit to produce 5 in [125 mm] vertical drop midway between the ends. Flexible conduit shall have a bonding jumper installed. In lieu of this flexible conduit, expansion and deflection couplings as specified above for conduits 15 in [375 mm] and larger are acceptable.
- C. Install expansion and deflection couplings where shown.

### 3.8 CONDUIT SUPPORTS, INSTALLATION

- A. Safe working load shall not exceed one-quarter of proof test load of fastening devices.
- B. Use pipe straps or individual conduit hangers for supporting individual conduits.
- C. Support multiple conduit runs with trapeze hangers. Use trapeze hangers that are designed to support a load equal to or greater than the sum of the weights of the conduits, wires, hanger itself, and 200 lbs [90 kg]. Attach each conduit with U-bolts or other approved fasteners.
- D. Support conduit independently of junction boxes, pull-boxes, fixtures, suspended ceiling T-bars, angle supports, and similar items.
- E. Fasteners and Supports in Solid Masonry and Concrete:
  - 1. Existing Construction:
    - a. Steel expansion anchors not less than 0.25 in [6 mm] bolt size and not less than 1.125 in [28 mm] embedment.

b. Power set fasteners not less than 0.25 in [6 mm] diameter with depth of penetration not less than 3 in [75 mm].

- c. Use vibration and shock-resistant anchors and fasteners for attaching to concrete ceilings.
- F. Hollow Masonry: Toggle bolts.
- G. Bolts supported only by plaster or gypsum wallboard are not acceptable.
- H. Metal Structures: Use machine screw fasteners or other devices specifically designed and approved for the application.
- I. Attachment by wood plugs, rawl plug, plastic, lead or soft metal anchors, or wood blocking and bolts supported only by plaster is prohibited.
- J. Chain, wire, or perforated strap shall not be used to support or fasten conduit.
- K. Spring steel type supports or fasteners are prohibited for all uses except horizontal and vertical supports/fasteners within walls.
- L. Vertical Supports: Vertical conduit runs shall have riser clamps and supports in accordance with the NEC and as shown. Provide supports for cable and wire with fittings that include internal wedges and retaining collars.

### 3.9 BOX INSTALLATION

- A. In addition to boxes shown, install additional boxes where needed to prevent damage to cables and wires during pulling-in operations.
- B. Remove only knockouts as required and plug unused openings. Use threaded plugs for cast metal boxes and snap-in metal covers for sheet metal boxes.
- C. Outlet boxes mounted back-to-back in the same wall are prohibited. A minimum 24 in [600 mm] center-to-center lateral spacing shall be maintained between boxes.
- D. Minimum size of outlet boxes for ground fault interrupter (GFI) receptacles is 4 in [100 mm] square x 2.125 in [55 mm] deep, with device covers for the wall material and thickness involved.
- E. Stencil or install phenolic nameplates on covers of the boxes identified on riser diagrams; for example "SIG-FA JB No. 1."
- F. On all branch circuit junction box covers, identify the circuits with black marker.

# END OF SECTION 26 05 33



# SECTION 26 27 26 WIRING DEVICES

### PART 1 - GENERAL

### 1.1 DESCRIPTION

This section specifies the furnishing, installation and connection of wiring devices.

### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements that are common to more than one section of Division 26.
- B. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits and outlets boxes.
- C. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW): Cables and wiring.
- D. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path to ground for possible ground fault currents.

### 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

## 1.4 SUBMITTALS

- A. In accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS, submit the following:
- B. Shop Drawings:
  - 1. Sufficient information, clearly presented, shall be included to determine compliance with drawings and specifications.
  - 2. Include electrical ratings, dimensions, mounting details, construction materials, grade and termination information.
- C. Manuals: Two weeks prior to final inspection, deliver four copies of the following to the COR: Technical data sheets and information for ordering replacement units.
- D. Certifications: Two weeks prior to final inspection, submit four copies of the following to the COR: Certification by the Contractor that the devices comply with the drawings and specifications, and have been properly installed, aligned, and tested.

## 1.5 APPLICABLE PUBLICATIONS

A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent

referenced. Publications are referenced in the text by basic designation only.

В.			Association	,
	70	 	National Electrica	al Code (NEC)

C.	National	Electrical	Manufacturers	Association	(NEMA):
	WD 1		General Colo	r Requirements	for Wiring Devices
	WD 6		Wiring Devic	es – Dimensiona	l Requirements

Ъ	Underwriter's	Tabanataniaa	T 70 0	/ TTT \ •
υ.	underwriter's	Laboratories,	inc.	(UL):

5	Surface Metal Raceways and Fittings
20	General-Use Snap Switches
231	Power Outlets
467	Grounding and Bonding Equipment
498	Attachment Plugs and Receptacles
943	Ground-Fault Circuit-Interrupters

## PART 2 - PRODUCTS

### 2.1 RECEPTACLES

- A. General: All receptacles shall be listed by Underwriters Laboratories, Inc., and conform to NEMA WD 6.
  - 1. Mounting straps shall be plated steel, with break-off plaster ears and shall include a self-grounding feature. Terminal screws shall be brass, brass plated or a copper alloy metal.
  - 2. Ground Fault Interrupter Duplex Receptacles: Shall be an integral unit, hospital-grade, suitable for mounting in a standard outlet box.
    - a. Ground fault interrupter shall be consist of a differential current transformer, solid state sensing circuitry and a circuit interrupter switch. Device shall have nominal sensitivity to ground leakage current of five milliamperes and shall function to interrupt the current supply for any value of ground leakage current above five milliamperes (+ or -1 milliamp) on the load side of the device. Device shall have a minimum nominal tripping time of 1/30th of a second.
    - b. Ground Fault Interrupter Duplex Receptacles (not hospital-grade) shall be the same as ground fault interrupter hospital-grade receptacles except for the "hospital-grade" listing.
- B. Weatherproof Receptacles: Shall consist of a duplex receptacle, mounted in box with a gasketed, weatherproof, cast metal cover plate and cap over each receptacle opening. The cap shall be permanently attached to the cover plate by a spring-hinged flap. The weatherproof integrity shall not be affected when heavy duty specification or hospital grade attachment plug caps are inserted.

# PART 3 - EXECUTION

## 3.1 INSTALLATION

A. Installation shall be in accordance with the NEC and as shown as on the drawings.

VA-528A7-12-706 WIRING DEVICES 26 27 26 - 2

B. Ground terminal of each receptacle shall be bonded to the outlet box with an approved green bonding jumper, and also connected to the green equipment grounding conductor.

- C. Coordinate with other work, including painting, electrical boxes and wiring installations, as necessary to interface installation of wiring devices with other work.
- D. Exact field locations of floors, walls, partitions, doors, windows, and equipment may vary from locations shown on the drawings. Prior to locating sleeves, boxes and chases for roughing-in of conduit and equipment, the Contractor shall coordinate exact field location of the above items with other trades.
- E. Install specific-use receptacles at heights shown on the drawings.
- F. Label device plates with a permanent adhesive label listing panel and circuit feeding the wiring device.
- G. Test wiring devices for damaged conductors, high circuit resistance, poor connections, inadequate fault current path, defective devices, or similar problems using a portable receptacle tester. Correct circuit conditions, remove malfunctioning units and replace with new, and retest as specified above.
- H. Test GFCI devices for tripping values specified in UL 1436 and UL 943.

END OF SECTION 26 27 26

VA-528A7-12-706 WIRING DEVICES 26 27 26 - 3



# SECTION 26 29 11 MOTOR STARTERS

### PART 1 - GENERAL

### 1.1 DESCRIPTION

All motor starters and variable speed motor controllers, including installation and connection (whether furnished with the equipment specified in other Divisions or otherwise), shall meet these specifications.

### 1.2 RELATED WORK

- A. Other sections which specify motor driven equipment, except elevator motor controllers.
- B. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one Section of Division 26.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS:
  Requirements for personnel safety and to provide a low impedance path
  for possible ground fault currents.

#### 1.3 OUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

### 1.4 SUBMITTALS

- A. Submit in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS:
- B. Shop Drawings:
  - 1. Sufficient information, clearly presented, shall be included to determine compliance with drawings and specifications.
  - 2. Include electrical ratings, dimensions, weights, mounting details, materials, running over current protection, size of enclosure, over current protection, wiring diagrams, starting characteristics, interlocking and accessories.

### C. Manuals:

- 1. Submit, simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals, including technical data sheets, wiring diagrams and information for ordering replacement parts.
  - a. Wiring diagrams shall have their terminals identified to facilitate installation, maintenance and operation.
  - b. Wiring diagrams shall indicate internal wiring for each item of equipment and interconnections between the items of equipment.
  - c. Elementary schematic diagrams shall be provided for clarity of operation.
- 2. Two weeks prior to the project final inspection, submit four copies of the final updated maintenance and operating manual to the COR.

D. Certification: Two weeks prior to final inspection, unless otherwise noted, submit four copies of the following certifications to the COR:

- 1. Certification that the equipment has been properly installed, adjusted, and tested.
- 2. Certification by the manufacturer that medium voltage motor controller(s) conforms to the requirements of the drawings and specifications. This certification must be furnished to the COR prior to shipping the controller(s) to the job site.

### 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by basic designation only.

- D. National Fire Protection Association (NFPA): 70......National Electrical Code (NEC)
- E. Underwriters Laboratories Inc. (UL): 508......Industrial Control Equipment

## PART 2 - PRODUCTS

## 2.1 MOTOR STARTERS, GENERAL

- A. Shall be in accordance with the requirements of the IEEE, NEC, NEMA (ICS 1, ICS 1.1, ICS 2, ICS 6, ICS 7 and ICS 7.1) and UL.
- B. Shall have the following features:
  - 1. Separately enclosed unless part of another assembly.
  - Circuit breakers and safety switches within the motor controller enclosures shall have external operating handles with lock-open padlocking provisions and shall indicate the ON and OFF positions.
  - 3. Motor control circuits:
    - a. Shall operate at not more than 120 volts.

- b. Shall be grounded except as follows:
  - 1) Where isolated control circuits are shown.
  - 2) Where manufacturers of equipment assemblies recommend that the control circuits be isolated.
- c. Incorporate a separate, heavy duty, control transformer within each motor controller enclosure to provide the control voltage for each motor operating over 120 volts.
- d. Incorporate over current protection for both primary and secondary windings of the control power transformers in accordance with the NEC.
- 4. Overload current protective devices:
  - a. Overload relay (thermal or induction type).
  - b. Overload relay (solid state type).
    - c. One for each pole.
    - d. Manual reset on the door of each motor controller enclosure.
    - e. Correctly sized for the associated motor's rated full load current.
    - f. Check every motor controller after installation and verify that correct sizes of protective devices have been installed.
    - g. Deliver four copies of a summarized list to the COR, which indicates and adequately identifies every motor controller installed. Include the catalog numbers for the correct sizes of protective devices for the motor controllers.
- 5. Hand-Off-Automatic (H-O-A) switch is required unless specifically stated on the drawings as not required for a particular starter. H-O-A switch is not required for manual motor starters.
- 6. Incorporate into each control circuit a 120-volt, solid state time delay relay (ON delay), minimum adjustable range from 0.3 to 10 minutes, with transient protection. Time delay relay is not required where H-O-A switch is not required.
- 7. Unless noted otherwise, equip with not less than two normally open and two normally closed auxiliary contacts. Provide green run pilot lights and H-O-A control devices as indicated, operable at front of enclosure without opening enclosure. Push buttons, selector switches, pilot lights, etc., shall be interchangeable.
- 8. Enclosures:
  - a. Shall be the NEMA types shown on the drawings for the motor controllers and shall be the NEMA types which are the most suitable for the environmental conditions where the motor controllers are being installed.
  - b. Doors mechanically interlocked to prevent opening unless the breaker or switch within the enclosure is open. Provision for padlock must be provided.
  - c. Enclosures shall be primed and finish coated at the factory with the manufacturer's prime coat and standard finish.
- C. Motor controllers incorporated with equipment assemblies shall also be designed for the specific requirements of the assemblies.
- D. Additional requirements for specific motor controllers, as indicated in other sections, shall also apply.
- E. Provide a disconnecting means or safety switch near and within sight of each motor. Provide all wiring and conduit required to facilitate a complete installation.

## 2.2 MANUAL MOTOR STARTERS

A. Shall be in accordance with applicable requirements of 2.1 above.

- B. Manual motor starters.
  - 1. Starters shall be general-purpose Class A, manually operated type with full voltage controller for induction motors, rated in horsepower.
  - 2. Units shall include overload protection, red pilot light and toggle operator.
- C. Fractional horsepower manual motor starters.
  - 1. Starters shall be general-purpose Class A, manually operated with full voltage controller for fractional horsepower induction motors.
  - 2. Units shall include thermal overload protection, red pilot light and toggle operator.
- D. Motor starting switches.
  - 1. Switches shall be general-purpose Class A, manually operated type with full voltage controller for fractional horsepower induction motors.
  - 2. Units shall include thermal overload protection, red pilot light and toggle operator.

### 2.3 VARIABLE SPEED MOTOR CONTROLLERS

- A. Shall be in accordance with applicable portions of 2.1 above.
- B. Shall be solid state, micro processor-based with adjustable frequency and voltage, three phase output capable of driving standard NEMA B design, three phase alternating current induction motors at full rated speed. The drives shall utilize a full wave bridge design incorporating diode rectifier circuitry with pulse width modulation (PWM). Other control techniques are not acceptable. Silicon controlled rectifiers (SCR) shall not be used in the rectifying circuitry. The drives shall be designed to be used on variable torque loads and shall be capable of providing sufficient torque to allow the motor to break away from rest upon first application of power.
- C. Unit shall be capable of operating within voltage parameters of plus 10 to minus 10 percent of line voltage, and be suitably rated for the full load amps of the maximum watts (HP) within its class.
- D. Operating and Design Conditions:

Elevation: 400 feet AMSL

Elevation: 400 feet AMSL Temperatures: Maximum +90°F, Minimum -10°F

Relative Humidity: 95%

- E. Controllers shall have the following features:
  - 1. Isolated power for control circuits.
  - 2. Manually re-settable motor overload protection for each phase.
  - 3. Adjustable current limiting circuitry to provide soft motor starting. Maximum starting current shall not exceed 200 percent of motor full load current.
  - 4. Independent acceleration and deceleration time adjustment, manually adjustable from 2 to 30 seconds. (Set timers to the equipment manufacturer's recommended time in the above range.)
  - 5. Provide 4 to 20 ma current follower circuitry for interface with mechanical sensor devices.
  - 6. Automatic frequency adjustment from 20 Hz to 60 Hz.
  - 7. Provide circuitry to initiate an orderly shutdown when any of the conditions listed below occur. The controller shall not be damaged by any of these electrical disturbances and shall automatically restart when the conditions are corrected. The drive shall be able to restart

into a rotating motor operating in either the forward or reverse direction and matching that frequency.

- a. Incorrect phase sequence.
- b. Single phasing.
- c. Over voltage in excess of 10 percent.
- d. Under voltage in excess of 10 percent.
- e. Running over current above 110 percent (shall not automatically reset for this condition.)
- f. Instantaneous overcurrent above 150 percent (shall not automatically reset for this condition).
- g. Surge voltage in excess of 1000 volts.
- h. Short duration power outages of 12 cycles or less (i.e., distribution line switching, generator testing, and automatic transfer switch operations.)
- 8. Automatic Reset/Restart: Attempt three restarts after drive fault or on return of power after an interruption and before shutting down for manual reset or fault correction; adjustable delay time between restart attempts.
- 9. Power-Interruption Protection: To prevent motor from re-energizing after a power interruption until motor has stopped, unless "Bidirectional Autospeed Search" feature is available and engaged.
- 10. Bidirectional Autospeed Search: Capable of starting VFC into rotating loads spinning in either direction and returning motor to set speed in proper direction, without causing damage to drive, motor, or load.
- F. Minimum efficiency shall be 95 percent at 100 percent speed and 85percent at 50 percent speed.
- G. The displacement power factor of the controller shall not be less than 95 percent under any speed or load condition.
- H. Controllers shall include a door interlocked fused safety disconnect switch or door interlocked circuit breaker switch which will disconnect all input power.
- I. Controller shall include a 3% line reactor, and RFI/EMI filter.
- J. The following accessories are to be door mounted:
  - 1. AC Power on light.
  - 2. Ammeter (RMS motor current).
  - 3. HAND-OFF-AUTOMATIC switch.
  - 4. Manual speed control in HAND mode.
  - 5. System protection lights indicating that the system has shutdown and will not automatically restart.
  - 6. System protection light indicating that the system has shutdown but will restart when conditions return to normal.
  - 7. Manual variable speed controller by-pass switch.
  - 8. Diagnostic shutdown indicator lights for each shutdown condition.
  - 9. Provide two N.O. and two N.C. dry contacts rated 120 volts, 10 amperes, 60 HZ for remote indication of the following:
    - a. System shutdown with auto restart.
    - b. System shutdown without auto restart.

- c. System running.
- 10. Incorporate into each control circuit a 120-volt, time delay relay (ON delay), adjustable from 0.3-10 minutes, with transient protection. Provide transformer/s for the control circuit/s.
- 11. Controller shall not add any current or voltage transients to the input AC power distribution system nor shall transients from other devices on the AC power distribution system affect the controller. Controllers shall be protected to comply with IEEE C37.90.1 and UL-508. Line noise and harmonic voltage distortion shall not exceed the values allowed by IEEE 519.
- K. Hardware and software to enable the BAS to monitor, control, and display controller status and alarms.
- L. Network Communications Ports: Ethernet and RS-485.
- M. Embedded BAS Protocols for Network Communications: As specified in Division 22.
- N. Bypass Operation: Manually transfers motor between power converter output and bypass circuit, manually, automatically, or both. Unit is capable of stable operation (starting, stopping, and running) with motor completely disconnected from power converter. Transfer between power converter and bypass contactor and retransfer shall only be allowed with the motor at zero speed.
- O. Bypass Controller: Provide contactor-style bypass, arranged to isolate the power converter input and output and permit safe testing of the power converter, both energized and de-energized, while motor is operating in bypass mode. Motor overload protection shall be provided.
  - 1. Bypass Contactor: Load-break NEMA-rated contactor.
  - 2. Input and Output Isolating Contactors: Non-load-break, NEMA-rated contactors.
  - 3. Isolating Switch: Non-load-break switch arranged to isolate power converter and permit safe troubleshooting and testing of the power converter, both energized and de-energized, while motor is operating in bypass mode; pad-lockable, door-mounted handle mechanism.

## PART 3 - EXECUTION

# 3.1 INSTALLATION

- A. Install motor control equipment in accordance with manufacturer's recommendations, the NEC, NEMA and as shown on the drawings.
- B. Furnish and install heater elements in motor starters and to match the installed motor characteristics. Submit a list of all motors listing motor nameplate rating and heater element installed.
- C. Motor Data: Provide neatly-typed label inside each motor starter enclosure door identifying motor served, nameplate horsepower, full load amperes, code letter, service factor, voltage/phase rating and heater element installed.
- D. Connect hand-off auto selector switches so that automatic control only is by-passed in "manual" position and any safety controls are not by-passed.
- E. Examine control diagrams indicated before ordering motor controllers. Should conflicting data exist in specifications, drawings and diagrams, request corrected data prior to placing orders.

VA-528A7-12-706 MOTOR STARTERS 26 29 11 - 6

### 3.2 ADJUSTING

A. Set field-adjustable switches, auxiliary relays, time-delay relays, timers, and overload-relay pickup and trip ranges.

- B. Adjust overload-relay heaters or settings if power factor correction capacitors are connected to the load side of the overload relays.
- C. Adjust trip settings of MCPs and thermal-magnetic circuit breakers with adjustable instantaneous trip elements. Initially adjust at six times the motor nameplate full-load ampere ratings and attempt to start motors several times, allowing for motor cooldown between starts. If tripping occurs on motor inrush, adjust settings in increments until motors start without tripping. Do not exceed eight times the motor full-load amperes (or 11 times for NEMA Premium Efficient motors if required). Where these maximum settings do not allow starting of a motor, notify COR before increasing settings.

#### 3.3 ACCEPTANCE CHECKS AND TESTS

- A. Perform in accordance with the manufacturer's recommendations. Include the following visual and mechanical inspections and electrical tests:
  - 1. Visual and Mechanical Inspection
    - a. Compare equipment nameplate data with specifications and approved shop drawings.
    - b. Inspect physical, electrical, and mechanical condition.
    - c. Inspect contactors.
    - d. Clean motor starters and variable speed motor controllers.
    - e. Verify overload element ratings are correct for their applications.
    - f. If motor-running protection is provided by fuses, verify correct fuse rating.
    - g. Verify tightness of accessible bolted electrical connections by calibrated torque-wrench method in accordance with manufacturer's published data.
  - 2. Variable speed motor controllers:
    - a. Final programming and connections to variable speed motor controllers shall be by a factory-trained technician. Set all programmable functions of the variable speed motor controllers to meet the requirements and conditions of use.
    - b. Test all control and safety features of the variable frequency drive.

## 3.4 FOLLOW-UP VERIFICATION

Upon completion of acceptance checks, settings, and tests, the Contractor shall show by demonstration in service that the motor starters and variable speed motor controllers are in good operating condition and properly performing the intended functions.

## 3.5 SPARE PARTS

Two weeks prior to the final inspection, provide one complete set of spare fuses (including heater elements) for each starter/controller installed on this project.

END OF SECTION 26 29 11

VA-528A7-12-706 MOTOR STARTERS 26 29 11 - 7



# SECTION 26 29 21 DISCONNECT SWITCHES

### PART 1 - GENERAL

### 1.1 DESCRIPTION

This section specifies the furnishing, installation, and connection of low voltage disconnect switches.

### 1.2 RELATED WORK

- A. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements and items that are common to more than one section of Division 26.
- B. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES 600 VOLTS AND BELOW: Cables and wiring.
- C. Section 26 05 26, GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS: Requirements for personnel safety and to provide a low impedance path for possible ground faults.
- D. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits for cables and wiring.
- E. Section 26 29 11, LOW-VOLTAGE MOTOR STARTERS: Motor rated toggle switches.

### 1.3 QUALITY ASSURANCE

Refer to Paragraph, QUALIFICATIONS, in Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

## 1.4 SUBMITTALS

- A. Submit in accordance with Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.
- B. Shop Drawings:
  - 1. Clearly present sufficient information to determine compliance with drawings and specifications.
  - 2. Include electrical ratings, dimensions, mounting details, materials, enclosure types, and fuse types and classes.
  - 3. Show the specific switch and fuse proposed for each specific piece of equipment or circuit.

## C. Manuals:

- Provide complete maintenance and operating manuals for disconnect switches, including technical data sheets, wiring diagrams, and information for ordering replacement parts.
   Deliver four copies to the COR two weeks prior to final inspection.
- 2. Terminals on wiring diagrams shall be identified to facilitate maintenance and operation.
- 3. Wiring diagrams shall indicate internal wiring and any interlocking.

D. Certifications: Two weeks prior to the final inspection, submit four copies of the following certifications to the COR:

- 1. Certification by the manufacturer that the materials conform to the requirements of the drawings and specifications.
- 2. Certification by the contractor that the materials have been properly installed, connected, and tested.

## 1.5 APPLICABLE PUBLICATIONS

- A. Publications listed below (including amendments, addenda, revisions, supplements, and errata) form a part of this specification to the extent referenced. Publications are referenced in the text by designation only.
- B. National Electrical Manufacturers Association (NEMA):

FU I-07	Low Voltage Cartridge Fuses
KS I-06	Enclosed and Miscellaneous Distribution Equipment Switches
	(600 Volts Maximum)

- C. National Fire Protection Association (NFPA):
  70-08......National Electrical Code (NEC)
- D. Underwriters Laboratories, Inc. (UL):

98-04	Enclosed and Dead-Front Switches
248-00	Low Voltage Fuses
977-94	Fused Power-Circuit Devices

## PART 2 - PRODUCTS

## 2.1 LOW VOLTAGE FUSIBLE SWITCHES RATED 600 AMPERES AND LESS

- A. In accordance with UL 98, NEMA KS1, and NEC.
- B. Shall have NEMA classification General Duty (GD) for 240 V switches and NEMA classification Heavy Duty (HD) for 480 V switches.
- C. Shall be HP rated.
- D. Shall have the following features:
  - 1. Switch mechanism shall be the quick-make, quick-break type.
  - 2. Copper blades, visible in the OFF position.
  - 3. An arc chute for each pole.
  - 4. External operating handle shall indicate ON and OFF position and have lock-open padlocking provisions.
  - 5. Mechanical interlock shall permit opening of the door only when the switch is in the OFF position, defeatable to permit inspection.
  - 6. Fuse holders for the sizes and types of fuses specified.
  - 7. Solid neutral for each switch being installed in a circuit which includes a neutral conductor.
  - 8. Ground lugs for each ground conductor.
  - 9. Enclosures:
    - a. Shall be the NEMA types shown on the drawings for the switches.

b. Where the types of switch enclosures are not shown, they shall be the NEMA types most suitable for the ambient environmental conditions. Unless otherwise indicated on the plans, all outdoor switches shall be NEMA 3R.

c. Shall be finished with manufacturer's standard gray baked enamel paint over pretreated steel (for the type of enclosure required).

## 2.2 LOW VOLTAGE UNFUSED SWITCHES RATED 600 AMPERES AND LESS

Shall be the same as Low Voltage Fusible Switches Rated 600 Amperes and Less, but without provisions for fuses.

### 2.3 LOW VOLTAGE FUSIBLE SWITCHES RATED OVER 600 AMPERES TO 1200 AMPERES

Shall be the same as Low Voltage Fusible Switches Rated 600 Amperes and Less, except for the minimum duty rating which shall be NEMA classification Heavy Duty (HD). These switches shall also be HP rated.

## 2.4 MOTOR RATED TOGGLE SWITCHES

Refer to Section 26 29 11, LOW-VOLTAGE MOTOR STARTERS.

### 2.5 LOW VOLTAGE CARTRIDGE FUSES

- A. In accordance with NEMA FU1.
- B. Motor Branch Circuits: Class RK1, time delay.
- C. Other Branch Circuits: Class RK1, time delay.
- D. Control Circuits: Class CC, time delay.

## PART 3 - EXECUTION

## 3.1 INSTALLATION

- A. Install disconnect switches in accordance with the NEC and as shown on the drawings.
- B. Fusible disconnect switches shall be furnished complete with fuses. Arrange fuses such that rating information is readable without removing the fuse.

## 3.2 SPARE PARTS

Two weeks prior to the final inspection, furnish one complete set of spare fuses for each fusible disconnect switch installed on the project. Deliver the spare fuses to the COR.

# END OF SECTION 26 29 21



# SECTION 28 31 00 FIRE DETECTION AND ALARM

### PART 1 - GENERAL

### 1.1 DESCRIPTION

- A. This section of the specifications includes the furnishing, installation, and connection of the fire alarm equipment to the existing Simplex fire alarm system. It shall include, but not be limited to, alarm initiating devices, alarm notification appliances, control units, fire safety control devices, annunciators, power supplies, and wiring as shown on the drawings and specified.
- B. Fire alarm systems shall comply with requirements of NFPA 72 unless variations to NFPA 72 are specifically identified within these contract documents by the following notation: "variation". The design, system layout, document submittal preparation, and supervision of installation and testing shall be provided by a technician that is certified NICET level III or a registered fire protection engineer. The NICET certified technician shall be on site for the supervision and testing of the system. Factory engineers from the equipment manufacturer, thoroughly familiar and knowledgeable with all equipment utilized, shall provide additional technical support at the site as required by the Contracting Officer or his authorized representative. Installers shall have a minimum of two years experience installing fire alarm systems.
- C. Alarm signals (by device), supervisory signals (by device) and system trouble signals (by device not reporting) shall be distinctly transmitted to the main fire alarm system control unit located in the security office.

## 1.2 SCOPE

- A. Extend existing fire alarm system, wiring, devices and equipment as shown on Drawings.
- B. New fire alarm system wiring, devices and equipment shall be installed in accordance with the specifications and drawings. Device location and wiring runs shown on the drawings are for reference only unless specifically dimensioned. Actual locations shall be in accordance with NFPA 72 and this specification. Fire Alarm system extension scope includes work to Building 16. Contractor shall provide interface for fan shutdown as required by NFPA 72 and indicated on Drawings.

### 1.3 RELATED WORK

- A. Section 01 00 00, GENERAL REQUIREMENTS: Restoration of existing surfaces.
- B. Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES: Procedures for submittals.
- C. Section 07 84 00, FIRESTOPPING: Fire proofing wall penetrations.

D. Section 09 91 00, PAINTING: Painting for equipment and existing surfaces.

- E. Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS: General electrical requirements for items which are common to other Division 26 sections.
- F. Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS: Conduits and boxes for cables/wiring.
- G. Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW: Cables/wiring.

#### 1.4 SUBMITTALS

A. General: Submit 4 copies and 1 reproducible in accordance with Section 01 33 23, SHOP DRAWINGS, PRODUCT DATA, AND SAMPLES, and Section 26 05 11, REQUIREMENTS FOR ELECTRICAL INSTALLATIONS.

## B. Manuals:

- Submit simultaneously with the shop drawings, companion copies of complete maintenance and operating manuals including technical data sheets for all items used in the system extension, power requirements, device wiring diagrams, dimensions, and information for ordering replacement parts.
  - a. Wiring diagrams shall have their terminals identified to facilitate installation, operation, expansion and maintenance.
  - b. Wiring diagrams shall indicate internal wiring for each item of equipment and the interconnections between the items of equipment.
  - c. Include complete listing of all software used and installation and operation instructions including the input/output matrix chart.
  - d. Provide a clear and concise description of operation that gives, in detail, the information required to properly operate, inspect, test and maintain the equipment and system.
     Provide all manufacturer's installation limitations including but not limited to circuit length limitations.
  - e. Include information indicating who will provide emergency service and perform post contract maintenance.
  - f. Provide a replacement parts list with current prices. Include a list of recommended spare parts, tools, and instruments for testing and maintenance purposes.

## C. Certifications:

- Together with the shop drawing submittal, submit the technician's NICET level III fire alarm
  certification as well as certification from the control unit manufacturer that the proposed
  performer of contract maintenance is an authorized representative of the major equipment
  manufacturer. Include in the certification the names and addresses of the proposed
  supervisor of installation and the proposed performer of contract maintenance. Also include
  the name and title of the manufacturer's representative who makes the certification.
- 2. Together with the shop drawing submittal, submit a certification from either the control unit manufacturer or the manufacturer of each component (e.g., smoke detector) that the components being furnished are compatible with the control unit.

3. Together with the shop drawing submittal, submit a certification from the major equipment manufacturer that the wiring and connection diagrams meet this specification, UL and NFPA 72 requirements.

#### 1.5 WARRANTY

All work performed and all material and equipment furnished under this contract shall be free from defects and shall remain so for a period of five (5) years from the date of acceptance of the entire installation by the Contracting Officer.

### 1.6 GUARANTY PERIOD SERVICES

- A. Complete inspection, testing, maintenance and repair service for the fire alarm system shall be provided by a factory trained authorized representative of the manufacturer of the major equipment for a period of five years from the date of acceptance of the entire installation by the Contracting Officer.
- B. Contractor shall provide all necessary test equipment, parts and labor to perform required inspection, testing, maintenance and repair.
- C. All inspection, testing, maintenance and permanent records required by NFPA 72, and recommended by the equipment manufacturer shall be provided by the contractor. Work shall include operation of sprinkler system alarm and supervisory devices as well as all reused existing equipment connected to the fire alarm system. It shall include all interfaced equipment including but not limited to elevators, HVAC shutdown, and extinguishing systems.
- D. Maintenance and testing shall be performed in accordance with NFPA 72. A computerized preventive maintenance schedule shall be provided and shall describe the protocol for preventive maintenance of equipment. The schedule shall include a systematic examination, adjustment and cleaning of all equipment.
- E. Non-included Work: Repair service shall not include the performance of any work due to improper use, accidents, or negligence for which the contractor is not responsible.
- F. Service and emergency personnel shall report to the Engineering Office or their authorized representative upon arrival at the hospital and again upon the completion of the required work. A copy of the work ticket containing a complete description of the work performed and parts replaced shall be provided to the VA Contracting Officer or his authorized representative.

## G. Emergency Service:

1. Warranty Period Service: Service other than the preventative maintenance, inspection, and testing required by NFPA 72 shall be considered emergency call-back service and covered under the warranty of the installation during the first year of the warranty period, unless the required service is a result of abuse or misuse by the Government. Written notification shall not be required for emergency warranty period service and the contractor shall respond as outlined in the following sections on Normal and Overtime Emergency Call-Back Service. Warranty period service can be required during normal or overtime emergency call-back

- service time periods at the discretion of the Contracting Officer or his authorized representative.
- 2. Normal and overtime emergency call-back service shall consist of an on-site response within two hours of notification of a system trouble.
- 3. Normal emergency call-back service times are between the hours of 7:30 a.m. and 4:00 p.m., Monday through Friday, exclusive of federal holidays. Service performed during all other times shall be considered to be overtime emergency call-back service. The cost of all normal emergency call-back service for years 2 through 5 shall be included in the cost of this contract.
- 4. Overtime emergency call-back service shall be provided for the system when requested by the Government. The cost of the first 40 manhours per year of overtime call-back service during years 2 through 5 of this contract shall be provided under this contract. Payment for overtime emergency call-back service in excess of the 40 man hours per year requirement will be handled through separate purchase orders. The method of calculating overtime emergency call-back hours is based on actual time spent on site and does not include travel time.
- H. The contractor shall maintain a log at each fire alarm control unit. The log shall list the date and time of all examinations and trouble calls, condition of the system, and name of the technician. Each trouble call shall be fully described, including the nature of the trouble, necessary correction performed, and parts replaced.
- I. In the event that VA modifies the fire alarm system post-Acceptance but during the five year Guaranty Period Service period, Contractor shall be required to verify that the system, as newly modified or added, is consistent with the manufacturer's requirements; any verification performed will be equitably adjusted under the Changes clause. The post-Acceptance modification or addition to the fire alarm system shall not void the continuing requirements under this contract set forth in the Guarantee Period Service provision for the fire alarm system as modified or added. The contract will be equitably adjusted under the Changes clause for such additional performance.

## 1.7 APPLICABLE PUBLICATIONS

- A. The publications listed below (including amendments, addenda, revisions, supplements and errata) form a part of this specification to the extent referenced. The publications are referenced in text by the basic designation only.
- B. National Fire Protection Association (NFPA):

72-2002 ...... National Fire Alarm Code.

90A-2002 ...... Installation of Air Conditioning and Ventilating Systems.

101-2003 ...... Life Safety Code

- C. Underwriters Laboratories, Inc. (UL): 2000-2000......Fire Protection Equipment Directory
- D. Factory Mutual Research Corp (FM): Approval Guide, 2005 Edition

- E. American National Standards Institute (ANSI): S3.41-1996......Audible Emergency Evacuation Signal
- F. International Code Council, International Building Code (IBC) 2003 Edition

## PART 2 - PRODUCTS

## 2.1 EQUIPMENT AND MATERIALS, GENERAL

A. All equipment and components shall be new and the manufacturer's current model. All equipment shall be tested and listed by Underwriters Laboratories, Inc. or Factory Mutual Research Corporation for use as part of a fire alarm system. The authorized representative of the manufacturer of the major equipment shall certify that the installation complies with all manufacturer's requirements and that satisfactory total system operation has been achieved.

### 2.2 CONDUIT, BOXES, AND WIRE

- A. Conduit shall be in accordance with Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS and as follows:
  - 1. All new and reused conduit shall be installed in accordance with NFPA 70.
  - 2. Conduit fill shall not exceed 40 percent of interior cross sectional area.
  - 3. All new conduit shall be 19 mm (3/4 inch) minimum.

## B. Wire:

- 1. All existing wiring shall be removed and new wiring installed in a conduit or raceway.
- 2. Wiring shall be in accordance with NEC article 760, Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW), and as recommended by the manufacturer of the fire alarm system. All wires shall be color coded. Number and size of conductors shall be as recommended by the fire alarm system manufacturer, but not less than 18 AWG for initiating device circuits and 14 AWG for notification device circuits.
- 3. Addressable circuits and wiring used for the multiplex communication loop shall be twisted and shielded unless specifically excepted by the fire alarm equipment manufacturer in writing.
- 4. Any fire alarm system wiring that extends outside of a building shall have additional power surge protection to protect equipment from physical damage and false signals due to lightning, voltage and current induced transients. Protection devices shall be shown on the submittal drawings and shall be UL listed or in accordance with written manufacturer's requirements.
- 5. All wire or cable used in underground conduits including those in concrete shall be listed for wet locations.
- C. Terminal Boxes, Junction Boxes, and Cabinets:
  - 1. Shall be galvanized steel in accordance with UL requirements.
  - 2. All new and reused boxes shall be sized and installed in accordance with NFPA 70.
  - 3. New and existing covers shall be repainted red in accordance with Section 09 91 00, PAINTING and shall be identified with white markings as "FA" for junction boxes and as

- "FIRE ALARM SYSTEM" for cabinets and terminal boxes. Lettering shall be a minimum of 19 mm (3/4 inch) high.
- 4. Terminal boxes and cabinets shall have a volume 50 percent greater than required by the NFPA 70. Minimum sized wire shall be considered as 14 AWG for calculation purposes.
- 5. Terminal boxes and cabinets shall have identified pressure type terminal strips and shall be located at the base of each riser. Terminal strips shall be labeled as specified or as approved by the COR.

#### 2.3 EXISTING FIRE ALARM CONTROL UNIT

#### A. General:

1. Extend existing fire alarm control panel as required to include all devices show on Contract Documents.

#### 2.4 SUPERVISORY DEVICES

### A. Duct Smoke Detectors:

- Duct smoke detectors shall be provided and connected by way of an address reporting
  interface device. Detectors shall be provided with an approved duct housing mounted
  exterior to the duct, and shall have perforated sampling tubes extending across the full
  width of the duct (wall to wall). Detector placement shall be such that there is uniform
  airflow in the cross section of the duct.
- 2. Interlocking with fans shall be provided in accordance with NFPA 90A and as specified hereinafter under Part 3.2, "TYPICAL OPERATION".
- 3. Provide remote indicator lamps, key test stations and identification nameplates (e.g. "DUCT SMOKE DETECTOR AHU-X") for all duct detectors. Locate key test stations in plain view on walls or ceilings so that they can be observed and operated from a normal standing position.

## 2.5 INSTRUCTION CHART:

Provide a typeset printed or typewritten instruction card mounted behind a Lexan plastic or glass cover in a stainless steel or aluminum frame with a backplate. Install the frame in a conspicuous location observable from each control unit where operations are performed. The card shall show those steps to be taken by an operator when a signal is received under all conditions, normal, alarm, supervisory, and trouble. Provide an additional copy with the binder for the input output matrix for the sequence of operation. The instructions shall be approved by the COR before being posted.

# PART 3 - EXECUTION

## 3.1 INSTALLATION:

A. Installation shall be in accordance with NFPA 70, 72, 90A, and 101 as shown on the drawings, and as recommended by the major equipment manufacturer. Fire alarm wiring shall be installed in conduit. All conduit and wire shall be installed in accordance with Section 26 05 33, RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS, Section 26 05 21, LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES (600 VOLTS AND BELOW), and all penetrations of smoke and fire barriers shall be protected as required by Section 07 84 00, FIRESTOPPING.

B. All new conduits, junction boxes, conduit supports and hangers shall be concealed in finished areas and may be exposed in unfinished areas. All existing accessible fire alarm conduit not reused shall be removed.

C. All new or reused exposed conduit shall be painted in accordance with Section 09 91 00, PAINTING to match surrounding finished areas and red in unfinished areas.

#### 3.2 TYPICAL OPERATION

A. Operation of duct smoke detectors shall cause a system supervisory condition and shut down the ventilation system and close the associated smoke dampers as appropriate.

### 3.3 TESTS

- A. Provide the service of a NICET level III, competent, factory-trained engineer or technician authorized by the manufacturer of the fire alarm equipment to technically supervise and participate during all of the adjustments and tests for the system. Make all adjustments and tests in the presence of the COR.
- B. When the systems have been completed and prior to the scheduling of the final inspection, furnish testing equipment and perform the following tests in the presence of the COR. When any defects are detected, make repairs or install replacement components, and repeat the tests until such time that the complete fire alarm systems meets all contract requirements. After the system has passed the initial test and been approved by the COR, the contractor may request a final inspection.
  - 1. Before energizing the cables and wires, check for correct connections and test for short circuits, ground faults, continuity, and insulation.
  - 2. Test the insulation on all installed cable and wiring by standard methods as recommended by the equipment manufacturer.
  - 3. Open each alarm initiating and notification circuit to see if trouble signal actuates.
  - 4. Ground each alarm initiation and notification circuit and verify response of trouble signals.

## 3.4 FINAL INSPECTION AND ACCEPTANCE

- A. Prior to final acceptance a minimum 30 day "burn-in" period shall be provided. The purpose shall be to allow equipment to stabilize and potential installation and software problems and equipment malfunctions to be identified and corrected. During this diagnostic period, all system operations and malfunctions shall be recorded. Final acceptance will be made upon successful completion of the "burn-in" period and where the last 14 days is without a system or equipment malfunction.
- B. At the final inspection a factory trained representative of the manufacturer of the major equipment shall repeat the tests in Article 3.3 TESTS and those required by NFPA 72. In addition the representative shall demonstrate that the systems function properly in every respect. The demonstration shall be made in the presence of a VA representative.

END OF SECTION 28 31 00